TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	BR-NH-4(016)	10A

TRAFFIC CONTROL QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY
	705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	EACH	2
(2)	705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	L.F.	460
(2)	711-04.21	CONCRETE BARRIER DELINEATION ENHANCEMENT	L.F.	1240
	712-01	TRAFFIC CONTROL	LS	1
	712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	L.F.	950
	712-05.01	WARNING LIGHTS (TYPE A)	EACH	4
	712-05.03	WARNING LIGHTS (TYPE C)	EACH	23
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	46
	712-06	SIGNS (CONSTRUCTION)	S.F.	155
(1)	712-06.01	VERTICAL PANELS	S.F.	124
	712-07.03	TEMPORARY BARRICADES (TYPE III)	L.F.	24
	716-01.05	TEMPORARY RAISED PAVEMENT MARKER	EACH	45
	713-16.01	CHANGEABLE MESSAGE SIGN UNIT	EACH	4
	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	2
	716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	L.F.	1750

(1) FOR VERTICAL PANELS VP-1R = 62 SF AND VP-1R = 62 SF
(2) LENGTH INDICATED IS GROSS LENGTH TO BE DELINEATED, NOT PRODUCT LENGTH

SIGN QUANTITIES

DESCRIPTION	UNIT	QUANTITY	ITEM NO. 712-06 (S.F.)	SIZE	M.U.T.C.D. NO.	REMARKS
END ROAD WORK	S.F.	2	9	36" x 18"	G20-2	
ROAD CLOSED	S.F.	2	20	48" x 30"	R11-2	
ROAD WORK 1/2 MILE	S.F.	2	18	36" x 36"	W20-1	
ROAD WORK 1500 FT	S.F.	2	18	36" x 36"	W20-1	
ROAD WORK 1000 FT	S.F.	2	18	36" x 36"	W20-1	
ROAD WORK 500 FT	S.F.	2	18	36" x 36"	W20-1	
ROAD NARROWS	S.F.	2	18	36" x 36"	W5-1	
FLAGGER - SYMBOL	S.F.	2	18	36" x 36"	W20-7	
BE PREPARED TO STOP	S.F.	2	18	36" x 36"	W3-4	
			155			

SEALED BY



03/11/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL QUANTITIES

10-MAR-2014 14:13
C:\Projects\Polk\Project Design\010A.sht