TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	PHSIP-21(19)	2B

PERMANENT SIGNS

	DESCRIPTION	M.U.T.C.D. NO.	MATERIAL	THICKNESS	UNIT	QUANTITY	SIZE	ITEM NO. 713-13.02 (S.F.)	ITEM NO. 713-13.03 (S.F.)	POST TYPE	POST LENGTH (FT.)	POST WEIGHT (LBS/FT)	ITEM NO. 713-11.02 (LB.)	ITEM NO. 713-01.01 (C.Y.)	ITEM NO. 713-01.02 (LB.)	REMARKS
1	REDUCED SCHOOL SPEED LIMIT AHEAD	S4-5	ALUMINUM	0.100"	S.F.	2	36"X36"		18.00	P8	13.00	2.164	57	0.7	50	SEE SHEET 4A, SIGN S1
1	END 20 MILE SPEED	TN-9	ALUMINUM	0.080"	S.F.	2	24"X30"	10.00		P2	11.50	2.060	48	0.7	50	SEE SHEET 4A, SIGN S2
								10.00	**18.00**				**105**	**2**	**100**	

1 WITH TYPE 4 FOOTING FOR BREAK-AWAY TYPE POST FOOTINGS - SEE STANDARD DRAWING T-S-12

SEALED BY

Digitally signed by Peter Strub
DN: c=US, st=South Carolina, l=Greenville, o=TranSystems Corporation, cn=Peter Strub, email=pmstrub@transystems.com
Date: 2015.06.19 11:18:34 -04'00'

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES

6/17/2015 10:16:25 AM
G:\ATI4\0014\Road\Construction Plans\002B - Tabulated Quantities.sht