TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	PHSIP-21(19)	2

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY
	105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1
	201-01	CLEARING AND GRUBBING	LS	1
	712-01	TRAFFIC CONTROL	LS	1
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	10
	712-06	SIGNS (CONSTRUCTION)	S.F.	81
	712-08.03	ARROW BOARD (TYPE C)	EACH	2
	713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	C.Y.	2
	713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	LB.	100
	713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	LB.	105
	713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	S.F.	10
	713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	S.F.	18
	717-01	MOBILIZATION	LS	1
1	730-01.08	SCHOOL SPEED LIMIT FLASHING SIGNAL INSTALLED	EACH	2
2	730-05.01	ELECTRICAL SERVICE CONNECTION	EACH	2
	730-05.02	SERVICE CABLE (2 CONDUCTOR, # 8 AWG)	L.F.	620
	730-11.01	STEEL CONDUIT RISER ASSEMBLY	EACH	2
	730-21.03	WOOD POLE (SIGNAL SUPPORT) CLASS 3, 45' LENGTH	EACH	2
3	740-11.01	TEMPORARY SEDIMENT TUBE 8IN (DESCRIPTION)	L.F.	25
	801-01	SEEDING (WITH MULCH)	UNIT	1
	801-03	WATER (SEEDING & SODDING)	M.G.	1

1 INCLUDES SIGN FACE, FLASHERS, CONTROLLER, ATTACHMENT HARDWARE FOR THE POLE MOUNTS AND OVERHEAD SIGNS, METER BASE WHERE INDICATED, ALL APPURTENANCES FOR A COMPLETE SYSTEM.
2 CONTRACTOR TO BE RESPONSIBLE FOR COSTS OF OBTAINING ELECTRICAL SERVICE CONNECTION
3 FOR USE AROUND SUPPORT POLES

SEALED BY

Digitally signed by Peter Strub
DN: c=US, st=South Carolina, l=Greenville, o=TranSystems Corporation, cn=Peter Strub, email=pmstrub@transystems.com
Date: 2015.06.19 11:11:55 -04'00'

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

6/17/2015 10:12:24 AM
G:\ATI4\0014\Road\Construction Plans\002 - Estimated Roadway Quantitites.sht