TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	PHSIP-21(19)	5

TRAFFIC CONTROL QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	REMARKS
712-01	TRAFFIC CONTROL	1	L.S.	
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	10	EACH	
712-06	SIGNS (CONSTRUCTION)	81	S.F.	
712-08.03	ARROW BOARD (TYPE C)	2	EACH	

TRAFFIC CONTROL QUANTITIES (SIGNS)

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	SIZE	ITEM NO. 712-06.10 (S.F.)	M.U.T.C.D. NO.	REMARKS
712-06	END ROAD WORK	S.F.	2	36"X18"	9.00	G20-2	
	ROAD WORK 1/2 MILE	S.F.	2	36"X36"	18.00	W20-1	
	FLAGGER	S.F.	2	36"X36"	18.00	W20-7	
	ROAD WORK 1500 FT	S.F.	2	36"X36"	18.00	W20-1	
	ROAD WORK 1000 FT	S.F.	2	36"X36"	18.00	W20-1	
TOTAL					**81.00**		

SEALED BY

Digitally signed by Peter Strub
DN: c=US, st=South Carolina, l=Greenville, o=TranSystems Corporation, cn=Peter Strub, email=pmstrub@transystems.com
Date: 2015.06.19 11:24:19 -04'00'

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL QUANTITIES

6/17/2015 10:17:29 AM
G:\AT14\0014\Road\Construction Plans\005 - Traffic Control Quantities.sht