TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	43009-4407-04	2B

TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY
1	105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1
2	209-05	SEDIMENT REMOVAL	C.Y.	6
2	209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	L.F.	155
3	712-01	TRAFFIC CONTROL	LS	1
4	712-06	SIGNS (CONSTRUCTION)	S.F.	137
	713-16.20	SIGNS (OM3-L)	EACH	2
	713-16.21	SIGNS (OM3-R)	EACH	2
	717-01	MOBILIZATION	LS	1
	740-11.01	TEMPORARY SEDIMENT TUBE (8 INCH)(STRAW WATTLES)	L.F.	40
5	801-01	SEEDING (WITH MULCH)	UNIT	1
6	801-03	WATER (SEEDING AND SODDING)	M.G.	1

FOOTNOTES

1. ALL DIMENSIONAL DETAILS SHOWN ON PLANS, INCLUDING ELEVATIONS, SHALL BE CHECKED BY THE CONTRACTOR TO ASSURE ACCURACY OF THE LAYOUT PRIOR TO CONSTRUCTION. ALL BRIDGE SUBSTRUCTURES SHALL BE CHECKED AS TO LOCATION, DIMENSIONAL LAYOUTS AND ELEVATIONS, BY MEANS OF TWO INDEPENDENT LAYOUT METHODS. ANY ERRORS AND APPARENT DISCREPANCIES FOUND IN PREVIOUS SURVEYS, OR IN EITHER THE SPECIFICATIONS OR SPECIAL PROVISIONS, SHALL BE CALLED TO THE ENGINEER'S ATTENTION BY THE CONTRACTOR IMMEDIATELY AND PRIOR TO PROCEEDING WITH WORK.
2. SEE SUBSECTION 209.07 OF THE STANDARD SPECIFICATIONS FOR MAINTENANCE REPLACEMENT.
3. INCLUDES COST FOR REMOVAL OF EXISTING OR CONFLICTING MARKINGS. INCLUDES COST OF PROVIDING FLAGGERS FOR TEMPORARY LANE CLOSURES.
4. BASED ON SECTION 712.10 OF STANDARD SPECIFICATIONS
5. ITEM MAY BE INCREASED, DECREASED OR ELIMINATED AS DIRECTED BY THE ENGINEER.
6. INCLUDES 1 THOUSAND GALLONS FOR EROSION PREVENTION AND SEDIMENT CONTROL.

JAMES R. GILLESPIE JR.
REGISTERED ENGINEER
AGRICULTURE
COMMERCE
NO. 102639
STATE OF TENNESSEE
06/10/2015

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

BRIDGE NO. 43-910-4.10
BAKERSVILLE ROAD
OVER BUFFALO RIVER
HUMPHREYS COUNTY
2015

ESTIMATED
ROADWAY
QUANTITIES