TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	STP/NH-SIP-37(16)	2C

PERMANENT SIGN QUANTITIES

	DESCRIPTION	UNIT	QUANTITY	SIZE	MATERIAL	THICKNESS	M.U.T.C.D. NO.	REMARKS
1	SIGNAL AHEAD	EACH	5	30" X 30"	ALUMINUM	0.080"	W3-3	SEE NOTE 1 BELOW
2	US 321 LEFT	EACH	1	96" X 18"	ALUMINUM	0.080"	D3-1	SEE SHEET 5, SIGN S1
2	STATE LINE RD.	EACH	1	96" X 18"	ALUMINUM	0.080"	D3-1	SEE SHEET 5, SIGN S2
2	US 321 RIGHT	EACH	1	96" X 18"	ALUMINUM	0.080"	D3-1	SEE SHEET 5, SIGN S3
	TOTAL		**8**					

1 UNIT PRICE PER EACH SHALL INCLUDE COST FOR THE REQUIRED TYPE P8 POST

2 SIGNS PAID AS EACH

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES

11/22/2013 10:24:44 AM
g:\NAI2\0074\Road\Construction Plans\002C - Tabulated Quantities.sht