TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	HSIP-118(10)	2

REV. 03-07-14: ADDED ALTERNATES AA1 & AA2 & REVISED FOOTNOTES.

REV. 03-24-14: REVISED FOOTNOTE NUMBERS; REMOVED NOS. 202-03.01, 307-01.01; ADDED ITEM NO. 415-01.02 TO ALTERNATE AA1; UPDATED QUANTITIES FOR ITEM NOS. 203-06 & 303-02.

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	92008-4210-04 QUANTITY	HSIP-118(10) QUANTITY	92008-4211-04 QUANTITY	TOTAL QUANTITY
	203-06	WATER	M.G.	29			29
	303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING D	TON	3790			3790
1 2	405-01.01	BITUMINOUS MATERIAL (BSC)	TON	323			323
3 2	405-01.02	MINERAL AGGREGATE (BSC)	TON	2457			2457
4 5	411-02.10	ACS MIX(PG70-22) GRADING D	TON	538			538
	604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	S.Y.			40	40
	617-04.02	TYPE 2 THIN EPOXY OVERLAY (LOW-MOD EPOXY)	S.Y.			3060	3060
6	705-04.07	TAN ENERGY ABSORBING TERM (NCHRP 350, TL3)	EACH		15		15
7	712-01	TRAFFIC CONTROL	LS	0.33			0.33
	712-06	SIGNS (CONSTRUCTION)	S.F.	2432			2432
8	716-01.21	SNWPLWBLE PVMT MRKRS (BI-DIR)(1 COLOR)	EACH		966		966
	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.		46		46
	716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	EACH		1		1
9	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	57.06			57.06
9	716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	L.M.		48.19		48.19
10							
9	717-01	MOBILIZATION	LS	0.33			0.33
		ALTERNATE AA1					
11 12	411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	TON	8702			8702
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	65			65
	415-01.02	COLD PLANING BITUMINOUS PAVEMENT	S.Y.	6608			6608
		ALTERNATE AA2					
	403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	TON	22			22
13	414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	TON	393			393
14	414-03.02	AGGREGATE FOR MICRO SURFACING	TON	3276			3276

FOOTNOTES

1. INCLUDES 9 TONS FOR EXTRA-WIDTH PAVING AND GORE AREAS.(CRS-2P)
2. SEE SPECIAL PROVISION NO. 405SCI RIDEABILITY SPECIFICATIONS.
3. INCLUDES 69.5 TONS FOR EXTRA WIDTH PAVING AND GORE AREAS.
4. INCLUDES 193 TONS FOR SPOT LEVELING.
5. INCLUDES 438 TONS FOR REPLACEMENT OF COLD PLANING AT BRIDGE END @ LM 4.71 (23'), LM 5.75 (20'), LM 9.73 (171'), LM 10.14 (86').
6. SEE BRIDGE TABULATION SHEET NO. B1
7. FOR UPGRADE OF EXISTING ANCHORS AT ALL STRUCTURE LOCATIONS IN PROJECT LIMITS. THE COST OF REMOVAL OF EXISTING GUARDRAIL AND ANCHORS TO BE INCLUDED IN THIS ITEM.
8. QUANTITY INCLUDES

2	ROAD WORK NEXT 15 MI.	(G20-1)	(48" X 24")
2	END ROAD WORK	(G20-2)	(48" X 24")
77	UNEVEN LANES	(W8-11)	(48" X 48")
27	ROAD WORK AHEAD	(W20-1)	(48" X 48")
2	ROAD WORK 1500 FT.	(W20-1)	(48' X 48")
2	ROAD WORK 1000 FT.	(W20-1)	(48" X 48")
2	ROAD WORK 500 FT.	(W20-1)	(48" X 48")
2	ONE LANE ROAD AHEAD	(W20-4)	(48" X 48")
2	FLAGGER AHEAD	(W20-7a)	(48" X 48")
2	FRESH OIL	(W21-2)	(48" X 48")
30	SHOULDER WORK	(W21-5)	(48" X 48")
4	GROOVED PAVEMENT	(TN-64)	(48" X 48")

THIS CONSTRUCTION SIGNING IS TO BE AS A MINIMUM. OTHER SIGNS AS DIRECTED BY THE ENGINEER MAY BE REQUIRED DURING DIFFERENT PHASES.

9. FOR FINAL PAVEMENT MARKING ONLY.
10. FOR USE AS TEMPORARY LINE MARKINGS, INCLUDES 10.87 MILES FOR TEMPORARY MARKINGS OVER COLD PLANED PAVEMENT AT BRIDGE ENDS, BREAKOUT, SPOT LEVELING, CITY STREETS AND INTERSECTIONS.
11. SEE SPECIAL PROVISION NO. 407G FOR MATERIAL TRANSFER DEVICE, AND SPECIAL PROVISION 411C FOR RIDEABILITY SPECIFICATIONS. (RIDEABILITY FROM L.M. 1.30 TO L.M. 14.78 ONLY)
12. INCLUDES 846 TONS FOR EXTRA-WIDTH PAVING, GORE AREA & TERMINAL SHORTAGE.
13. INCLUDES 11 TONS FOR EXTRA WIDTH PAVING AND GORE AREAS.
14. INCLUDES 93 TONS FOR EXTRA WIDTH PAVING AND GORE AREAS.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

24-MAR-2014 13:39
\\j04wf01.tdot.state.tn.us\04SHARED\Design\DESIGN\RESURF REG4 PROJ\WEAKLEY\SRI8\LM 0.29\92 SRI8 LM 0.29-14.78 QUANTITIES.dgn