TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	19180-3212-04	2B

SPECIAL NOTES CONTINUED

SIGNAL (OR LIGHTING) EROSION PREVENTION AND SEDIMENT CONTROL SPECIAL NOTES CONTINUED

(40) FOR THE INSTALLATION OF CONDUITS AND CABLES, TRENCHES SHALL BE BACKFILLED DAILY AS CONSTRUCTION PROCEEDS. BACKFILLED TRENCHES SHALL BE SEEDED AND MULCHED OR SODDED DAILY IF POSSIBLE, BUT NO LATER THAN SEVEN DAYS AFTER BEING BACKFILLED, OR IMMEDIATELY AFTER ANY INSPECTION. ANY TEMPORARY SPOIL OF EXCAVATED EARTH SHALL BE LOCATED WITHIN TDOT EROSION PREVENTION AND SEDIMENT CONTROL MEASURES. IF TRENCHES ARE NOT BACKFILLED OVERNIGHT, APPROPRIATE EPSC MEASURES WILL BE INSTALLED BY THE CONTRACTOR UNTIL SUCH TIME AS THE TRENCH IS BACKFILLED.

(41) RAIN WATER WHICH COLLECTS IN THE OPEN EXCAVATIONS (TRENCHES OR FOUNDATION EXCAVATIONS) SHALL BE PUMPED INTO A DEWATERING STRUCTURE OR SEDIMENT FILTER BAG AND MAINTAINED. NO SEPARATE PAYMENT FOR THIS REQUIREMENT.

(42) SPOILS FROM FOUNDATION EXCAVATIONS SHALL BE PICKED UP AS BORING PROGRESSES, OR CONTAINED WITHIN APPROPRIATE EPSC MEASURES.

LIGHTING SCOPE OF SERVICES

(43) THE PROPOSED LIGHTING DESIGN LIMITS INCLUDE THE INTERCHANGE OF SR 386 AT CONFERENCE DRIVE.

(44) THE LIGHTING DESIGN CONSISTS OF:

A. 1-COBRAHEAD LUMINAIRE WITH 15' ARM (LP 1).

B. 18-OFFSET LUMINAIRES (LP 2 THRU LP 19).

C. 7-HIGH MAST LUMINAIRES (HM 1 THRU HM 7).

D. 4-UNDERPASS LUMINAIRES (UPL 1 THRU UPL 4).

(45) THE EXISTING COBRAHEAD LUMINAIRES SHALL REMAIN IN PLACE. LP 1 SHALL BE CONNECTED TO THE EXISTING COBRAHEAD LIGHTING SYSTEM.

(46) ALL TREE REMOVALS SHALL BE APPROVED BY THE ENGINEER (SEE NOTES 5 AND 6 ON SHEET 7).

SEALED BY

Brenda K Booker



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, SPECIAL NOTES, AND LIGHTING SCOPE OF SERVICES

2/18/2013 10:42:50 AM
C:\Users\BE-Bea\Desktop\Booker\01_ACTIVE\TDOT\E16\DAVIDSON\02_SR 386 INTERCHANGE LIGHTING STUDY AND DESIGN\PART 2 - LIGHTING DESIGN\04_FINAL CONST DGN FILES\002B.SHT