| TYPE | YEAR | PROJECT NO. | SHEET NO. |
|---|---|---|---|
| RESURF. | 2014 | NH-I-65-3(121) | 7 |
| | | | |
| | | | |
| | | | |

## TRAFFIC CONTROL QUANTITIES

| ITEM NO. | DESCRIPTION | UNIT | QUANTITY | M.U.T.C.D. NO. | REMARKS |
|---|---|---|---|---|---|
| 712-01 | TRAFFIC CONTROL | LS | 1 | | |
| 712-04.01 | FLEXIBLE DRUMS (CHANNELIZING) | EACH | 300 | | |
| 712-06.16 | WORKERS PRESENT REDUCED SPEED | EACH | 2 | TN-44 | |
| 712-08.03 | ARROW BOARD (TYPE C) | EACH | 5 | | |
| 713-16.01 | CHANGEABLE MESSAGE SIGN UNIT | EACH | 2 | | |
| 717-01 | MOBILIZATION | LS | 1 | | |

## SIGNS (CONSTRUCTION) 712-06

| ITEM NO. | DESCRIPTION | UNIT | QUANTITY | ITEM NO. 712-06 (S.F.) | SIZE | M.U.T.C.D. NO. | REMARKS |
|---|---|---|---|---|---|---|---|
| 712-06 | REDUCED SPEED AHEAD | | 2 | 40 | 48x60 | R2-5A | SIGN |
| 712-06 | "RECORD A COMMENT" | | 2 | 64 | 96x48 | TN-55A | SIGN |
| 712-06 | ROAD WORK AHEAD | | 11 | 176 | 48 x 48 | W20-1 | SIGN |
| 712-06 | ROAD WORK 2 MILE | | 4 | 64 | 48 x 48 | W20-1 | SIGN |
| 712-06 | ROAD WORK 1 MILE | | 4 | 64 | 48 x 48 | W20-1 | SIGN |
| 712-06 | ROAD WORK 1/2 MILE | | 4 | 64 | 48 x 48 | W20-1 | SIGN |
| 712-06 | ROAD WORK 1000 FEET | | 4 | 64 | 48 x 48 | W20-1 | SIGN |
| 712-06 | RIGHT LANE CLOSED 1 MILE | | 2 | 32 | 48 x 48 | W20-5R | SIGN |
| 712-06 | RIGHT LANE CLOSED 1/2 MILE | | 2 | 32 | 48 x 48 | W20-5R | SIGN |
| 712-06 | RIGHT LANE CLOSED 1500 FEET | | 2 | 32 | 48 x 48 | W20-5R | SIGN |
| 712-06 | LEFT LANE CLOSED 1 MILE | | 2 | 32 | 48 x 48 | W20-5L | SIGN |
| 712-06 | LEFT LANE CLOSED 1/2 MILE | | 2 | 32 | 48 x 48 | W20-5L | SIGN |
| 712-06 | LEFT LANE CLOSED 1500 FEET | | 2 | 32 | 48 x 48 | W20-5L | SIGN |
| 712-06 | GROOVED PAVEMENT - PORTABLE | | 11 | 176 | 48 x 48 | W21-1 | SIGN |
| 712-06 | MERGE NOW (SPECIAL) | | 2 | 32 | 48 x 48 | W8-11 | SIGN |
| 712-06 | ROAD WORK NEXT 3 MILES | | 1 | 16 | 30 x 24 | G20-1 | SIGN |
| 712-06 | END ROAD WORK | | 8 | 128 | 48 x 24 | G20-2A | SIGN |
| 712-06 | SPEED LIMIT (70 MPH) | | 2 | 40 | 48 x 60 | R2-1 | SIGN |
| 712-06 | SHIFT ARROW | | 2 | 32 | 48 x 48 | W1-4AR | SIGN |
| 712-06 | DO NOT PASS IN RIGHT LANE | | 2 | 70 | 120 x 40 | R4-1(MOD) | SIGN |
| 712-06 | UNEVEN LANES - PORTABLE | | 2 | 32 | 48 x 48 | W8-11 | SIGN |
| 712-06 | SHOULDER DROP-OFF - PORTABLE | | 2 | 32 | 48 x 48 | W8-9a | SIGN |
| 712-06 | EXIT (MOUNTED ON FLEXIBLE DRUM) | | 3 | 15 | 30 x 24 | M4-9R | SIGN |
| 712-06 | YIELD | | 3 | 13.5 | 36 x 36 x 36 | R1-2 | SIGN |
| 712-06 | ON RAMP | | 7 | 63 | 36X36 | W13-4 | SIGN |
| 712-06 | RAMP NARROWS | | 11 | 176 | 48X48 | W5-1(MOD) | SIGN |
| | | | | | | | |
| **TOTAL** | | | | **1746** | | | |

SEALED BY




01/22/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

# TRAFFIC CONTROL QUANTITIES

22-JAN-2014 13:34
\\JJ03WF01.tdot.state.tn.us\03Shared\SURVEY\DESIGN\Resurfacing Plans\2014Interstate\DavidsonSumnerCos,I-65\104520.01-007TrafficControl.dgn