TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	STP-M-9401(10)	2

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
	203-06	WATER	M.G.	2
1	303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (TYPE D)	TON	258
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	5
2	411-02.10	ACS MIX (PG70-22) GRADING D	TON	1049
	701-02.01	CONCRETE HANDICAP RAMP (RETROFIT)	S.F.	1026
	712-01	TRAFFIC CONTROL	LS	1
3	712-06	SIGNS (CONSTRUCTION)	S.F.	528
4	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	36
4	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	5
	717-01	MOBILIZATION	LS	1

FOOTNOTES

1. FOR USE ON SHOULDERS AND 10 TONS ± FOR OTHER LOCATIONS AS NEEDED OR DIRECTED BY ENGINEER.
2. INCLUDES 94 TONS FOR COUNTY ROADS, CITY STREETS, PRIVATE DRIVES, AND FIELD ENTRANCES, AND 50 TONS FOR ADDITIONAL PAVEMENT.
3. QUANTITY INCLUDES

2	ROAD WORK NEXT 1 MI.	(G20-1)	(48" X 24")
4	END ROAD WORK	(G20-2)	(48" X 24")
4	UNEVEN LANES	(W8-11)	(48" X 48")
14	ROAD WORK AHEAD	(W20-1)	(48" X 48")
2	ROAD WORK 1500 FT.	(W20-1)	(48" X 48")
2	ROAD WORK 1000 FT.	(W20-1)	(48" X 48")
2	ROAD WORK 500 FT.	(W20-1)	(48" X 48")
2	ONE LANE ROAD AHEAD	(W20-4)	(48" X 48")
2	FLAGGER AHEAD	(W20-7a)	(48" X 48")
2	FRESH OIL	(W21-2)	(48" X 48")

THIS CONSTRUCTION SIGNING IS TO BE AS A MINIMUM. OTHER SIGNS AS DIRECTED BY THE ENGINEER MAY BE REQUIRED DURING DIFFERENT PHASES.

4. FINAL PAVEMENT MARKING ONLY.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

28-JAN-2014 07:16
\\j04wf01.tdot.state.tn.us\04SHARED\Design\DESIGN\RESURF REG4 PROJ\HARDEMAN\BOLIVAR\City Streets - E. Margin & Fairgrounds\City of Bolivar\35 2 CITY STREETS EST QTYS.dgn