TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2014	STP/HSIP-456(10)	3

SCOTT CO. S.R. 456
76010-4225-04
76010-3225-94
76010-8225-14

TABULATED GUARDRAIL QUANTITIES

LOG MILE	LOCATION	SINGLE TYPE 2 GUARDRAIL 705-02.02 (FT)	TYPE 38 TERMINAL 705-04.07 (EACH)	EARTH PAD 705-04.09 (EACH)	GUARDRAIL REMOVED 706-01 (FT)
9.21	LT		1	1	50
9.71	LT, RT		2	2	100
9.83 - 9.90	LT	275	2		100
TOTALS		275	5	3	250

NOTE:
TO BE USED IN LOCATIONS LISTED ABOVE OR AS DIRECTED BY THE TDOT OPERATIONS DISTRICT ENGINEER.

TABULATED SIGN QUANTITIES

ITEM NO.	CODE	LOCATIONS	NO.
713-16.20	OM-3	L.M. 8.82± RT & LT, L.M. 9.42± RT & LT	8
713-16.23	TN-17A	L.M. 9.00± RT	1
713-16.24	W1-7	L.M. 9.84± LT, L.M. 9.94± LT	2
713-16.58	W2-2	L.M. 8.46± RT L.M. 2.00± RT	1
713-16.59	W1-3	L.M. 8.51± LT	1
713-16.60	R1-1	L.M. 9.12± RT, L.M. 10.05± RT	1

NOTE:
TO BE USED IN LOCATIONS LISTED ABOVE OR AS DIRECTED BY THE TDOT OPERATIONS DISTRICT ENGINEER.

NOTE:
EXISTING SIGNS TO BE REMOVED SHALL BECOME PROPERTY OF THE STATE MAINTENANCE FORCES UPON COMPLETION OF THE PROJECT.

TABULATED CONSTRUCTION SIGNS ITEM NO.712-06

NO.	DESCRIPTION	CODE	SIZE	QUANTITY (SF)
28	ROAD WORK	W20-1	48"X48"	448
2	ONE LANE ROAD	W20-4	48"X48"	32
2	FLAGGER	W20-7A	48"X48"	32
2	ROAD WORK NEXT 2 MILES	G20-1	36"X18"	9
2	ADVISORY SPEED	W13-1	24"X24"	8
4	END ROAD WORK	G20-2	36"X18"	18
10	UNEVEN LANES	W8-11	36"X36"	90
			TOTAL:	637

NOTE: THIS CONSTRUCTION SIGNING IS TO BE A MINIMUM. OTHER SIGNS MAY BE REQUIRED AS DIRECTED BY THE TDOT OPERATIONS DISTRICT ENGINEER.

ESTIMATED BRIDGE QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY 65014-4208-04
604-10.50	BRIDGE DECK REPAIRS (Partial Depth of Slab)	S.Y.	5
617-04.02	TYPE 2 THIN EPOXY OVERLAY (Low -Mod Epoxy)	S.Y.	940

NOTE: SEE SHEET B1 FOR DETAILS.

SEALED BY



01/22/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES AND ESTIMATED BRIDGE QUANTITIES

22-JAN-2014 09:36
\\JOIWF01.tdot.state.tn.us\OIShared\SURVDES\DESIGN\PROJECTS\RESURF\2014\Scott SR456\ScottSR456.dgn