TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	76010-8225-14	B2
		STP/HSIP-456(10)	
BRIDGE REPAIR	2014	76010-4225-04	

TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

SPECIAL RAILROAD NOTES

1.) THE CONTRACTOR SHALL CONDUCT HIS WORK SO AS TO PROTECT THE RAILROAD'S TRACKS AND PROPERTIES FROM ANY DAMAGE. THE WORK SHALL BE DONE IN ACCORDANCE WITH REGULATIONS STIPULATED BY SOUTHER RAILROAD ON THIS PROJECT SO AS TO MAINTAIN CLEARANCE AND NOT INTERRUPT TRAIN TRAFFIC IN ANY MANNER.

2.) THE CONTRACTOR SHALL BE REQUIRED TO SUBMIT A DETAILED AND COMPREHENSIVE SCHEDULE, PLAN AND PROCEDURE FOR REVIEW AND APPROVAL BY SOUTHER RAILROAD FOR THE FOLLOWING TASKS IN THE RAILROAD'S RIGHT-OF-WAY:

A) BRIDGE DECK REPAIR.
B) BRIDGE DECK SEALANT

3.) FOR CONCRETE DECK REPAIR OVER THE RAILROAD, CONTRACTOR SHALL USE EXTREME CARE AND TAKE ANY MEASURE NECESSARY TO PREVENT DEBRIS FROM FALLING ON TO THE RAILROAD'S RIGHT OF WAY. FOR FULL DEPTH CONCRETE DECK REPAIR IN THE RAILROAD SPAN THIS SHALL BE ACCOMPLISHED BY USE OF BASKETS, NETTING, WRAPPING, SHIELD, OR SIMILARLY EFFECTIVE MEANS THAT WILL NOT INFRINGE ON THE VERTICAL CONSTRUCTION CLEARANCES IN THESE PLANS. BE ADVISED THAT RAILROADS WILL NOT ALLOW TRACK OR TRACKS TO BE OBSTRUCTED WITH AT GRADE CRANE MAT PROTECTION. FOR FULL DEPTH CONCRETE DECK REPAIR IN THE RAILROAD SPAN COMPLETE AND FULL ENCLOSURE OF STRUCTURE DEMOLITION WITHIN ALLOWABLE CLEARANCES WILL BE REQUIRED. COST OF REMOVING AND DISPOSING OF DEBRIS,COMPLETE AND FULL PROTECTION OF THE CONTRACTOR WORK AREA FOR DEMOLITION SHALL BE INCLUDED IN ITEMS BID ON.

4.) NO TEMPORARY FALSEWORK IF APPLICABLE WILL BE ALLOWED THAT INFRINGES ON A TEMPORARY HORIZONTAL CONSTRUCTION CLEARANCE OF 13'-0" FOR TANGENT TRACK OR 14'-0" FOR CURVED TRACK OR A TEMPORARY VERTICAL CONSTRUCTION CLEARANCE OF 22'-0". IT IS ANTICIPATED THAT FULL TIME FLAGGING WILL ONLY BE REQUIRED FOR FULL DEPTH CONCRETE DECK REPAIRS, AND ANY OTHER FLAGGING SERVICES REQUIREMENTS FOR THE BRIDGE DECK SEAL REPAIR CONSTRUCTION WILL BE AT THE DISCRETION OF THE RAILROAD.

5.) SEE RAILROAD AGREEMENT/ STATE CONTRACT SPECIAL PROVISION 105C(R)[Railroad special Provisions] AND STATE CONTRACT NORFOLK SOUTHERN PUBLIC PROJECTS MANUAL DATED JULY 1,2013 TO SET UP FLAGGING SERVICES, TO SUBMIT FOR INSURANCE REQUIRED FOR WORK ON HIGHWAY BRIDGE OVER THE RAILROAD, AND FOR INFORMATION ON ALL OTHER RAILROAD RULES AND SPECIFICATIONS THAT APPLY TO THIS PROJECT.

CNO&TP RAILWAY CAMPANY CONTACT ADDRESSES:

NORFOLK SOUTHERN CORPORATION
BRIDGES & STRUCTURES DEPARTMENT
ATTN: MR. DANIEL PARKER
1200 PEACHTREE STREET, NE
ATLANTA, GA 30309

PHONE: (404) 529-1256
FAX: (404) 527-2589
EMAIL: daniel.parker@nscorp.com

NORFOLK SOUTHERN CORPORATION CENTRAL DIVISION

MR. DON SUTHERLAND, DIVISION ENGINEER
7208 OLD RUTLEDGE PIKE
KNOXVILLE, TN 37914
PHONE: (865) 521-1409
E-MAIL: donald.sutherland@nscorp.com



11/12/13

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

RAILROAD NOTES

11/12/2013 9:59:39 AM
P:\STRUCT_RP\Bridgerepair\Sleshi\Tabulated Sheets\Rg.1\STATE ROUTE\Scott Co\76-SR456-9.57.dgn