TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2014	STP/HSIP-456(10)	2

SCOTT CO. S.R. 456
76010-4225-04
76010-3225-94
76010-8225-14

REV. 01-29-14: REVISED PROJECT NUMBER IN QUANTITY BLOCK.

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY 76010-8225-14	QUANTITY STP/HSIP-456(10) 76010-3225-94
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	17	
1	411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	TON	395	
2	411-01.10	ACS MIX(PG64-22) GRADING D	TON	2134	
3	411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	L.M.	3	
4	415-01.01	COLD PLANING BITUMINOUS PAVEMENT	TON	2293	
5	611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	EACH	9	
	705-02.02	SINGLE GUARDRAIL (TYPE 2)	L.F.		275
	705-04.07	TAN ENERGY ABSORBING TERM (NCHRP 350, TL3)	EACH		5
	705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	EACH		3
	706-01	GUARDRAIL REMOVED	L.F.		250
	712-01	TRAFFIC CONTROL	LS	0.1	
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	138	
	712-05.01	WARNING LIGHTS (TYPE A)	EACH	69	
	712-06	SIGNS (CONSTRUCTION)	S.F.	637	
	712-08.03	ARROW BOARD (TYPE C)	EACH	2	
	713-16.20	SIGNS (OM-3 OBJECT MARKERS)	EACH		8
	713-16.23	SIGNS (TN-17A)	EACH		1
	713-16.24	SIGNS (W1-7)	EACH		2
	713-16.58	REMOVE AND REPLACE SIGN (W2-2)	EACH		1
	713-16.59	REMOVE AND REPLACE SIGN (W1-3)	EACH		1
	713-16.60	REMOVE AND REPLACE SIGN (R1-1)	EACH		1
6	716-01.21	SNWPLWBLE PVMT MRKRS (BI-DIR) (1 COLOR)	EACH		147
8	716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	S.Y.		104
7	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.		210
	716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH		6
	716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	EACH		2
9	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	7	
	716-13.01	SPRAY THERMO PVMT MRKNG (60 MIL) (4 IN LINE)	L.M.	7	
	717-01	MOBILIZATION	LS	0.1	

FOOTNOTES

1. INCLUDES 24 TONS FOR PRIVATE DRIVES AND 24 TONS FOR BUSINESS ENTRANCES.
2. INCLUDES 52 TONS FOR PRIVATE DRIVES, 51 TONS FOR BUSINESS ENTRANCES AND 160 TONS FOR COUNTY ROADS.
3. TO BE LOCATED FROM L.M. 8.34± TO L.M. 9.26± OR AS DIRECTED BY THE TDOT OPERATIONS DISTRICT ENGINEER.
4. INCLUDES 160 TONS FOR COUNTY ROADS.
5. TO BE USED AS FOLLOWS OR AS DIRECTED BY THE T.D.O.T. OPERATIONS DISTRICT ENGINEER:

   L.M. 9.73 (RT.) L.M. 9.92 (LT.)
   L.M. 9.74 (RT.) L.M. 9.97 (LT.)
   L.M. 9.79 (RT.) L.M. 9.99 (LT.)
   L.M. 9.82 (RT.) L.M. 10.01 (LT.)
   L.M. 9.87 (RT.)
6. INCLUDES COST OF REMOVAL OF ANY EXISTING MARKINGS.
7. THE CONTRACTOR MAY ELECT TO SUBSTITUTE PREFORMED PLASTIC FOR THERMOPLASTIC. PREFORMED PLASTIC SHALL BE PAID FOR AT THE SAME UNIT PRICE AS BID FOR THERMOPLASTIC.
8. INCLUDES 54 S.Y. (725 L.F.) FOR 8" BARRIER LINE.
9. TO BE USED FOR TEMPORARY PAVEMENT MARKING ON INTERMEDIATE LAYERS.

SEALED BY

01/29/2014

SEE SHEET NO. 3 FOR TABULATED QUANTITIES AND ESTIMATED BRIDGE QUANTITIES

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

29-JAN-2014 13:33
\\JOIWF01.tdot.state.tn.us\OIShared\SURVDES\DESIGN\PROJECTS\RESURF\2014\Scott SR456\Scott SR456.dgn