TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	NH/HSIP-69(87)	2

TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	40008-8228-14 QUANTITY	NH/HSIP-69(87) QUANTITY	TOTAL QUANTITY
	202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	100		100
	203-06	WATER	M.G.	9		9
1	303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING "C" OR "D"	TON	1182		1182
2	307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	TON	46		46
3	307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	TON	1704		1704
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	49		49
4 5	411-01.10	ACS MIX(PG64-22) GRADING D	TON	242		242
6 7 8 9	411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	TON	3361		3361
	411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	L.M.		8.58	8.58
10	415-01.02	COLD PLANING BITUMINOUS PAVEMENT	S.Y.	1600		1600
11	705-04.07	TAN ENERGY ABSORBING TERM (NCHRP 350, TL3)	EACH		2	2
	712-01	TRAFFIC CONTROL	LS	0.4		0.4
12	712-06	SIGNS (CONSTRUCTION)	S.F.	1056		1056
	716-01.21	Snwplwble Pvmt Mrkrs (Bi-Dir)(1 Color)	EACH		434	434
	716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	EACH		332	332
	716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	S.Y.		129	129
14	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.		161	161
14	716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH		5	5
14	716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	EACH		2	2
13	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	17.053		17.053
14	716-13.03	SPRAY THERMO PVMT MRKNG (60 mil) (8IN BARRIER LINE)	L.F.		637	637
15	716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	L.M.		17.053	17.053
	717-01	MOBILIZATION	LS	0.4		0.4

FOOTNOTES

1. INCLUDES 68 TONS FOR BREAKOUT.
2. FOR REPLACEMENT OF QUANTITY REMOVED UNDER ITEM 202-03.01 ONLY.
3. INCLUDES 249 TONS FOR ADDITIONAL EXTRA-WIDTH PAVING FOR GORE AREAS, TURNLANES, INTERSECTIONS,TERMINI SHORTAGE AND RAMP ENTRANCE AT S.R. 54.
4. INCLUDES 142 TONS FOR REPLACEMENT OF COLDPLANING AND 100 TONS FOR SPOT LEVELING.
5. SEE SPECIAL PROVISION NO. 407G FOR MATERIAL TRANSFER DEVICE.
6. INCLUDES 212 TONS FOR COUNTY ROADS, CITY STREETS, PRIVATE DRIVES, FIELD ENTRANCES, BUSINESS FRONTAGE AND COLDPLANED SECTIONS AT BRIDGE ENDS.
7. INCLUDES 459 TONS FOR ADDITIONAL EXTRA-WIDTH PAVING FOR GORE AREAS, TURNLANES, INTERSECTIONS,TERMINI SHORTAGE AND RAMP ENTRANCE AT S.R. 54.
8. SEE SPECIAL PROVISION NO. 407G FOR MATERIAL TRANSFER DEVICE AND SPECIAL PROVISION NO. 411C FOR RIDEABILITY SPECIFICATIONS.
9. SEE SPECIAL PROVISION NUMBER 411TLD.
10. FOR USE ON 300' OFF EACH END OF BRIDGE, AT L.M. 13.47.
11. FOR UPGRADE OF EXISTING ANCHORS AT ALL STRUCTURE LOCATIONS IN PROJECT LIMITS. THE COST OF REMOVAL OF EXISTING GUARDRAIL AND ANCHORS TO BE INCLUDED IN THIS ITEM.
12. QUANTITY INCLUDES

2	ROAD WORK NEXT 5 MI.	(G20-1)	(48" X 24")
2	END ROAD WORK	(G20-2)	(48" X 24")
24	UNEVEN LANES	(W8-11)	(48" X 48")
13	ROAD WORK AHEAD	(W20-1)	(48" X 48")
3	ROAD WORK 1500 FT.	(W20-1)	(48" X 48")
3	ROAD WORK 1000 FT.	(W20-1)	(48" X 48")
3	ROAD WORK 500 FT.	(W20-1)	(48" X 48")
2	ONE LANE ROAD AHEAD	(W20-4)	(48" X 48")
2	FLAGGER AHEAD	(W20-7a)	(48" X 48")
2	FRESH OIL	(W21-2)	(48" X 48")
10	SHOULDER WORK	(W21-5)	(48" X 48")
2	MOTORCYCLE GROOVE SIGN	(TN-64)	(48" X 48")

13. FOR USE AS TEMPORARY LINE MARKINGS.
14. FOR FINAL PAVEMENT MARKING ONLY.
15. FOR FINAL PAVEMENT MARKING. TO BE IN ACCORDANCE WITH SPECIAL PROVISION 716ST REGARDING SPRAY THERMAL PAVEMENT MARKINGS DATED 07-15-05. THIS ITEM TO BE APPLIED TO THE SCORING OF THE PAVEMENT.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

28-JAN-2014 08:46
\\jj04wf01.tdot.state.tn.us\04SHARED\Design\DESIGN\RESURF REG4 PROJ\HENRY\SR69\LMI3-05-LMI7-28\40069LMI3-05 EST QTYS.dgn