TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	NH/HSIP-69(85)	2

ESTIMATED ROADWAY QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	40006-8206-14 QUANTITY	NH/HSIP-69(85) QUANTITY	TOTAL QUANTITY
	202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	50	0	50
	203-06	WATER	M.G.	1	0	1
1	303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (C OR D)	TON	34	0	34
2	307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	TON	23	0	23
3	307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	TON	239	0	239
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	9	0	9
4 5	411-02.10	ACS MIX(PG70-22) GRADING D	TON	713	0	713
6	415-01.02	COLD PLANING BITUMINOUS PAVEMENT	S.Y.	9681	0	9681
	701-02.01	CONCRETE HANDICAP RAMP (RETROFIT)	S.F.	0	798	798
	712-01	TRAFFIC CONTROL	LS	0.3	0	0.3
7	712-06	SIGNS (CONSTRUCTION)	S.F.	416	0	416
	712-08.03	ARROW BOARD (TYPE C)	EACH	2	0	2
	716-01.23	Snwplwble Pvmt Mrkrs (Bi-Dir)(2 Color)	EACH	0	23	23
8	716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	0	482	482
8	716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	S.Y.	0	18	18
8	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	0	200	200
8	716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH	0	5	5
8	716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	EACH	0	1	1
9	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	1.99	0	1.99
8 10	716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	L.F.	413	0	413
11	716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	L.M.	0	1.99	1.99
	717-01	MOBILIZATION	LS	0.3	0	0.3

FOOTNOTES

1. FOR BREAKOUT ONLY.
2. FOR REPLACEMENT OF QUANTITY REMOVED UNDER ITEM 202-03.01 ONLY.
3. INCLUDES 5 TONS ADDITIONAL PAVEMENT FOR GORE AREAS, TURNLANES, LARGE INTERSECTIONS AND SIDE ROADS.
4. INCLUDES 59 TONS ADDITIONAL PAVEMENT FOR GORE AREAS, TURNLANES, LARGE INTERSECTIONS, SIDE ROADS AND 25 TONS FOR SPOT LEVELING.
5. SEE SPECIAL PROVISION NO. 407G FOR MATERIAL TRANSFER DEVICE.
6. INCLUDES 200 SQ.YD. FOR GORE AREAS, TURNLANES, LARGE INTERSECTIONS AND SIDE ROADS.
7. QUANTITY INCLUDES

2	ROAD WORK NEXT 1 MI.	(G20-1)	(48" X 24")
2	END ROAD WORK	(G20-2)	(48" X 24")
2	UNEVEN LANES	(W8-11)	(48" X 48")
6	ROAD WORK AHEAD	(W20-1)	(48" X 48")
2	ROAD WORK 1500 FT.	(W20-1)	(48' X 48")
2	ROAD WORK 1000 FT.	(W20-1)	(48" X 48")
2	ROAD WORK 500 FT.	(W20-1)	(48" X 48")
2	ONE LANE ROAD AHEAD	(W20-4)	(48" X 48")
2	FLAGGER AHEAD	(W20-7a)	(48" X 48")
2	FRESH OIL	(W21-2)	(48" X 48")
2	MOTORCYCLE GROOVE SIGN	(TN-64)	(48" X 48")
2	SHOULDER WORK	(W21-5)	(48" X 48")

THIS CONSTRUCTION SIGNING IS TO BE AS A MINIMUM. OTHER SIGNS AS DIRECTED BY THE ENGINEER MAY BE REQUIRED DURING DIFFERENT PHASES.

8. FOR FINAL PAVEMENT MARKING ONLY.
9. FOR USE AS TEMPORARY LINE MARKINGS, INCLUDES 1 MILES FOR BREAKOUT, SPOT LEVELING, CITY STREETS AND INTERSECTIONS.
10. INCLUDES 6 PARALLEL AND 13 PERPENDICULAR PARKING SPACES.
11. FOR USE AS FINAL PAVEMENT MARKINGS, INCLUDES 1 MILES FOR CITY STREETS AND TURN LANES.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED ROADWAY QUANTITIES

28-JAN-2014 09:15
\\j04wf01.tdot.state.tn.us\04SHARED\Design\DESIGN\RESURF REG4 PROJ\HENRY\SR69\LMI2-8I-LMI3-03\40069LMI2-8IEST QTYS.dgn