TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	PHSIP/STP-SIP-NH-109(30)	18

PROJECT COMMITMENTS

COMMITMENT ID	SOURCE DIVISON	DESCRIPTION	STA. / LOCATION
EDHZ002	Environmental Division, Hazardous Materials	1.Underground storage tanks (USTs) were abandoned in place on Tract 3 due to telephone and gas utility lines that were on top of the USTs. The abandoned USTs are most likely buried at a depth of between 2 and 4 feet below ground surface (bgs). 2.Contaminated soil is likely to be encountered throughout the project. Any soil that is discolored or exhibits a strong odor should be stockpiled on 3-mil plastic and covered with plastic until characterized. TDOT Environmental Division will be responsible for coordinating the sampling and disposition of the excavated material. Notify the TDOT Hazardous Materials Manager at 615-532-8684 at least two business days prior to beginning excavation. 3.Groundwater is expected to be shallow (less than 5 ft. bgs) and may be contaminated. If groundwater is removed it should be characterized and disposed of properly.	Approx. Sta. 101+15.00± to 101+40.00± Rt.
EDHZ003	Environmental Division, Hazardous Materials	4.Concrete and PVC may be encountered in the vicinity of the former monitoring wells and remediation system wells that were abandoned in place. These may extend down to depths of 10 to 20 feet bgs. 5.It is recommended that all personnel use engineering controls (rubber boots, gloves) and good hygienic practices if they must come into contact with the soil. Contractors should follow their company health and safety plan if contacting potentially contaminated soil.	Approx. Sta. 101+15.00± to 101+40.00± Rt.

SEALED BY

06/17/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PROJECT COMMITMENTS

17-JUN-2014 13:41
\\JJO3WF01.tdot.state.tn.us\03Shared\SURVEY\DESIGN\PIN 114367.01 Sumner Co SR-109 (Donoho Branch)\001B_ProjectCommitments.sht