TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	PHSIP/STP-SIP-NH-109(30)	2D

BOX BRIDGE TABULATION

STATION	LOCATION	SPAN	HEIGHT	LENGTH	SKEW	DRAINAGE AREA ACRES	BOX BRIDGE BOX CLASS "A" CONC. CU. YD.	BOX BRIDGE BOX REINF. STEEL LBS.	CULVERT EXC. CU. YD.	DRAWING NO.	BACKFILLING ITEM 303-01.01 DWG. STD-10-1 TONS	FOUNDATION FILL MATERIAL CU. YD.
101+82	SR-109	2 @ 10' X 5'	7'	6'	64	719	17	3133	476	STD-17-74	13	3
TOTALS							17	3133	476		13	3

CROSS DRAIN TABULATION

STATION	RCP CLASS III 18"	24"	30"	36"	48"	SKEW	RIP-RAP 709-05.06 (TON)	END TREATMENT INLET TYPE	INLET DRAWING NO.	OUTLET TYPE	OUTLET DRAWING NO.	REMARKS
101+45.32	5					78						STUB 18" RCP THRU PROPOSED WING WALL OF CONCRETE BOX BRIDGE
TOTALS	5	0	0	0	0		0					

PAVEMENT QUANTITIES

LOCATION	PAY ITEMS 403-01 (TON)	411-02.10 (TON)	415-01.01 (TON)
STA. 100+85.49 TO STA. 102+45.33	1.0	18.0	14.0
TOTALS	1.0	18.0	14.0

REMOVAL OF SIGNS

LOCATION	DESCRIPTION	SIGN TEXT
SR-109 @ DONOHO BRANCH CULVERT	R9-9L	SIDEWALK CLOSED
SR-109 @ DONOHO BRANCH CULVERT	R9-9R	SIDEWALK CLOSED
SR-52 @ MAPLE STREET INTERSECTION	R9-11L(MOD)	SIDEWALK CLOSED AT BRIDGE CROSS HERE
@ MARKET STREET INTERSECTION	R9-11R(MOD)	SIDEWALK CLOSED AT BRIDGE CROSS HERE

SEALED BY

06/17/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES

7-JUN-2014 13:45
\\JJ03WF01.tdot.state.tn.us\03Shared\SURVEY\DESIGN\PIN 114367.01 Sumner Co SR-109 (Donoho Branch)\002D_Tabulated.sht