SOUTH M3-1

ALL SIGNS SHOWN WITH DESIGNATIONS ARE TO BE FABRICATED AS DETAILED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (CURRENT EDITION)

SEE STD. DWG. NO. T-S-19

SIGN NO	LEGEND	SHEET NO	SIZE				COPY				SHIELD	ARROW	SIGN FACE			STEEL DESIGN (BREAK-AWAY)					MINIMUM VERTICAL CLEARANCE	REMARKS
			LENGTH	HEIGHT	RADIUS	BORDER WIDTH	CAPITAL	LOWER CASE	NUMERAL	SERIES			COPY	BACKGROUND	MATERIAL	SUPPORT TYPE	SUPPORT LENGTH	FOOTING	CONC. CU. YD.	REIN STEEL LBS.		
4	SPEED LIMIT 35 R2-1		30"	36"									BLACK	WHITE (REF.)	0.080" SHEET ALUMINUM	P8	h =12'-6"				5'-0"	
8	W3-3		36"	36"									BLACK RED (REF.) GREEN (REF.)	YELLOW (REF.)	0.100" SHEET ALUMINUM	P8	h =13'-6"				5'-0"	
5	W1-2		36"	36"									BLACK	YELLOW (REF.)	0.100" SHEET ALUMINUM	P8	h =13'-6"				5'-0"	
2	TN-17b MILE 0 345 MILE 0 345 TN-17b		6"	19"									WHITE (REF.)	GREEN (REF.)	0.080" SHEET ALUMINUM	U1	h =9"-0"				5'-0"	MOUNT SIGNS BACK TO BACK
3	NORTH M3-3 345 TN-6B		24" 30"	12" 24"									BLACK	(REF.) WHITE	0.080" SHEET ALUMINUM	P8	h =13'-0"				5'-0"	
1	NORTH M3-3 345 TN-6B M6-1		24" 30" 21"	12" 24" 15"									BLACK	(REF.) WHITE	0.080" SHEET ALUMINUM	P8	h =14'-6"				5'-0"	
6	S↔N TN-39 25E M1-4		30" 30"	15" 24"									BLACK	(REF.) WHITE	0.080" SHEET ALUMINUM	P8	h =13'-0"				5'-0"	
7	M3-1 SOUTH NORTH M3-3 M1-4 25E 25E M1-4 M5-1 M5-1		24" 30" 21"	12" 24" 15"									BLACK	(REF.) WHITE	0.080" SHEET ALUMINUM	P8	h_1=14'-6" h_2=15'-0"				5'-0"	
	Hwy 25E D3-1		66"	18"			8"	6"		"D"			WHITE (REF.)	GREEN (REF.)	0.100" SHEET ALUMINUM							SEE SIGNAL SHEETS FOR DETAILS.
	← Church St D3-1 (MOD.)		84"	18"			8"	6"		"D"		TYPE "A"	WHITE (REF.)	GREEN (REF.)	0.100" SHEET ALUMINUM							
	Church St → D3-1 (MOD.)		84"	18"			8"	6"		"D"		TYPE "A"	WHITE (REF.)	GREEN (REF.)	0.100" SHEET ALUMINUM							
	← Cedar Fork Rd D3-1 (MOD.)		96"	18"			8"	6"		"D"		TYPE "A"	WHITE (REF.)	GREEN (REF.)	0.100" SHEET ALUMINUM							
	Cedar Fork Rd → D3-1 (MOD.)		96"	18"			8"	6"		"D"		TYPE "A"	WHITE (REF.)	GREEN (REF.)	0.100" SHEET ALUMINUM							

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	PHSIP-345(11)	12

U-POST SUBSTITUTION TABLE

BID ITEM 713-11.01	SUBSTITUTION ALLOWED
2#/FT. U1	2#/FT. MU1 OR 2#/FT. R1
2.5#/FT. U3	2.5#/FT. MU3 OR 3#/FT. R2*
3#/FT. U6	
4#/FT. U7	NO SUBSTITUTES

* PAID AT A RATE OF 2.5#/FT.

SEALED BY

ROLAND LEE JONES REGISTERED ENGINEER AGRICULTURE NO. 17 STATE OF TENNESSEE

05-15-14

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULE