TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST	2014	79005-4167-04	3A

PROJECT COMMITMENTS

COMMITMENT ID	SOURCE DIVISION	DESCRIPTION	STA./LOCATION
EDHZ001	ENVIRONMENTAL DIVISION, HAZARDOUS MATERIALS	1. TO MINIMIZE THE RISK TO CONSTRUCTION WORKERS, TDOT IS COMMITTED TO THE REMOVAL OF ASBESTOS CONTAINING MATERIALS (ACM) FROM BRIDGES THAT ARE BEING DEMOLISHED, REHABILITATED OR REPAIRED. 2. BRIDGE NO. 79I00550057, SR-14 BRIDGE OVER I-55, L.M. 7.46, HAS ACM IN THE DECK DRAINS. IF THIS MATERIAL IS DISTURBED DURING REPAIR ACTIVITIES, ABATEMENT SHOULD BE ACCOMPLISHED PER SP202ACM SPECIAL PROVISION REGARDING REMOVAL OF ASBESTOS CONTAINING MATERIALS. ACM ABATEMENT SHOULD BE COMPLETED PRIOR TO ANY DEMOLITION ACTIVITIES. 3. STATE OF TENNESSEE ASBESTOS ACCREDITATION REQUIREMENTS (TCA 1200-01-20) MANDATE THAT ACM ABATEMENT WORK BE PERFORMED BY AN ACCREDITED FIRM (CONTRACTOR) USING ACCREDITED ABATEMENT WORKERS AND SUPERVISORS. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING A NOTICE TO THE TDEC, DIVISION OF AIR POLLUTION CONTROL TEN (10) DAYS IN ADVANCE OF ANY ACM ABATEMENT OR DEMOLITION.	DECK DRAINS

AMJAD S. KHAIRI
REGISTERED ENGINEER
AGRICULTURE
NO. 106650
01/21/14
STATE OF TENNESSEE

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
BUREAU OF PLANNING AND DEVELOPMENT

PROJECT COMMITMENTS

GARVER

LiCobos 1/21/2014 1:28:56 PM
WORKSPACE: TDOT Bridge
L:\2010\001763\- TDOT - Bridge Repair over Interstate 55\Drawings\BRG\Final\03-Sheet 3A.dgn