ALL SIGNS SHOWN WITH DESIGNATIONS ARE TO BE FABRICATED AS DETAILED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (CURRENT EDITION)

SEE STD. DWG. NO. T-S-19

SIGN NO	LEGEND	SHEET NO	SIZE				COPY				SHIELD	ARROW	SIGN FACE			STEEL DESIGN (BREAK-AWAY)					MINIMUM VERTICAL CLEARANCE	REMARKS
			LENGTH	HEIGHT	RADIUS	BORDER WIDTH	CAPITAL	LOWER CASE	NUMERAL	SERIES			COPY	BACKGROUND	MATERIAL	SUPPORT TYPE	SUPPORT LENGTH	FOOTING	CONC. CU. YD.	REIN STEEL LBS.		
13	Brentwood →		8'-0"	2'-0"			8"	6"		EMOD		TYPE "A"	WHITE (REF.)	GREEN (REF.)	2-12" ALUMINUM EXTRUSIONS	S3X5.7	h_1=15'-6" h_2=16'-0"	TYPE 5 D=1'-3"	0.18"	50.1	* 5'-0"	* 5'-0" TO BOTTOM OF M5-1 ARROW
	M3-2 EAST WEST M3-4		24"	12"																		
28	TN-6B 253 253 TN-6B		30"	24"									BLACK	WHITE (REF.)	0.080" SHEET ALUMINUM							
	M6-1 ← → M6-1		21"	15"																		

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	HSIP-I-65-2(97)	10E

U-POST SUBSTITUTION TABLE

BID ITEM 713-11.01	SUBSTITUTION ALLOWED
2#/FT. U1	2#/FT. MUI OR 2#/FT. R1
2.5#/FT. U3	2.5#/FT. MU3 OR 3#/FT. R2*
3#/FT. U6	
4#/FT. U7	NO SUBSTITUTES

* PAID AT A RATE OF 2.5#/FT.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULE