TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	19010-4164-04	2D

TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

ROADWAY GENERAL AND SPECIAL NOTES (CONT'D)

SWPPP, PERMITS, PLANS, RECORDS (CONT'D)

(34) ANY DISAGREEMENT BETWEEN THE PROJECT PLANS, THE PROJECT AS CONSTRUCTED, AND THE PERMIT(S) ISSUED FOR THE PROJECT, SHALL BE BROUGHT TO THE ATTENTION OF THE TDOT PROJECT ENGINEER. THE ENVIRONMENTAL DIVISION, DESIGN DIVISION, AND HEADQUARTERS CONSTRUCTION OFFICE SHALL BE CONTACTED IN THESE INSTANCES AND DECIDE WHICH HAS PRECEDENCE AND WHETHER PERMIT OR PLANS REVISIONS ARE NEEDED. IN GENERAL, PERMIT CONDITIONS WILL PREVAIL.

(35) THE FOLLOWING INFORMATION SHALL BE MAINTAINED ON OR NEAR THE SITE: DATES THAT MAJOR GRADING ACTIVITIES OCCUR, DATES WHERE CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE, DATES WHEN STABILIZATION MEASURES ARE INITIATED, EPSC INSPECTION RECORDS AND PRECIPITATION RECORDS.

(36) ALL WATER QUALITY AND STORM WATER PERMITS, INCLUDING THE LOCATION OF THE SWPPP, SHALL BE POSTED NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE ACCESSIBLE TO THE PUBLIC. IF POSTING THIS INFORMATION NEAR A MAIN ENTRANCE IS INFEASIBLE, THE INFORMATION SHALL BE PLACED IN A PUBLICLY ACCESSIBLE LOCATION NEAR WHERE THE CONSTRUCTION IS ACTIVELY UNDERWAY AND MOVED AS NECESSARY. THIS LOCATION SHALL BE POSTED AT THE CONSTRUCTION SITE.

(37) IF A CHANGE IN PROJECT SCOPE OCCURS DURING CONSTRUCTION, INCLUDING VALUE ENGINEERING, THE ENVIRONMENTAL DIVISION SHALL BE CONTACTED TO DETERMINE WHETHER PERMIT REVISIONS ARE NEEDED. THE DESIGN DIVISION SHALL BE CONTACTED TO DETERMINE IF ANY PLAN REVISIONS ARE NEEDED.

(38) PROJECT INSPECTORS AND SUPERVISORS (INCLUDING TDOT STAFF, CONSULTANTS AND CONTRACTOR STAFF) RESPONSIBLE FOR THE IMPLEMENTATION AND MAINTENANCE OF EPSC PLANS SHALL SUCCESSFULLY COMPLETE THE TDEC "LEVEL I - FUNDAMENTALS OF EROSION PREVENTION AND SEDIMENT CONTROL FOR CONSTRUCTION SITES" COURSE OR EQUIVALENT COURSE. A COPY OF CERTIFICATION RECORDS FOR THIS COURSE SHALL BE KEPT ON SITE AND AVAILABLE UPON REQUEST.

LITTER, DEBRIS, WASTE, PETROLEUM

(39) THE CONTRACTOR SHALL ESTABLISH AND MAINTAIN A PROACTIVE METHOD TO PREVENT LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION WASTES FROM ENTERING WATERS OF THE STATE/U.S.

(40) THE CONTRACTOR SHALL TAKE APPROPRIATE STEPS TO ENSURE THAT PETROLEUM PRODUCTS OR OTHER CHEMICAL POLLUTANTS ARE PREVENTED FROM ENTERING WATERS OF THE STATE/U.S. ALL EQUIPMENT REFUELING, SERVICING, AND STAGING AREAS SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL LAWS, RULES, REGULATIONS, AND ORDINANCES, INCLUDING THOSE OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA). APPROPRIATE CONTAINMENT MEASURES FOR THESE AREAS SHALL BE USED. ALL SPILLS MUST BE REPORTED TO THE APPROPRIATE AGENCY, AND MEASURES SHALL BE TAKEN IMMEDIATELY TO PREVENT THE POLLUTION OF WATERS OF THE STATE/U.S., INCLUDING GROUNDWATER, SHOULD A SPILL OCCUR.

SPECIAL NOTES

(41) NO LESS THAN SEVEN (7) DAYS PRIOR TO THE CLOSURE OF LANES, THE CONTRACTOR SHALL NOTIFY THE FOLLOWING INDIVIDUALS OR AGENCIES COMPLETELY DESCRIBING THE AFFECTED ROADS AND THE APPROXIMATE DURATION OF THE CONSTRUCTION: THESE PARTIES INCLUDE, BUT ARE NOT LIMITED TO: (1) METRO NASHVILLE POLICE DEPARTMENT, (2) METRO NASHVILLE FIRE DEPARTMENT, (3) LOCAL AMBULANCE SERVICE, (4) DAVIDSON COUNTY SCHOOL SUPERINTENDENT, (5) LOCAL POSTAL SERVICE, (6) TDOT REGION 3 TRAFFIC ENGINEERING OFFICE, (7) METRO PUBLIC WORKS, AND (8) METRO TRANSIT AUTHORITY.

(42) COST OF PROVIDING CONTAINMENT OF DEBRIS AND OVERSPRAY SHALL NOT BE PAID FOR DIRECTLY BUT SHALL BE INCLUDED IN THE OTHER ITEMS OF CONSTRUCTION.

NASHVILLE & EASTERN RAILROAD NOTES

(43) THE CONTRACTOR SHALL NOT, FOR ANY REASON, STORE CONSTRUCTION EQUIPMENT UPON NOR STORE OR DUMP WASTE CONSTRUCTION MATERIALS UPON THE RAILROAD'S RIGHTS-OF-WAY.

(44) THE CONTRACTOR SHALL CONDUCT HIS WORK SO AS TO PROTECT THE RAILROAD'S TRACK FACILITIES AND PROPERTY FROM DAMAGE AND ANY WORK BY THE CONTRACTOR OVER OR WITHIN 25 FEET OF THE RAILROAD'S R.O.W WILL, AT THE DISCRETION OF THE RAILROAD, REQUIRE THE PRESENCE AND PERMISSION OF AN AUTHORIZED RAILROAD WATCHMAN OR FLAGGER.

(45) SEE SPECIAL PROVISION 105C(SL) TO SET UP FLAGGING SERVICES AND SUBMIT FOR INSURANCE REQUIRED FOR WORK AT OR OVER THE RAILROAD ON THIS PROJECT.

(46) THE CONTRACTOR SHALL COORDINATE HIS WORK OVER THE RAILROAD'S TRACKS WITH THE FOLLOWING REPRESENTATIVES OF THE RAILROAD:

NASHVILLE & EASTERN RAILWAY:
MR. WILLIAM J. DRUNSIC, PRESIDENT
NASHVILLE & EASTERN RAILROAD CORPORATION
5138 MAIN STREET
BATTEN SHIRE BLDG.
MANCHESTER CENTER, VT 05255
PHONE: (800) 722-8725 (EXT.#1)
FAX: (802) 362-1918

MR. CRAIG WADE, VICE PRES & GENERAL MANAGER
NASHVILLE & EASTERN RAILROAD CORPORATION
514 KNOXVILLE AVENUE
LEBANON, TN 37087
PHONE: (615) 444-1567
FAX: (615) 444-4682
CELL: (615) 445-5353

JAMES R. GILLESPIE JR.
REGISTERED ENGINEER
NO. 102630
STATE OF TENNESSEE
03/11/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

BRIDGE NO. 19-I24-15.42LT
BRIDGE NO. 19-I24-15.42RT
INTERSTATE 24 OVER
CUMBERLAND RIVER
DAVIDSON COUNTY
2014

ROADWAY
GENERAL AND
SPECIAL NOTES