TENNESSEE D.O.T.
DESIGN DIVISION
FILE NO.

TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2014	19010-4164-04	1B

(1) 05-05-14 JRG ADDED SHEET DRAWING TO SET OF PLANS

PROJECT COMMITMENTS

COMMITMENT TO	SOURCE DIVISION	DESCRIPTION	STA./LOCATION
-------	ENVIRONMENTAL DIVISION, ENVIRONMENT	BRIDGE# 19I00240119 (I-24 RT OVER CUMBERLAND RIVER, 19-I0024-15.42 RT) AND BRIDGE# 19I00240120 (I-24 LT OVER CUMBERLAND RIVER, 19-I0024-15.42 LT), HAVE ASBESTOS CONTAINING MATERIAL (ACM) IN THE TEXTURE COAT ON ALL SURFACES EXCEPT THE INSIDE FACE OF THE PARAPETS. IF THE ACM WILL BE DISTURBED DURING REPAIR ACTIVITIES, SPECIAL PROVISION 202ACM, SPECIAL PROVISION REGARDING REMOVAL OF ASBESTOS CONTAINING MATERIAL, SHOULD BE INCLUDED IN BID DOCUMENTS. STATE OF TENNESSEE ASBESTOS ACCREDITATION REQUIREMENTS (TCA 1200-01-20) MANDATE THAT ACM ABATEMENT WORK BE PERFORMED BY AN ACCREDITED FIRM (CONTRACTOR) USING ACCREDITED ABATEMENT WORKERS AND SUPERVISORS. A NOTICE TO THE TDEC, DIVISION OF AIR POLLUTION CONTROL IS REQUIRED TEN (10) DAYS IN ADVANCE OF ANY ACM ABATEMENT ACTIVITIES IF THE ASBESTOS CONTAINING TEXTURE COAT TO BE REMOVED EXCEEDS 160 SQUARE FEET.	LM 15.42

JAMES R. GILLESPIE JR.
REGISTERED ENGINEER
AGRICULTURE
COMMERCE
NO. 102630
STATE OF TENNESSEE
05/05/2014

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

BRIDGE NO. 19-I24-15.42LT
BRIDGE NO. 19-I24-15.42RT
INTERSTATE 24 OVER
CUMBERLAND RIVER
DAVIDSON COUNTY
2014

PROJECT COMMITMENTS