CONST. NO. 19005-3161-44

PROJECT NO.	YEAR	SHEET NO.
BH-I-40-4(86)	2015	

REVISIONS

NO.	DATE	BY	BRIEF DESCRIPTION

Superstructure (Epoxy)

Location	Bar	Size	Quantity	Length
Left	B570E	5	200	3.3330
Cantilever	A5 T	5	7	70.0000
	A5 B	5	6	70.0000
Median	M470E	4	12	7.5000
	A5 T	5	19	70.0000
	A5 B	5	16	70.0000
	A6 T&B	6	90	17.2500
Right	B570E	5	200	3.3330
Cantilever	A5 T	5	8	70.0000
	A5 B	5	5	70.0000
Closure	A5	5	52	70.0000
Pour				
Joints				
Bents	A6	6	12	11.5000
(Each)	Dowell	6	24	3.0000
	L4B	4	22	9.0000
	L4C	4	4	8.5000
	H4	4	4	15.0000

NOTE: BAR LENGTHS SHOWN INCLUDE SPLICE LENGTH WHERE APPROPRIATE. FINAL BAR CUT LENGTH DETERMINED BY FABRICATOR.



BRIDGE NO. 4

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

BILL OF STEEL

I-40
OVER
JO JOHNSTON AVE.
BR. NO. 19-I0040-16.88
DAVIDSON COUNTY
2015

BR-119-175

DESIGNED BY GRESHAM SMITH & PARTNERS DATE 2/09/2015
DRAWN BY R. PALMER DATE 1/2015
SUPERVISED BY T. KNIAZEWYCZ DATE 1/2015
CHECKED BY T. KNIAZEWYCZ DATE 2/2015

GRESHAM SMITH AND PARTNERS

kniazet
Q:\2807115\b\Bridge C Jo Johnston\bridge 1\8071b15cblr1.sht
2/13/2015
PRF