TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	BH-I-40-4(86)	42A

ROADWAY LIGHTING AND LUMINAIRE SCHEDULE

SHEET NO.	POLE NO.	STA.	ROADWAY	MTG. HGT.	TYPE FIXTURE	IES TYPE	NO. FIXTURES	WATT / FIXTURE	SERVICE	CIRCUIT	FOUNDATION TYPE	COMMENTS
	1	EXISTING	I-40	EXISTING	HPS	III	1	250 W	A	3	EXISTING	TO REMAIN
	2	EXISTING	I-40	EXISTING	HPS	III	1	250 W	A	4	EXISTING	TO REMAIN
	3	EXISTING	I-40	EXISTING	HPS	III	1	250 W	A	3	EXISTING	TO REMAIN
	4	EXISTING	I-40	EXISTING	HPS	III	1	250 W	A	4	EXISTING	REMOVE POLE ONLY DURING CONST SEE NOTE 4
	5	1025+80	I-40	EXISTING	HPS	III	1	250 W	A	4	BRIDGE	FIXTURE ON BRIDGE SEE NOTE 1 BELOW
	6	1026+96	I-40	40	HPS	III	1	250 W	A	3	BRIDGE	NEW FIXTURE ON BRIDGE SEE NOTE 2 BELOW
	7	1028+46	I-40	EXISTING	HPS	III	1	250 W	A	3	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	8	1029+47	I-40	EXISTING	HPS	III	1	250 W	A	4	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	9	1030+85	I-40	EXISTING	HPS	III	1	250 W	A	3	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	10	1032+22	I-40	EXISTING	HPS	III	1	250 W	A	4	BRIDGE	FIXTURE ON BRIDGE SEE NOTE 1 BELOW
	11	1033+44	I-40	EXISTING	HPS	III	1	250 W	A	3	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	12	1034+57	I-40	EXISTING	HPS	III	1	250 W	A	4	BRIDGE	FIXTURE ON BRIDGE SEE NOTE 1 BELOW
	13	1035+65	I-40	EXISTING	HPS	III	1	250 W	A	3	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	14	1036+81	I-40	EXISTING	HPS	III	1	250 W	A	4	BARRIER WALL	REPLACE ON NEW BARRIER WALL
	15	1037+70	I-40	EXISTING	HPS	III	1	250 W	A	3	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	16	1038+95	I-40	EXISTING	HPS	III	1	250 W	A	4	BRIDGE	FIXTURE ON BRIDGE SEE NOTE 1 BELOW
	17	1039+93	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	18	1041+32	I-40 ON RAMP	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	18A	1041+95	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	19	1041+44	I -40 OFF RAMP	EXISTING	HPS	III	1	250 W	A	4	BARRIER WALL	REPLACE ON NEW BARRIER WALL
	20	1044+62	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	21	1045+44	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	22	1047+05	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	23	1048+05	I-40	EXISTING	HPS	III	1	250 W	A	1	CONCRETE FOOTER	REMOVE AND RE-INSTALL - SEE NOTE 1
	24	1049+45	I-40	EXISTING	HPS	III	1	250 W	A	1	BRIDGE	FIXTURE ON BRIDGE SEE NOTE 1 BELOW
	25	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	26	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	27	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	28	1043+47	I -40 OFF RAMP	EXISTING	HPS	III	1	250 W	A	4	BARRIER WALL	REPLACE ON NEW BARRIER WALL
	29	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	30	EXISTING	I -40 OFF RAMP	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN - SEE NOTE 5
	31	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	32	EXISTING	12TH AVE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	33	EXISTING	CHARLOTTE	EXISTING	HPS	III	1	250 W	A	2	EXISTING	TO REMAIN
	34	EXISTING	G L DAVIS BLVD	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	35	EXISTING	G L DAVIS BLVD	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	36	EXISTING	G L DAVIS BLVD	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	37	EXISTING	G L DAVIS BLVD	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	38	EXISTING	G L DAVIS BLVD	EXISTING	HPS	III	1	400 W	A	1	EXISTING	TO REMAIN
	39	EXISTING	I40 ON RAMP	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	40	EXISTING	I40 ON RAMP	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	41	EXISTING	I40 ON RAMP	EXISTING	HPS	III	1	250 W	A	1	EXISTING	TO REMAIN
	42	1025+37	HERMAN	17'	WALLPACK	III	1	150 W	A	1	PIER WALL	NEW SURFACE MOUNT WALL PACKS
	43	1025+37	HERMAN	17'	WALLPACK	III	1	150 W	A	1	PIER WALL	NEW SURFACE MOUNT WALL PACKS
	44	31+40	CLINTON	17'	WALLPACK	III	1	150 W	A	1	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS
	45	32+05	CLINTON	17'	WALLPACK	III	1	150 W	A	1	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS
	46	41+55	JO JOHNSON	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	47	42+30	JO JOHNSON	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	48	51+93	CHARLOTTE	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	49	50+95	CHARLOTTE	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	50	52+05	CHARLOTTE	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	51	51+18	CHARLOTTE	17'	WALLPACK	III	1	150 W	A	3	BRIDGE WALL	NEW SURFACE MOUNT WALL PACKS - SEE NOTE 3
	52	1050+48	I-40	EXISTING	HPS	III	1	400 W	B	*	BRIDGE	SEE NOTE 4

(1) EXSITING LIGHT FIXTURES 5 THRU 24 AND 28 ARE TO BE REMOVED, STORED AND RE-INSTALLATION ONCE BRIDGE AND ROAD CONSTRUCTION IS COMPLETED.
(2) EXISTNG LIGHT FIXTURE ON BRIDGE FOUNDATION IS MISSING. NEW POLE AND FIXTURE WILL BE INSTALLED ON NEW BRIDGE AT THIS LOCATION
(3) EXISITNG WALL PACK FIXTURES SHALL BE REMOVED AND REPLACED WITH NEW SURFACE MOUNT WALL PACK FIXTURES
(4) POLE TO BE REMOVED FOR BRIDGE CONSTRUCTION. ONCE BRIDGE CONSTRUCTION IS COMPLETE POLE IS TO BE REINSTALLED.
(5) POLE SERVICE IS FED OVER HEAD FROM FIXTURE 30. THIS SERVICE IS TO BE REINSTALLED ONCE POLES ARE RE-INSATLLED.
(6) NEW FOUNDATIONS SHALL BE INSTALLED FOR FIXTURES 7, 8, 9, 11, 13, 15, 17, 18, 18A, 20, 21, 22, 23

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

LIGHTING SCHEDULE

2/10/2015 10:30:59 PM
0:\280715\+\Lighting\L01.sht