TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2015	BH-I-40-4(86)	2N-1

REV. 02/12/15:
SHEET ADDED TO PLAN SET.

REV. 02/19/15:
UPDATED QUANTITIES FOR ITEM NO.'S 203-01 AND 303-10.04.

ESTIMATED GRADING QUANTITIES

LOCATION	ROAD AND DRAINAGE EXC. (UNCL.) 203-01 C.Y.	UNDERCUTTING 203-05 C.Y.	GRANULAR BACKFILL (RETAINING WALLS) 303-01.03 TON	MINERAL AGGREGATE (SIZE 57 OR SIZE 4) 303-10.04 TON
RETAINING WALL #1	2669	2161	3781	10686
RETAINING WALL #2	403	1030	1802	
RETAINING WALL #3	1646	4202	7354	
M.L. I-40 (CSX AND CLINTON)				18781
RETAINING WALL #4	2872	2417	4230	11357
RETAINING WALL #5	2745	2484	4346	10318
RETAINING WALL #6	2338	2297	4020	8246
RETAINING WALL #7	2127	2450	4287	1825
RETAINING WALL #8	2245	2244	3927	7377
TEMP. CONST. ENTRANCE	331			
EROSION & SEDIMENT CONTROL	72			73
TOTALS	17447	19285	33749	68663

PROPOSED BARRIER WALL

SHEET NO.	LOCATION	SIDE			STATION		BARRIER WALL			
		LT	CL	RT	FROM	TO	32IN SINGLE SLOPE 711-05.70 (L.F.)	FLARED SINGLE SLOPE 711-05.77 (L.F.)	32IN HALF SINGLE SLOPE 711-05.81 (L.F.)	CONC. MEDIAN BARRIER (MOD.) 711-01.01 (L.F.)
5A	I-40		X		1021+54	1021+64				10
5A	I-40		X		1021+64	1024+55	291			
5A	I-40		X		1028+00	1028+95		95		
5A,6A	I-40		X		1028+95	1031+67	272			
6A	I-40		X		1032+51	1034+03	152			
6A	I-40	X			1032+51	1033+97	146			
6A	I-40			X	1032+51	1034+09	158			
6A	I-40		X		1034+81	1038+53	372			
6A	I-40			X	1034+88	1035+40	52			
6A	I-40			X	1035+40	1038+08			268	
6A	I-40			X	1038+08	1038+70	62			
6A	I-40		X		1039+21	1041+70	249			
6A	I-40			X	1039+39	1039+99	60			
6A,7A	I-40		X		1041+70	1042+50		80		
7A	I-40		X		1042+50	1048+22	575			
7A	I-40		X		1048+22	1049+02		80		
7A	I-40		X		1049+02	1049+44	42			
7A	I-40		X		1050+76	1054+55	379			
7A	I-40		X		1054+55	1054+65				10
TOTALS							2810	255	268	20

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES

2/19/2015 9:30:11 AM
Q:\2807115\T\002N1.sht