SPECIAL NOTES

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2015	STP/HSIP-1(334)	6
		93001-3262-94 93001-8262-14	
		18002-3231-94 18002-8231-14	

TRAFFIC CONTROL

(1) THE CONTRACTOR SHALL COMPLY WITH SECTION 712 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION REGARDING TEMPORARY TRAFFIC CONTROL AND THE CURRENT EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

(2) SHOULD A FLAGGING OPERATION FOR TRAFFIC CONTROL BE UTILIZED FOR RESURFACING, THE CONTRACTOR SHALL MAKE PROVISIONS TO SAFELY CONTROL TRAFFIC INGRESS AT ALL ROADWAY ENTRANCES WITHIN THE FLAGGED WORK ZONE TO THE SATISFACTION OF THE ENGINEER, ALL COST ASSOCIATED WITH THE CONTROLS WILL BE INCLUDED IN THE PRICE BID FOR TRAFFIC CONTROL.

(3) EXISTING CONSTRUCTION, REGULATORY AND WARNING SIGNS WHICH CONFLICT WITH THE CONSTRUCTION SIGNING SHALL BE REMOVED DURING CONSTRUCTION AND REINSTALLED AS DIRECTED BY THE ENGINEER. ALL COSTS TO BE INCLUDED IN THE PRICE BID FOR ITEM NO. 712-01, TRAFFIC CONTROL, PER LUMP SUM.

(4) THE CONTRACTOR SHALL GIVE THE TDOT PROJECT SUPERVISOR A MINIMUM OF SEVEN (7) DAYS NOTICE PRIOR TO STARTING WORK SO THAT SUFFICIENT NOTICE CAN BE PREPARED AND DISTRIBUTED TO THE MEDIA.

(5) IMMEDIATELY UPON COMPLETION OF EACH CONSTRUCTION PHASE, ALL TRAFFIC CONTROL ITEMS THAT ARE NOT NECESSARY FOR THE SUCCEEDING PHASE SHALL BE REMOVED, COVERED OR TURNED TO FACE AWAY FROM TRAFFIC.

(6) THE CONTRACTOR SHALL PROVIDE FLAGGER AT EACH SIDEROAD WITHIN THE PAVING OPERATION.

LANE CLOSURES

(7) THE RESTRICTION OF TRAFFIC TO ONE LANE SHALL NOT EXCEED ONE DAY'S PAVING OPERATION.

(8) THE CONTRACTOR SHALL KEEP ALL TRAFFIC LANES OPEN TO TRAFFIC DURING NON-WORKING HOURS AND/OR NON-WORK DAYS.

(9) OVERNIGHT LANE CLOSURES WILL NOT BE ALLOWED UNLESS DIRECTED BY THE TDOT PROJECT SUPERVISOR.

(10) THE CONTRACTOR SHALL SCHEDULE PAVING OPERATIONS TO PREVENT INTERRUPTION OF SCHOOL TRAFFIC DURING MORNING START AND AFTERNOON DISMISSAL.

(11) THE CONTRACTOR SHALL NOT BE ALLOWED TO INTERRUPT TRAFFIC FLOW AND SHALL MAINTAIN ALL LANES OF TRAFFIC IN EACH DIRECTION ON THE FOLLOWING DAYS:

A. OFFICIAL STATE HOLIDAYS.

B. FRIDAY AT 6:00 PM UNTIL TUESDAY AT 7:00 AM, IF A STATE HOLIDAY OCCURS OR IS OBSERVED ON MONDAY.

C. THURSDAY AT 6:00 PM UNTIL MONDAY AT 7:00 AM, IF A STATE HOLIDAY OCCURS OR IS OBSERVED ON FRIDAY.

D. DURING LOCAL FESTIVALS, GAMES OR EVENTS THAT COULD BE IMPEDED BY THE PAVING OPERATIONS WHERE AND AS DIRECTED BY THE TDOT PROJECT SUPERVISOR.

PAVING

(12) ALL SURPLUS PATCHING AND JOINT MATERIAL IS TO BE REMOVED BEFORE PLACING TACK COAT AND SURFACE. THIS WORK WILL NOT BE MEASURED AND PAID FOR DIRECTLY, BUT WILL BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF CONSTRUCTION.

(13) MATERIAL TRANSFER DEVICE (MTD) TO BE USED ON ALL MIXES. COST TO BE INCLUDED IN THE UNIT PRICE BID ON ASPHALT PAVEMENT ITEMS. SEE SPECIAL PROVISION 407G.

(14) ANY QUANTITY REMAINING ON ITEMS COMPLETED PRIOR TO THE PAVING OPERATION WILL NOT BE CONVERTED TO ADDITIONAL ASPHALT FOR THE ROADWAY.

(15) ITEM NO. 303-01, CRUSHED STONE FOR SHOULDERS, IS TO BE PLACED TO EXISTING SHOULDER WIDTH OR AS DIRECTED BY THE TDOT PROJECT SUPERVISOR. ALL COSTS OF CONSTRUCTING SHOULDERS, SHAPING OR CLIPPING OF EXISTING SHOULDERS AND DISPOSAL OF ANY DEBRIS FROM SHOULDER CLIPPING ARE TO BE INCLUDED IN THE UNIT BID PRICE FOR ITEM NO. 303-01.

COLD PLANING

(16) THE CONTRACTOR WILL BE REQUIRED TO PAVE THE COLD PLANED PAVEMENT WITHIN A PERIOD OF 48 HOURS.

(17) PROVIDED THAT THE CONTRACTOR USES A COLD PLANED PLANNING MACHINE WITH THE MILLING DRUM SPECIFICATIONS OF CLOSELY SPACED FINE TOOTH (5/16 INCHES OR SMALLER) MILLING DRUM, MOVING FORWARD AT MODERATE SPEED (50 TO 65 FPM.) AND THE UNDER SURFACE REMAINS INTACT (HAVING NO LOOSE MATERIAL OR GOUGES,) THEN THE CONTRACTOR MAY GET PERMISSION FROM REGION 2 CONSTRUCTION TO MILL ALL SURFACES BEFORE COVERING WITH BITUMINOUS MATERIAL.

(18) ALL COLD PLANED MATERIAL IS TO BECOME THE PROPERTY OF THE CONTRACTOR.

(19) IF SUBSURFACE PAVEMENT FAILURE IS EXPOSED AFTER MILLING, REMOVE AREA OF FAILURE TO SOUND PAVEMENT AND REPLACE WITH "THIN LIFT D" MIX PRIOR TO PROPOSED OVERLAY.

(20) AT THE COMPLETION OF COLD PLANING OPERATION, ANY DEPRESSIONS WILL BE CLEANED AND BROUGHT TO PROPER GRADE WITH "THIN LIFT D" MIX MATERIAL. THE COST OF THE CLEAN UP WILL BE INCLUDED IN THE UNIT PRICE FOR "THIN LIFT D" MIX MATERIAL.

PAVEMENT MARKING

(21) THE CONTRACTOR IS RESPONSIBLE FOR THE LAYOUT OF ALL PAVEMENT MARKING. ANY CHANGE FROM THE EXISTING PAVEMENT MARKINGS MUST BE APPROVED BY THE REGION 2 TRAFFIC MANAGER.

(22) EXISTING PAVEMENT MARKINGS IN THE SIDE ROAD RADII SHALL BE RE-TRACED AS DIRECTED BY THE TDOT PROJECT SUPERVISOR DURING FINAL STRIPING.

(23) TEMPORARY PAVEMENT LINE MARKINGS ON INTERMEDIATE LAYERS OF PAVEMENT AND TAPERED JOINTS SHALL BE REFLECTIVE TAPE OR REFLECTORIIZED PAINT INSTALLED TO PERMANENT STANDARDS BEFORE DARK HOURS, SHORT UNMARKED SECTIONS SHALL NOT BE ALLOWED. THESE MARKINGS WILL BE MEASURED AND PAID FOR UNDER ITEM NO. 716-05.01, PAINTED PAVEMENT MARKING (4") LINE.

CLEANING DITCHES

(24) DITCHES MAY NEED TO BE CLEANED OUT AS DIRECTED BY THE TDOT PROJECT SUPERVISOR. ALL COST ASSOCIATED WITH CLEANING DITCHES TO BE INCLUDED IN OTHER ITEMS.

(25) THE CONTRACTOR SHALL TAKE APPROPRIATE STEPS BEFORE CLEANING OUT OR REMOVAL/REPLACEMENT OF DITCHES, SIDEDRAINS, AND CROSSDRAINS, TO ENSURE THAT THE DRAINAGE FEATURES/ WATER-COURSES ARE NOT STREAMS OR WETLANDS. IF THE CONTRACTOR/TDOT INSPECTOR IS UNSURE WHETHER THE DRAINAGE FEATURES ARE STREAMS OR WETLANDS, THE INSPECTOR SHALL CONTACT THE TDOT ENVIRONMENTAL DIVISION, PERMITS SECTION TO OBTAIN THE APPROPRIATE PERMITS.

NPDES

(26) DUE TO THE TYPE OF WORK, IT IS OUR UDERSTANDING THAT THE PROJECT WILL NOT DISTURB MORE THAN ONE ACRE. IF THE DISTURBED ARE IS MORE THAN ONE ACRE, PLEASE CONTACT THE TDOT ENVIRONMENTAL DIVISION, PERMITS SECTION BECAUSE A NPDES PERMIT WILL BE REQUIRED.

MISCELLANEOUS

(27) TIME ON THE PROJECT WILL START THE DAY THAT CONSTRUCTION SIGNS ARE PUT UP OR IN ACCORDANCE WITH SP108B IF A MAXIMUM AMOUNT OF CALENDAR DAYS IS SPECIFIED.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SPECIAL NOTES

02-DEC-2014 14:02
\\JU02WF01.tdot.state.tn.us\02Shared\Design County Folders\Design Resurfacing Folders\Resurf 2015\2015 State Routes\FF20-1(2014) Cumberland-White-1\006_Cumb-White-1_SN.dgn