

Technical Appendices

Programmatic Categorical Exclusion Reevaluation

State Route 193

(Macon Road), Bridge over Branch, LM 11.48 (IA)

Fayette County

PIN 128113.02

State Transportation Improvement Program Fiscal Years 2017-2020

STIP Project List

STIP # 1799001 **TDOT PIN #** **LENGTH IN MILES** **LEAD AGENCY** TDOT
COUNTY STATEWIDE - RURAL **TOTAL PROJECT COST** \$426,000,000
ROUTE
TERMINI SURFACE TRANSPORTATION BLOCK GRANT PROGRAM (STBGP) - GROUPING
PROJECT DESCRIPTION SEE APPENDIX STATE GROUPING DESCRIPTION FOR A COMPREHENSIVE LISTING OF ACTIVITIES INCLUDED BUT NOT LIMITED FOR ELIGIBILITY
REMARKS



COUNTY MAP

FY	PHASE	FUNDING	TOTAL FUNDS	FED FUNDS	STATE FUNDS	LOCAL FUNDS
2017	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2018	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2019	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2020	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	



VICINITY MAP

ALL SCHEDULES SUBJECT TO AVAILABILITY OF FUNDS

Grouping Category	Function of Grouping Activities	Allowable Work Types
<p>Surface Transportation Block Grant Program (STBG) Grouping</p> <p>STIP# 1799001</p>	<p>Projects and programs for the preservation and improvement of the conditions and performance of Federal-aid highways and public roads, including:</p> <ul style="list-style-type: none"> • Rehabilitation, resurfacing, restoration, preservation, and operational improvements on Federal-aid highways and designated routes of the Appalachian Development Highway System (ADHS) and local access roads under 40 USC 14501, • Traffic operations on Federal-aid highways, • Bridge and tunnel improvements on public roads, • Safety improvements on public roads, • Environmental mitigation • Scenic and historic highway programs, • Landscaping and scenic beautification, 	<p>Activities previously authorized under the Surface Transportation Program (STP):</p> <ul style="list-style-type: none"> • Minor rehabilitation, pavement resurfacing, preventative maintenance, restoration, and pavement preservation treatments to extend the service life of highway infrastructure, including pavement markings and improvements to roadside hardware or sight distance • Highway improvement work including slide repair, rock fall mitigation, drainage repairs, or other preventative work necessary to maintain or extend the service life of the existing infrastructure in a good operational condition • Minor operational and safety improvements to intersections and interchanges such as adding turn lanes, addressing existing geometric deficiencies, and extending on/off ramps • Capital and operating costs for intelligent transportation systems (ITS) and traffic monitoring, management, and control facilities and programs: <ul style="list-style-type: none"> ○ Infrastructure-based intelligent transportation systems (ITS) capital improvements ○ Traffic Management Center (TMC) operations and utilities ○ Freeway service patrols ○ Traveler information • Bridge and tunnel construction (no additional travel lanes), replacement, rehabilitation, preservation, protection, inspection, evaluation, and inspector training and inspection and evaluation of other infrastructure assets, such as signs, walls, and drainage structures • Development and implementation of a State Asset Management Plan including data collection, maintenance and integration, software costs, and equipment costs that support the development of performance-based management systems for infrastructure • Rail-highway grade crossing improvements • Highway safety improvements: <ul style="list-style-type: none"> ○ Installation of new or improvement of existing guardrail ○ Installation of traffic signs and signals/lights ○ Spot safety improvements • Sidewalk improvements • Pedestrian and/or bicycle facilities • Traffic calming and traffic diversion improvements • Transportation Alternatives as defined by 23 USC 213(B), 23 USC. 101(A)(29), and Section 1122 of MAP-21 • Noise walls • Wetland and/or stream mitigation • Environmental restoration and pollution abatement • Control of noxious weeds and establishment of native species <p>Activities previously authorized under the Transportation Enhancement Program:</p>

Appendices

<p>Surface Transportation Block Grant Program (STBG) Grouping</p> <p>(continued)</p> <p>STIP# 1799001</p>	<ul style="list-style-type: none"> ● Historic preservation, ● On- and off-road pedestrian and bicycle facilities, ● Infrastructure projects for improving non-driver access to public transportation and enhanced mobility, ● Community improvement activities, ● Recreational Trail Program projects, ● Safe Routes to School (SRTS) projects, ● Transportation Enhancement projects, ● Transportation Alternatives projects, ● Projects for the creation, rehabilitation, and maintenance of multi-use recreational trails. 	<ul style="list-style-type: none"> ○ Pedestrian and bicycle facilities, safety, and educational activities ○ Acquisition of scenic easements and scenic or historic sites ○ Scenic or historic highway programs ○ Landscaping and other scenic beautification activities ○ Historic preservation ○ Rehabilitation and operation of historic transportation buildings, structures, or facilities ○ Preservation of abandoned railway corridors ○ Inventory, control, and removal of outdoor advertising ○ Archaeological planning and research ○ Environmental mitigation to address water pollution due to highway runoff or reduce vehicle-caused wildlife mortality while maintaining habitat connectivity ○ Establishment of transportation museums ○ Activities under the Tennessee Roadscapes grant program, including landscaping, irrigation, benches, trash cans, paths and signage <p>Activities previously authorized under the Safe Routes to School Program (SRTS):</p> <ul style="list-style-type: none"> ● Sidewalk improvements ● Traffic calming and speed reduction improvements ● Pedestrian and bicycle crossing improvements ● On-street bicycle facilities ● Off-street bicycle and pedestrian facilities ● Secure bicycle parking facilities ● Traffic diversion improvements approximately within 2 miles of a school location ● Non-infrastructure related activities: <ul style="list-style-type: none"> ○ Public awareness campaigns and outreach to press and community leaders ○ Traffic education and enforcement in the vicinity of schools <ul style="list-style-type: none"> ▪ Student sessions on bicycle and pedestrian safety, health, and environment ▪ Funding for training, volunteers, and managers of safe routes to school program <p>Activities previously authorized under the Transportation Alternatives Program (TAP):</p> <ul style="list-style-type: none"> ● Construction, planning, and design of on-road and off-road trail facilities for pedestrians, bicyclists, and other non-motorized forms of transportation, including: <ul style="list-style-type: none"> ○ Sidewalk improvements ○ Bicycle infrastructure ○ Pedestrian and bicycle signals ○ Traffic calming techniques ○ Lighting and other safety-related infrastructure
--	--	--

Appendices

<p>Surface Transportation Block Grant Program (STBG) Grouping</p> <p>(continued)</p> <p>STIP# 1799001</p>	<ul style="list-style-type: none"> ● Projects for the planning, design or construction of boulevards and other roadways largely in the right-of-way of former Interstate System routes or other divided highways. 	<ul style="list-style-type: none"> ○ Transportation projects to achieve compliance with the Americans with Disabilities Act of 1990 ● Construction, planning, and design of infrastructure-related projects and systems that will provide safe routes for non-drivers, including children, older adults, and individuals with disabilities to access daily needs ● Conversion and use of abandoned railroad corridors for trails for pedestrians, bicyclists, or other non-motorized transportation users ● Construction of turnouts, overlooks, and viewing areas ● Community improvement activities, which include but are not limited to: <ul style="list-style-type: none"> ○ Inventory, control, or removal of outdoor advertising ○ Historic preservation and rehabilitation of historic transportation facilities ○ Vegetation management in transportation rights-of-way to improve roadway safety, prevent invasive species, and provide erosion control ○ Archaeological activities relating to impacts from implementation of a transportation project eligible under Title 23 of the USC ● Any environmental mitigation activity, including pollution prevention and pollution abatement activities and mitigation to: <ul style="list-style-type: none"> ○ Address stormwater management, control, and water pollution prevention or abatement related to highway construction or due to highway runoff ○ Reduce vehicle-caused wildlife mortality or to restore and maintain connectivity among terrestrial or aquatic habitats ● Recreational Trails Program activities under 23 USC 206 ● SRTS Program infrastructure-related projects, non-infrastructure-related activities (such as pedestrian and bicycle safety and educational activities advanced under the SRTS program), and SRTS Coordinator positions. ● Planning, designing, or constructing boulevards and other roadways largely in the right-of-way of former Interstate System routes or other divided highways <p>Activities previously authorized under the Recreational Trails Program (RTP):</p> <ul style="list-style-type: none"> ● Maintenance and restoration of existing recreational trails ● Development and rehabilitation of trailside and trailhead facilities and trail linkages for recreational trails ● Purchase and lease of recreational trail construction and maintenance equipment ● Construction of new recreational trails ● Acquisition of easements and fee simple title to property for recreational trails or recreational trail corridors ● Assessment of trail conditions for accessibility and maintenance ● Development and dissemination of publications and operation of educational programs to promote safety and environmental protection ● Payment of costs to the State incurred in administering the program
---	--	---

Project Development

TENNESSEE
DEPARTMENT OF TRANSPORTATION



TRANSPORTATION INVESTMENT REPORT


Improve Act
SR-193 (Macon Road)
Bridge over Unknown Branch,
Bridge ID 24015420001
Log Mile 11.48 Fayette County
PIN 124285.00

PREPARED BY PALMER ENGINEERING for
Strategic Transportation Investments Division


Approved by Toks Onyiah Date 3-27-18 Approved by Paul D. Dwyer Date 3/23/18
Chief of Environment and Planning Deputy Commissioner and Chief Engineer

Approved by:	Signature	DATE
TRANSPORTATION DIRECTOR STRATEGIC TRANSPORTATION INVESTMENTS DIVISION		3-22-18
ENGINEERING DIRECTOR DESIGN DIVISION		03/22/18
ENGINEERING DIRECTOR STRUCTURES DIVISION		3/23/18

This document is covered by 23 USC § 409 and its production pursuant to fulfilling public planning requirements does not waive the provisions of § 409.




**BRIDGE ID 24015420001
(BRIDGE OVER UNKNOWN BRANCH)**





Sources: Esri, HERE, DeLorme, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), MapmyIndia, NGCC, © OpenStreetMap contributors, and the GIS User Community




**AREA MAP
SR-193 BRIDGE OVER
UNKNOWN BRANCH (LM 11.48)
FAYETTE COUNTY**






**BRIDGE ID 24015420001
(BRIDGE OVER UNKNOWN BRANCH)**




**LOCATION MAP
SR-193 BRIDGE OVER
UNKNOWN BRANCH (LM 11.48)
FAYETTE COUNTY**





**BRIDGE ID 24015420001
(BRIDGE OVER UNKNOWN BRANCH)**



Copyright: © 2013 National Geographic Society, i-cubed



**TOPOGRAPHIC MAP
SR-193 BRIDGE OVER
UNKNOWN BRANCH (LM 11.48)
FAYETTE COUNTY**





STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
STRATEGIC TRANSPORTATION INVESTMENTS DIVISION
SUITE 1000, JAMES K. POLK BUILDING
505 DEADERICK STREET
NASHVILLE, TN 37243
(615) 741-2208

JOHN C. SCHROER
COMMISSIONER

BILL HASLAM
GOVERNOR

MEMORANDUM

TO: Steve Allen, Transportation Director
Strategic Transportation Investments Division

FROM: Mike Gilbert, CE Manager 2
Strategic Transportation Investments Division

DATE: March 9, 2018

SUBJECT: TIR Field Review (Improve Act)
SR-193 (Macon Road), Bridge over Branch
Bridge ID: 24015420001
Log Mile 11.48
Fayette County
PIN: 124285.00

A field review was held for the above-mentioned project on December 12, 2017.

The existing structure, built in 1965, is a two (2) span concrete channel beam bridge with timber substructure crossing an unnamed branch. The structure has an out-to-out width of 21.67 feet. The overall structure length is 37 feet with approximately 7.5 feet of vertical clearance at the lowest flow in the stream bed. The sufficiency rating for this structure is 44.6 based on the Bridge Inspection Report from September 29, 2016.

The discharges for the drainage basin were determined using StreamStats Version 4.1.8. which used a drainage area of 1.15 square miles. The 10-year discharge rate (Q10) was 794 cubic feet per second (cfs), Q50 was 1,060 cfs, and Q100 was 1,170 cfs.

The proposed alignment and grade for the replacement structure will remain the same as the existing structure including the 45° skew with the branch. There is a 45 mph posted speed limit on SR-193 and the proposed design speed will be 50 mph. TDOT hydraulics section has recommended that the proposed structure be a reinforced concrete box bridge with two (2) barrels with a width of 18 feet each and a clearance of six (6) feet on 45° skew (2 @ 18'x6'

RCBB). It is estimated that two tracts of land will be affected resulting in 0.16 acres of estimated right-of-way acquisition and that underground and overhead utilities will need to be relocated.

Closing the road and utilizing a detour route was briefly discussed at the field review. It was determined that the 16.2 mile detour was too far for emergency responders and school buses. It was decided that the better option was to use traffic signals to stage construct the new box bridge while maintaining one lane open during construction. It should be noted that the signals will have to be moved back approximately 400 feet on either end of the existing structure due to horizontal and vertical curve sight distance issues. Additional signage and message boards will be necessary due to this additional distance.

The route has a base year 2022 AADT of 1,540 and a design year 2042 AADT of 1,730. The two (2) lane existing structure and roadway approaches have nine (9) foot travel lanes. The route is classified as a Rural Major Collector and Standard Drawing RD01-TS-2 was used for design considerations. Table IV shows a minimum roadway width of 22 feet and minimum shoulder width of six (6) feet for AADT's between 1500 and 2000. Table I, on the same standard drawing allows a minimum of four (4) foot shoulders; however, due to the need to maintain one lane of traffic during construction the six (6) foot shoulders will be required. Therefore, the typical section on the proposed structure will be eleven (11) foot travel lanes with six (6) foot shoulders. The top of the proposed box bridge will be the new riding surface; so an additional 2.75 feet will be required on either side to allow for guardrail attachment to the top of the box for a total out-to-out width of 39.5 feet on the structure. The project will extend 170 feet from either end of the new proposed structure in order to install guardrail and to taper the lanes and shoulders back to the existing roadway. One (1) lane will remain open during the construction phasing while using temporary signals, signage and message boards to maintain traffic.


This project has been recommended for design-build by the Construction Division within TDOT. It is also possible that an ABC approach to complete the project with a weekend road closure by utilizing a triple barrel precast box. This would save four (4) feet of box length by reducing the six (6) foot shoulders to four (4) and would also eliminate the need for traffic signals for the lane closure for the maintenance of traffic during construction.

The cost for the estimated required approach work, estimated replacement, and estimated preliminary engineering for this bridge replacement is approximately \$833,000. Right-of-way acquisition is anticipated for this project.

DMG

cc: File

TYPE	YEAR	COUNTY	FIGURE NO.
TIR	2018	FAYETTE	1



2 - 11 FT LANES WITH 6 FT SHOULDERS
 TRANSITIONING TO MATCH EXISTING

PROP. R.O.W.
 PROP. 2 @ 18' x 6' RCBB

PROP. R.O.W.

EXISTING ROW
 SR-193 (MACON DRIVE)
 EXISTING ROW


BRANCH



BRIDGE TIR
 STATE ROUTE 193 (MACON DRIVE)
 L.M. 11.48
 FAYETTE COUNTY

STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION
 STRATEGIC TRANSPORTATION
 INVESTMENT DIVISION


FIGURE 1
 SR-193
 L.M. 11.48





3/8/2018 10:34:3 PM T:\1\DOT\131\DOT\2017 BIR\Fayette\6893-LM\48\FINAL\5893-Br\06a\FR-Fla.dgn

ENVIRONMENTAL TECHNICAL STUDY AREA
 STATE ROUTE 193 (MACON DRIVE)
 L.M. 11.48
 FAYETTE COUNTY

EXISTING STRUCTURE (INLET)




PROPOSED STRUCTURE (INLET)




BRIDGE PROFILES
MACON RD (SR193) FAYETTE COUNTY
BRIDGE OVER UNNAMED BRANCH @ L.M. 11.48
BRIDGE ID: 24015420001

EXISTING STRUCTURE




TOTAL WIDTH: 21'-8"


PHASE I




PHASE II



PROPOSED STRUCTURE



TOTAL WIDTH: 39'-6"



**PROPOSED TYPICAL SECTION AND
PHASED CONSTRUCTION**
MACON RD (SR193) FAYETTE COUNTY
BRIDGE OVER UNNAMED BRANCH @ L.M. 11.48
BRIDGE ID: 24015420001

COST ESTIMATE SUMMARY

Route:	SR -193 (Macon Road)
Description:	Bridge TIR RCBB over Branch
County:	Fayette
Length:	0.1 Mile
Date:	March 9, 2018



DESCRIPTION	LOCAL 0%	STATE 0%	FEDERAL 0%	TOTAL
Construction Items				
Pavement Removal	\$0	\$0	\$0	\$6,900
Asphalt Paving	\$0	\$0	\$0	\$60,200
Concrete Pavement	\$0	\$0	\$0	\$0
Drainage	\$0	\$0	\$0	\$4,200
Appurtenances	\$0	\$0	\$0	\$0
Structures	\$0	\$0	\$0	\$227,500
Fencing	\$0	\$0	\$0	\$0
Signalization	\$0	\$0	\$0	\$20,000
Railroad Crossing or Separation	\$0	\$0	\$0	\$0
Earthwork	\$0	\$0	\$0	\$69,300
Clearing and Grubbing	\$0	\$0	\$0	\$0
Seeding & Sodding	\$0	\$0	\$0	\$4,500
Rip-Rap or Slope Protection	\$0	\$0	\$0	\$1,400
Guardrail	\$0	\$0	\$0	\$21,400
Signing	\$0	\$0	\$0	\$400
Pavement Markings	\$0	\$0	\$0	\$2,100
Maintenance of Traffic	\$0	\$0	\$0	\$20,600
Mobilization (5%)	\$0	\$0	\$0	\$21,900
Other Items = 10%	\$0	\$0	\$0	\$46,000
Const. Contingency = 15%	\$0	\$0	\$0	\$41,800
Construction Estimate	\$0	\$0	\$0	\$548,200
Interchanges & Unique Intersections				
Roundabouts	\$0	\$0	\$0	\$0
Interchanges	\$0	\$0	\$0	\$0
Right-of-Way & Utilities				
	LOCAL 0%	STATE 0%	FEDERAL 0%	TOTAL
Right-of-Way	\$0	\$0	\$0	\$9,500
Utilities	\$0	\$0	\$0	\$136,300
Preliminary & Construction Engineering and Inspection				
Prelim. Eng. 10%	\$0	\$0	\$0	\$69,400
Const. Eng. & Inspec. 10%	\$0	\$0	\$0	\$69,400
Total Project Cost	\$0	\$0	\$0	\$ 833,000

DESCRIPTION	% Contribution
Pavement Removal	1.57%
Asphalt Paving	13.73%
Concrete Pavement	0.00%
Drainage	0.96%
Appurtenances	0.00%
Structures	51.88%
Fencing	0.00%
Signalization	4.56%
Railroad Crossing or Separation	0.00%
Earthwork	15.80%
Clearing and Grubbing	0.00%
Seeding & Sodding	1.03%
Rip-Rap or Slope Protection	0.32%
Guardrail	4.88%
Signing	0.09%
Pavement Markings	0.48%
Maintenance of Traffic	4.70%
Mobilization (5%)	
Other Items = 10%	
Const. Contingency = 15%	
Construction Estimate	

DESCRIPTION	Per Mile Cost
Total Project Cost	\$ 10,412,500.00

PAY ITEM SUMMARY

TDOT PAY ITEM	TDOT DESCRIPTION	UNIT	TOOL QUANTITIES	ADDITIONAL QUANTITIES	TOOL QUANTITIES + ADDITIONAL QUANTITIES	Statewide UNIT COST	TOTAL COST
Pavement Removal							
415-01.02	Cold Planning Bituminous Pavement	SY	892		892	\$ 7.63	\$ 6,800.56
PAVEMENT REMOVAL TOTAL (ROUNDED)							\$ 6,900
Asphalt Roads							
303-01	Mineral Aggregate, Type A Base, Grading D	TON	1248		1248	\$ 31.98	\$ 39,903.43
307-02.01	Asphalt Concrete Mix (PG70-22) (BPMB-HM) Grading A	TON	24		24	\$ 101.32	\$ 2,460.90
307-02.02	Asphalt Cement (PG70-22)(BPMB-HM) Grading A-S	TON	1		1	\$ 727.26	\$ 414.71
307-02.03	Aggregate (BPMB-HM) Grading A-S Mix	TON	18		18	\$ 74.35	\$ 1,370.76
307-02.08	Asphalt Concrete Mix (PG70-22) (BPMB-HM) Grading B-M2	TON	16		16	\$ 113.83	\$ 1,811.03
402-01	Bituminous Material For Prime Coat (PC)	TON	1		1	\$ 713.29	\$ 695.62
402-02	Aggregate For Cover Material (PC)	TON	4		4	\$ 66.05	\$ 232.50
403-01	Bituminous Material For Tack Coat (TC)	TON	0		0	\$ 781.16	\$ 311.08
411-01.07	ACS (PG64-22) GR "E"	TON	45		45	\$ 112.43	\$ 5,105.09
411-02.10	ACS Mix(PG70-22) Grading D	TON	68		68	\$ 115.27	\$ 7,884.87
PAVING TOTAL (ROUNDED)							\$ 60,200
Concrete Roads							
CONCRETE RAMPS AND ROADWAYS TOTAL (ROUNDED)							\$ -
Drainage							
607-05.02	24" Concrete Pipe Culvert (Class III)	LF	55	-55	0	\$ 85.64	\$ 17.13
710.02	Aggregate Underdrains (with pipe)	LF	845		845	\$ 5.46	\$ 4,612.61
DRAINAGE TOTAL (ROUNDED)							\$ 4,200
Appurtenances							
ROADWAY AND PAVEMENT APPURTENANCES TOTAL (ROUNDED)							\$ -
Earthwork & Mineral							
105-01	Construction Stakes, Lines, and Grades	LS	1	-0.8	0.2	\$ 112,407.96	\$ 22,481.59
203-01	Road & Drainage Excavation (Unclassified)	CY	3191	-1595	1596	\$ 16.79	\$ 26,802.82
203-03	Borrow Excavation (Unclassified)	CY	2660	-1330	1330	\$ 15.04	\$ 19,996.92
EARTHWORK & MINERAL TOTAL (ROUNDED)							\$ 69,300
Structures							
N/A	Removal of Bridge	SF	814		814	\$ 20.00	\$ 16,280.00
N/A	New Bridge (Box)	SF	2011		2011	\$ 105.00	\$ 211,150.80
STRUCTURES TOTAL (ROUNDED)							\$ 227,500
Interchanges and Unique Intersections							
INTERCHANGES AND UNIQUE INTERSECTIONS TOTAL (ROUNDED)							\$ -
Lighting & Signalization							
730-40	Temporary Traffic Signal System	EA		1	1	\$ 20,000.00	\$ 20,000.00
LIGHTING & SIGNALIZATION TOTAL (ROUNDED)							\$ 20,000
Guardrail							
705-02.02	Single Guardrail (Type 2)	LF	232	130	362.32	\$ 18.79	\$ 6,809.37
705-04.07	Tan Energy Absg Term (NCHRP, 350, TL3)	EA	5	-1	4	\$ 2,352.59	\$ 9,410.38
705-04.09	Earth Pad for Type 38 GR End Treatment	EA	5	-1	4	\$ 1,294.80	\$ 5,179.21
GUARDRAIL TOTAL (ROUNDED)							\$ 21,400
Seeding and Sodding							
801-01	Seeding (With Mulch)	UNIT	37		37	\$ 77.90	\$ 2,879.12
801-01.07	Temporary Seeding (With Mulch)	UNIT	28		28	\$ 29.91	\$ 829.03
801-02	Seeding (Without Mulch)	UNIT	28		28	\$ 28.44	\$ 788.41
SODDING TOTAL (ROUNDED)							\$ 4,500
Maintenance of Traffic							
N/A	Traffic Control	LS	1		1		\$ 16,716.00
712-02.02	Interconnected Portable Barrier Rail	LF	21	55	76	\$ 31.96	\$ 2,432.77
712-01.02	Lane Closure	EA	1		1	\$ 117.36	\$ 117.36
712-04.01	Flexible Drums (Channelizing)	EA	50		50	\$ 25.83	\$ 1,291.64
MAINTENANCE OF TRAFFIC TOTAL (ROUNDED)							\$ 20,600
Signs							
Not Listed	Signs (Construction)	LS	1		1	\$ -	\$ 400
SIGNING TOTAL (ROUNDED)							\$ 400
Pavement Markings							
716-13.06	Spray Thermo P.M. (40 mil 4")	LM	0.7		0.7	\$ 2,886.74	\$ 2,032.26
PAVEMENT MARKINGS TOTAL (ROUNDED)							\$ 2,100
Fencing							
FENCE TOTAL (ROUNDED)							\$ -
Rip-Rap							
709-05.08	Machined Rip-Rap (Class B)	TON		40	40	\$ 33.70	\$ 1,347.90
RIP-RAP & SLOPE PROTECTION TOTAL (ROUNDED)							\$ 1,400.00
Clearing and Grubbing							
CLEAR AND GRUBBING TOTAL (ROUNDED)							\$ -
Railroad At-Grade Crossing							
RAILROAD CROSSING OR SEPARATION TOTAL (ROUNDED)							\$ -
Utilities							
N/A	Overhead Distribution	LM	0.1		0.1	\$ 375,000	\$ 37,500
N/A	Underground Communication	LM	0.1		0.1	\$ 500,000	\$ 50,000
N/A	Underground Gas	LM	0.1		0.1	\$ 250,000	\$ 25,000
N/A	Underground Water	LM	0.1		0.1	\$ 237,600	\$ 23,760
UTILITIES TOTAL (ROUNDED)							\$ 136,300.00
Right-of-Way							
N/A	Right-of-Way	LS	1		1	\$ 9,454.55	\$ 9,454.55
RIGHT-OF-WAY TOTAL (ROUNDED)							\$ 9,500.00

BRIDGE TIR

Fayette
SR-193 (Macon Rd.) at LM 11.48

LOCATION			
Bridge #:	24015420001	Feature Crossed:	Unnamed Branch
Road Name:	SR-193 (Macon Rd.)	Log mile:	11.48
Route ID:	SR193	System:	05-STP Rural State
City:	Macon	Functional Class:	Rural Major Collector
County:	Fayette	State Project Number	24029-0207-94
PIN:	124285.00		

ROADWAY		
	Existing	Proposed (Preliminary Design Estimate)
Design Standard		RD01-TS-2 / 2011 Green Book
Route Characteristics		
AADT:	1540	1730
AADT Year:	2022	2042
Terrain:	Rolling	Rolling
No. Lanes:	2	2
Speed(Posted):	45	50
Speed (Design):		50
Approach Character.		
Lane Width (ft):	9	11
Shoulder Width (ft):	4	6
ROW Width (ft):	60	90
ROW Tracts Affected		2
ROW Required (acre)		0.16
Cross Section Width (ft):	18/26/60	22/34/90
Approach Length (ft):		170' (north), 170' (south)
Alignment:	tangent	tangent
Grade:		grade to remain the same as existing
Surface Material:	Pavement	Pavement
Sidewalks (R/L):	No	No
App. Lower Than Structure	No	No
Utilities (list)	UG water, OH electric, UG Fiber, UG Gas	N/A
Utilities to be Relocated	N/A	UG water, OH electric, UG Fiber, UG Gas
Comments	Discussions at Field Review on large farming equipment having impacts on existing guardrail.	This project has been recommended for design build by the Construction Division within TDOT.

BRIDGE TIR

Fayette
SR-193 (Macon Rd.) at LM 11.48

STRUCTURE		
	Existing	Proposed (Preliminary Design Estimate)
Bridge Characteristics		
Year Built	1965	
Load Limit	15 tons	
Sufficiency Rating	44.6	
Skew	45	45
Structure Type	PCCS with Timber Substructure	2 @ 18'X6" RCBB
Structures in Channel	Yes	Yes
Length (ft)	37	53.74
No. Spans (App./Main)	0 2	0 2
Width (curb to curb) (ft)	20	34
Width (o to o) (ft)	21.6	39.5
Sidewalks on Structure	No	No
Vert. Clearance (ft)	7.5	6
Superstructure Depth (in)	17	N/A
Girder Depth (in)	17	N/A
Finish Grade-Low Girder (in)	17	N/A
High Water Marks	N/A	
Bridge Rail Type	Metal Gaurdrail	Metal Guardrail attached to Box
Bridge Rail Height (ft)	2.17	2.58
Indication Overtopping	No	
Local Scour	No	
Obstructions	No	
Other Structures	N/A	Another option to consider is an ABC approach to complete the project with a weekend road closure by utilizing a triple barrel precast box. This would save 4 feet of box length by reducing the 6 foot shoulders to 4 and would also eliminate the need for temporary traffic signals.
Comments	Concrete filled retaining walls added to each abutment. Mild timber decay of pier columns.	This project has been recommended for design build by the Construction Division within TDOT.

FLOW RATES (from USGS StreamStats Program Version 3)

Drainage Area (sq. miles)	1.15 sq mi
10 Year Discharge Rate (Q10) cfs	794
50 Year Discharge Rate (Q50) cfs	1060
100 Year Discharge Rate (Q100) cfs	1170

CHANNEL

Depth (ft)	6
Width of Normal Flow (ft)	25
Depth of Normal Flow (ft)	2
Skew of Channel with Roadway	45
Type of Material in Stream Bed	rock, gravel, sand, and silt
Type of Vegetation on Banks	low growth, large timber, dead trees
Are Channel Banks Stable	No
Signs of Stream Aggradation	No
Signs of Stream Degradation	No
Drift or Drift Potential	Yes
Comments	

FLOODPLAIN

Skew Same as Channel	Yes
Symmetrical About Channel	Yes
Approx. Floor Elevations	N/A
Type of Vegetation in Floodplain	low growth, large timber, grass
Any Buildings in Floodplain	No
Flood Information From Locals	N/A
Comments	

MAINTENANCE OF TRAFFIC

Method of Maintaining Traffic	stage construct
Description	Utilizing traffic signals, the new box bridge will be stage constructed while maintaining one lane open during construction. It should be noted that the signals will have to be moved back on either end due to horizontal and vertical curve limitations. Additional signage and message boards will be required.
Comments	Another option to consider is an ABC approach to complete the project with a weekend road closure by utilizing a triple barrel precast box.

BRIDGE TIR

Fayette

SR-193 (Macon Rd.) at LM 11.48

SITE VISIT ATTENDEES			DATE: 3/17/2016
Name	Organization	Phone	Email
Mike Gilbert	TDOT (STID)	615-741-0772	michael.gilbert@tn.gov
Glen Blankenship	TDOT - Survey	731-935-0137	glen.blankenship@tn.gov
James Boyd	TDOT - Survey	731-935-0138	james.boyd@tn.gov
Derek Ryan	TDOT- Traffic		derek.ryan@tn.gov
Willie Coleman	TDOT - Utilities	731-935-0160	willie.coleman@tn.gov
Marcus Powell	TDOT	901-537-4399	marcus.l.powell@tn.gov
Jason D. Moody	TDOT	731-935-0183	jason.d.moody@tn.gov
Ryan Philpott	TDOT	731-935-0147	ryan.philpott@tn.gov
Dustin Tucker	TDOT	731-935-0101	dustin.tucker@tn.gov
Evelyn DiOrio	TDOT	731-935-0302	evelyn.diorio@tn.gov
Eric Philipps	TDOT	731-935-0174	eric.philipps@tn.gov
Elizabeth Cardwell	TDOT	731-935-0243	elizabeth.cardwell@tn.gov
Peter DeLong	TDOT	731-935-0338	peter.delong@tn.gov
Todd Kemp	Palmer	615-476-0772	tkemp@palmernet.com
Kyle McLemore	Palmer	615-297-8957	kmclemore@palmernet.com

**TENNESSEE DEPARTMENT OF TRANSPORTATION
STRATEGIC TRANSPORTATION INVESTMENTS DIVISION**

PROJECT NO.: 24029-1207-94 ROUTE: S.R. 193
 COUNTY: FAYETTE CITY: _____
 PROJECT PIN NUMBER: 124285.00
 PROJECT DESCRIPTION: BRIDGE OVER BRANCH (L.M. 11.48)
BRIDGE ID: 24015420001

DIVISION REQUESTING:

MAINTENANCE PAVEMENT DESIGN
 S.T.I.D. STRUCTURES
 PROG. DEVELOPMENT & ADM. SURVEY & ROADWAY DESIGN
 PUBLIC TRANS. & AERO. TRAFFIC SIGNAL DESIGN
 OTHER
 YEAR PROJECT PROGRAMMED FOR CONSTRUCTION: _____
 PROJECTED LETTING DATE: _____

TRAFFIC ASSIGNMENT:

BASE YEAR		DESIGN YEAR					DESIGN ROADWAY % TRUCKS		DESIGN AVERAGE DAILY LOADS	
AADT	YEAR	AADT	DHV	%	YEAR	DIR.DIST.	DHV	AADT	FLEX	RIGID
1,540	2022	1,730	190	11	2042	65-35	3	4	42	58

REQUESTED BY: NAME MICHAEL GILBERT DATE 2/28/18
 DIVISION S.T.I.D.
 ADDRESS J.K. POLK BLDG.
NASHVILLE, TN. 37243

REVIEWED BY: TONY ARMSTRONG *Tony Armstrong* DATE 2.28.18
 TRANSPORTATION MANAGER 1
 SUITE 1000, JAMES K. POLK BUILDING

APPROVED BY: JIM WATERS *Jim Waters* DATE 3/1/18
 ASSISTANT DIRECTOR
 SUITE 1000, JAMES K. POLK BUILDING

COMMENTS:

THIS TRAFFIC BASED ON 2017 CYCLE COUNTS. THE DESIGN YEAR TRAFFIC BASED ON GROWTH RATE FROM THE MEMPHIS MPO COMPUTER ASSIGNMENT MODEL.

DHV'S ARE NOT REQUIRED FOR SIDE ROADS LESS THAN 1000 AADT.

NOTE: FOR BRIDGE REPLACEMENT PROJECTS, ADLs ARE NOT REQUIRED FOR ADTs OF 1000 OR LESS AND PERCENTAGE OF TRUCKS OF 7% OR LESS.
 SEE ATTACHMENTS FOR TURNING MOVEMENTS AND/OR OTHER DETAILS.

**TENNESSEE DEPARTMENT OF TRANSPORTATION
STRATEGIC TRANSPORTATION INVESTMENTS DIVISION**

PROJECT NO.: 24029-1207-94 ROUTE NO.: S.R. 193
 COUNTY: FAYETTE CITY: _____
 PROJECT DESCRIPTION: BRIDGE OVER BRANCH (L.M. 11.48)
 BRIDGE ID: 240154200001

FAP Rural

Pavement Structural Design

Calculation of Equivalent Daily 18 Kip Single Axle Loads


Type Vehicle	ADT (No. Counted)	Flexible		Rigid	
		18-kip Factor	ADL	18-kip Factor	ADL
Pass. cars and motorcycles (1-2)	973	0.001	1	0.001	1
Pick-up, Panel, Van (3)	597	0.005	3	0.004	2
Sing. Unit Buses (4)	0	0.300	0	0.300	0
2-axle, 6-tire (5)	13	0.240	3	0.310	4
3-axle or more (6-7)	26	1.700	44	2.300	60
Comb. 4-axle (8)	11	1.110	12	1.500	17
5-axle or more (9-13)	15	1.320	20	2.200	33
Totals (2032 AADT)	1,635		83		117

Suggested Percentages of Trucks in Design Lane


5,000 or less ADT 95%
 5,000 - 10,000 ADT 90%
 10,000 - 15,000 ADT 85%
 15,000 - 20,000 ADT 80%
 20,000 - 30,000 ADT 75%
 30,000 - 40,000 ADT 70%
 40,000 Plus 60%

No. of Lanes: 2
 % Trucks in Design Lane: 100%
 ADL in Design Lane:
 FLEX: 0.5 X 1.00 X 83.3 = 42
 RIGID: 0.5 X 1.00 X 116.7 = 58

ADL Calculations By: RANDY BOGUSKIE Date: 2/28/2018
 Reviewed By: *Tony Amato* Date: 2.28.18
 [REV. 7/1/14]



FAYETTE COUNTY
S.R. 193 @ L.M. 11.48



MAP SCALE 1" = 1000'



NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0315C

FIRM
FLOOD INSURANCE RATE MAP
FAYETTE COUNTY,
TENNESSEE
AND INCORPORATED AREAS

PANEL 315 OF 605
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
FAYETTE COUNTY	470352	0315	C
OAKLAND, TOWN OF	470410	0315	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
47047C0315C

EFFECTIVE DATE
NOVEMBER 5, 2008




Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

Fayette SR 193 @ LM 11.48 StreamStats Report

Region ID: TN
 Workspace ID: TN20180205214405755000
 Clicked Point (Latitude, Longitude): 35.15558, -89.44109
 Time: 2018-02-05 15:44:20 -0600



Basin Characteristics

Parameter Code	Parameter Description	Value	Unit
CONDA	Area that contributes flow to a point on a stream	1.15	square miles
DRNAREA	Area that drains to a point on a stream	1.15	square miles
RECESS	Number of days required for streamflow to recede one order of magnitude when hydrograph is plotted on logarithmic scale	140	days per log cycle
PERMGTE2IN	Percent of area underlain by soils with permeability greater than or equal to 2 inches per hour	37.002	percent
CLIMFAC2YR	Two-year climate factor from Lichy and Karlinger (1990)	2.424	dimensionless
SOILPERM	Average Soil Permeability	1.07	inches per hour
TNCLFACT2	Tennessee climate factor, 2-year interval	2.424	
TNSOILFAC	Tennessee soil factor, percentage of area underlain by a soil permeability greater than or equal to 2 inches per hour	37	
CSL10_85	Change in elevation divided by length between points 10 and 85 percent of distance along main channel to basin divide - main channel method not known	49.48	feet per mi

Peak-Flow Statistics Parameters [DAOnly Area 4]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
CONDA	Contributing Drainage Area	1.15	square miles	0.76	2308

Peak-Flow Statistics Flow Report [DAOnly Area 4]

PII: Prediction Interval-Lower, Plu: Prediction Interval-Upper, SEp: Standard Error of Prediction, SE: Standard Error (other -- see report)

Statistic	Value	Unit	PII	Plu	SE	SEp	Equiv. Yrs.
2 Year Peak Flood	469	ft ³ /s	247	893	38.7	38.7	1.8
5 Year Peak Flood	667	ft ³ /s	358	1240	37.2	37.2	2.4
10 Year Peak Flood	794	ft ³ /s	422	1500	38	38	3.1
25 Year Peak Flood	950	ft ³ /s	488	1850	40.1	40.1	3.8
50 Year Peak Flood	1060	ft ³ /s	527	2140	42.2	42.2	4.2
100 Year Peak Flood	1170	ft ³ /s	560	2450	44.7	44.7	4.4
500 Year Peak Flood	1420	ft ³ /s	618	3270	51.1	51.1	4.7

Peak-Flow Statistics Citations

Law, G.S., and Tasker G.D., 2003, **Flood-Frequency Prediction Methods for Unregulated Streams of Tennessee, 2000: U.S. Geological Survey Water-Resources Investigations Report 03-4176, 79p.** (<http://pubs.usgs.gov/wri/wri034176/>)

Low-Flow Statistics Parameters [Low Flow West Region 2009 5159]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	1.15	square miles	2	2405
RECESS	Recession Index	140	days per log cycle	32	350
PERMGTE2IN	Percent permeability gte 2 in per hr	37.002	percent	2	98

Low-Flow Statistics Disclaimers [Low Flow West Region 2009 5159]

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors

Low-Flow Statistics Flow Report [Low Flow West Region 2009 5159]

Statistic	Value	Unit
7 Day 10 Year Low Flow	0.0156	ft ³ /s
30 Day 5 Year Low Flow	0.0359	ft ³ /s

Low-Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009-5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

Annual Flow Statistics Parameters [Low Flow West Region 2009 5159]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	1.15	square miles	2	2405
RECESS	Recession Index	140	days per log cycle	32	350
CLIMFAC2YR	Tennessee Climate Factor 2 Year	2.424	dimensionless	2.307	2.455
PERMGTE2IN	Percent permeability gte 2 in per hr	37.002	percent	2	98

Annual Flow Statistics Disclaimers [Low Flow West Region 2009 5159]

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors

Annual Flow Statistics Flow Report [Low Flow West Region 2009 5159]

Statistic	Value	Unit
Mean Annual Flow	1.5	ft ³ /s

Annual Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009-5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

Seasonal Flow Statistics Parameters [Low Flow West Region 2009 5159]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	1.15	square miles	2	2405
RECESS	Recession Index	140	days per log cycle	32	350
PERMGTE2IN	Percent permeability gte 2 in per hr	37.002	percent	2	98

Seasonal Flow Statistics Disclaimers [Low Flow West Region 2009 5159]

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors

Seasonal Flow Statistics Flow Report [Low Flow West Region 2009 5159]

Statistic	Value	Unit
Summer Mean Flow	0.328	ft ³ /s

Seasonal Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009-5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

Flow-Duration Statistics Parameters [Low Flow West Region 2009 5159]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	1.15	square miles	2	2405
RECESS	Recession Index	140	days per log cycle	32	350
PERMGTE2IN	Percent permeability gte 2 in per hr	37.002	percent	2	98
CLIMFAC2YR	Tennessee Climate Factor 2 Year	2.424	dimensionless	2.307	2.455
SOILPERM	Average Soil Permeability	1.07	inches per hour	0.97	2.44

Flow-Duration Statistics Disclaimers [Low Flow West Region 2009 5159]

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors

Flow-Duration Statistics Flow Report [Low Flow West Region 2009 5159]

Statistic	Value	Unit
99.5 Percent Duration	0.0144	ft ³ /s
99 Percent Duration	0.0206	ft ³ /s
98 Percent Duration	0.0273	ft ³ /s
95 Percent Duration	0.0391	ft ³ /s
90 Percent Duration	0.0532	ft ³ /s
80 Percent Duration	0.0775	ft ³ /s
70 Percent Duration	0.119	ft ³ /s
60 Percent Duration	0.178	ft ³ /s
50 Percent Duration	0.24	ft ³ /s
40 Percent Duration	0.406	ft ³ /s
30 Percent Duration	1.04	ft ³ /s
20 Percent Duration	1.81	ft ³ /s
10 Percent Duration	3.16	ft ³ /s

Flow-Duration Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009-5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

CHECK LIST OF DETERMINANTS FOR LOCATION STUDY

If any of the following facilities or ESE categories are located within the project area or corridor, place an "x" in the blank opposite the item. Where more than one alternate is to be considered, place its letter designation in the blank.

1. Agricultural land usage	X
2. Airport (existing or proposed)	
3. Commercial area, shopping center	
4. Floodplains	X
5. Forested land	
6. Historical, cultural, or natural landmark	
7. Industrial park, factory	
8. Institutional usages	
a. School or other educational institution	
b. Church or other religious institution (Cemetery)	
c. Hospital or other medical facility	
d. Public building, e.g., fire station	
e. Defense installation	
9. Recreation usages	
a. Park or recreational area	
b. Game preserve or wildlife area	
10. Residential establishment	
11. Urban area, town, city, or community	
12. Waterway, lake, pond, river, stream, spring	
Permit required:	
Coast Guard	
Section 404	X
TVA Section 26a review	
NPDES	X
Aquatic Resource Alteration	X
13. Other	
14. Location coordinated with local officials	
15. Railroad crossings	
16. Hazardous materials site	

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Bridge Number



Looking west across bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking west across bridge standing near east end of bridge



Looking west standing near middle of bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking east across bridge standing near west end of bridge



Looking east standing near middle of bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking east standing off east end of bridge



Pavement failure at west end of bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at downstream side standing off SW corner of bridge



Looking at upstream side standing off NW corner of bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch




Looking at downstream side standing off SE corner of bridge



Looking north at upstream side standing on bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking south at downstream side standing on bridge



Looking south at downstream side standing on bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at west abutment standing on the south side of bridge



Looking at west abutment standing on the south side of bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at east abutment standing on the south side of bridge



Looking under bridge deck

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at west abutment standing under bridge



Looking at center pier and east abutment standing under bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at west abutment standing under bridge



Looking at center pier and east abutment standing under bridge

Transportation Investment Report
Bridge ID: #24015420001
Fayette County
SR-193 (Macon Rd.) at LM 11.48 over Branch



Looking at center pier and east abutment standing under bridge

Previous Environmental Documentation

Programmatic Categorical Exclusion

State Route (SR) 193 (Macon Road)
Bridge over Branch, Log Mile (LM) 11.48
Unincorporated Fayette, Tennessee
Fayette County
PIN 128113.02

Submitted Pursuant to the National Environmental Policy Act of 1969, 42 U.S.C. 4332(2)

Project Information

General Information


Route: State Route (SR) 193 (Macon Road)
Termini: Bridge over Branch, Log Mile (LM) 11.48
Municipality: Unincorporated Fayette, Tennessee
County: Fayette
PIN: 128113.02
Plans: Transportation Investment Report
Date of Plans: 03/27/2018

Project Funding

Planning Area: West Tennessee Rural Planning Organization (RPO)
STIP/TIP: 1799001 - Surface Transportation Block Grant Program (STBGP) Grouping

Funding Source	Preliminary Engineering	Right-of-Way	Construction
Federal	BR-STP-193(11)	BR-STP-193(11)	BR-STP-193(11)
State	24029-0207-94	24029-2207-94	24029-3207-94

Project Location



Project Overview

Introduction

The Tennessee Department of Transportation (TDOT), in cooperation with the Federal Highway Administration (FHWA), proposes to replace the SR-193 (Macon Road) Bridge (24015420001) over an unnamed branch at LM 11.48 in Fayette County, TN.

Background

Every two years, TDOT performs a comprehensive inspection and subsequent evaluation of all public bridges across the state in order to determine the status of their working condition and operating limits to ensure that they are in accordance with the Federal Highway Administration (FHWA) National Bridge Inspection Standards (NBIS). These inspections are recorded and published in the National Bridge Inventory (NBI) Tennessee Inventory and Appraisal Report. One of the components of this evaluation is the designation of a sufficiency rating. A sufficiency rating is calculated for each individual bridge that is used to carry vehicular traffic. Ratings are measured on a scale of 0 to 100. A rating of 100 corresponds to a bridge that qualifies as an “entirely sufficient bridge,” while a rating of 0 denotes a bridge that is “entirely deficient.” Bridges that receive a sufficiency rating of less than 80.0 are eligible for rehabilitation; bridges that earn a rating below 50.0 are eligible for replacement. Another component of the NBI are the condition ratings. Condition ratings are used to describe the existing, in-place bridge as compared to the as-built condition. The physical condition of the deck, superstructure, and substructure components of a bridge are evaluated for a condition rating. Condition ratings are assigned codes ranging from 0-9, with 0 being failed condition and 9 being excellent condition.

According to the Transportation Investment Report (TIR) dated 03/27/2018 (located in the Technical Appendices), the SR-193 Bridge over Branch at LM 11.48 received a sufficiency rating of 44.6. Formerly the proposed project was assigned project PIN 124285.00, however correspondence provided on 10/03/2018 shows a new project PIN (PIN 128113.02), has been assigned. This correspondence can be found in the Technical Appendices. All responses from the technical studies areas list the former PIN.

Project Development

Need

The proposed project is needed to address insufficient structural elements due to the deterioration of the bridge as indicated by the sufficiency rating.

Purpose

The purpose of this project is to improve structural elements of the SR-193 Bridge over Branch at LM 11.48 by replacing the existing bridge.

Range of Alternatives

Other than the selected design, were any alternative build designs developed for this project?

No

No-Build

In the development of design solutions that address the needs outlined above and achieve the purpose of the project, TDOT evaluated the potential consequences should the project not be implemented. This option, known as the No-Build alternative, assumed the continuation of current conditions and set the baseline from which the impacts of the selected design were compared.

The No-Build Alternative was not selected as it does not meet the purpose and need of the project.

Public Involvement

Has there been any public involvement for the project?

No

Existing Conditions and Layout

The proposed project is located in the southwest region of Tennessee in Fayette County between the city of Macon and Williston. The project segment of SR-193 runs east to west connecting the two cities, and according to the 2018 TIR, is a Rural Major Collector consisting of two lanes, (one lane in each direction), with nine foot wide travel lanes and four foot wide shoulders. The speed limit along the project segment is 45 miles per hour (mph).

The SR-193 Bridge (ID 24015420001), built in 1965, is a two-span concrete channel beam bridge with a timber substructure crossing an unnamed branch. The total length of the bridge is 37 feet long with an out-to-out width of 21.67 feet and a vertical height of 7.5 feet at the lowest flow in the stream bed (see Figure 1).




Figure 1. Shows the profile of the existing bridge structure according to TIR dated 03/27/2018.

Proposed Project Description

The proposed bridge would consist of a 53.74 foot long reinforced concrete box bridge consisting of two barrels, each at a width of 18 feet and a vertical height clearance of six feet. The new structure would have an out-to-out width of 39.5 feet (see Figure 2).

The project segment of SR-193 would consist of two 11 foot wide travel lanes, (one in each direction), and six foot wide shoulders. The riding surface for SR-193 would be the top of the new replacement bridge, so the proposed project would add an additional 2.75 feet of roadway width to construct guardrail along both sides of SR-193. The proposed project would add the guardrail and taper both the lanes and shoulders from 170 feet from the project bridge back to the existing roadway in both directions. A new speed limit of 50 mph was proposed for the project segment of SR-193.

PROPOSED STRUCTURE (INLET)




Figure 2. Shows profile of the replacement bridge according to TIR dated 03/27/2018.

Right-of-Way

Does this project require the acquisition of right-of-way or easements?

Yes

Right-of-Way Acquisition Table

Permanent Acquisition			Temporary Acquisition		
R.O.W Acquisition	Drainage Easements	Total	Slope Easements	Construction Easements	Total
0.16	0	0.16	0	0	0

*Measured in acres

According to the TIR dated 03/27/2018, "It is estimated that two tracts of land will be affected resulting in 0.16 acres of estimated right-of-way acquisition."

Displacements and Relocations

Will this project result in residential, business or non-profit displacements and relocations?

No

Changes in Access Control

Will changes in access control impact the functional utility of any adjacent parcels?

No

Traffic and Access Disruption

At this time, are traffic control measures and temporary access information available?

Yes

Will this project involve traffic control measures that may result in major traffic disruptions?

No

Traffic control would be conducted in two phases for the proposed project using traffic signals. Each phase of the construction would maintain one 11-foot lane of traffic at all times during construction. Also, due to the curvature of the roadway it was determined that the traffic signals would have to be moved back approximately 400 feet from the existing bridge due to sight distance issues. Additional signage and message boards will be necessary due to this additional distance.

Environmental Studies

Water Resources

Are there any water resources, wetlands or natural habitat located within the project area?

Yes

Preliminary Impact Form

County: Fayette Route: SR-193 PIN: 124285.00

Date Prepared: 7/17/2018

Prepared by:
TDOT Region 4 - Environmental Tech Office

NOTE: This document is for "preliminary" use only and will not be considered accurate until the time of permit application.

Streams

Labels	Type *	Function	Quality	Impacts (feet)		
				Permanent	Temporary	Total
STR-1	Stream		Undetermined at this time	100		100
			Total	100		100

* Identification of features has not been reviewed by regulatory agencies. Determinations could change.

Mitigation of impacts to streams or any other fluvial systems will be accomplished through the avoidance and minimization of potential impacts during the design process. Permanent stream alterations such as relocations, impoundments or channel modification will be mitigated on-site to the extent possible in order to return the channel to its most probable natural state. Impacts that cannot be mitigated on-site will be subject to a compensatory mitigation plan that may include restoration of a comparable resource or application of an in-lieu fee program.

Protected Species

Is the GPNEA Consultation (2017) or the TDEC-DNA (2015) MOA applicable to this project?

No

Rare Species Dataviewer:

The TDEC Rare Species Dataviewer was reviewed on 06/21/2018.

According to the Environmental Boundaries Report (EBR) dated 07/16/2018 from the TDOT Ecology Section, no species were located within a one mile radius of the proposed project. One species was within a one mile to four mile radius of the project, was identified as a Barking tree frog (*Hyla gratiosa*), a threatened state animal, with the present habitat unsuitable (see Technical Appendices).

U.S. Fish and Wildlife Service (USFWS):

Coordination with the USFWS was completed on 07/13/2018.

The USFWS correspondence states, "Upon review of the information provided and our database, we would not anticipate impacts to any federally listed or proposed species as a result of the project. Therefore, based on the best information available at this time, we believe that the requirements of section 7 of the Endangered Species Act (Act) of 1973, as amended, are fulfilled for all species that currently receive protection under the Act."

Tennessee Wildlife Resources Agency (TWRA):

Coordination with TWRA was completed on 07/11/2018.

The TWRA correspondence states, "The Tennessee Wildlife Resources Agency has reviewed the information that you provided regarding the proposed SR-193 (Macon Drive) Bridge in Fayette County, Tennessee and we have no concerns regarding the project and do not anticipate adverse impacts to state listed species under our authority due to the project."

Floodplain Management

Flood Zone: Zone X (White) - Area Determined to be Outside the 500-year Floodplain.

Portions of this project are located in or near a Federal Emergency Management Agency (FEMA) defined floodplain however there is no detailed study. The project is located on Flood Insurance Rate Maps in Fayette County, Panel 315 of 605, Map # 47047C0315C. The design of the roadway system will be consistent with the Memorandum of Understanding (MOU) between FHWA and FEMA and with the floodplain management criteria set forth in the National Flood Insurance Regulations of Title 44 of the Code of Federal Regulations (CFR). It will be consistent with the requirements of floodplain management guidelines for implementing Executive Order 11988 and FHWA guidelines 23 CFR 650A. A portion of the FEMA FIRM is included in the Attachments.

Air Quality

Transportation Conformity:

Coordination with the TDOT Air and Noise Section dated 06/08/2018 states, "This project is in Fayette County which is in attainment for all transportation-related regulated criteria pollutants. Therefore, conformity does not apply to this project."

Mobile Source Air Toxics (MSAT):

The same coordination also states, "This project qualifies as a categorical exclusion under 23 CFR 771.117 and does not require a Mobile Source Air Toxics (MSATs) evaluation per FHWA's 'Interim Guidance Update on Air Toxic Analysis in NEPA Documents' dated October 2016."

Noise

In accordance with FHWA requirements and TDOT's Noise Policy this project is determined to be **Type III**

No significant noise impacts are anticipated for this project and a noise study is not needed.

Farmland

Is this project exempt from the provisions of the Farmland Protection Policy Act (FPPA)? **Yes**

FPPA Exemption: Small Acreage (3 acres or less for an existing bridge or interchange)

Section 4(f)

Does this project involve the use of property protected by Section 4(f) (49 USC 303)? **No**

Section 6(f)

Does this project involve the use of property assisted by the L&WCF? **No**

Cultural Resources

Does the Interstate Highway exemption or MOU between TDOT and the SHPO (2015) apply? **No**

Are NRHP listed or eligible cultural resources within the project Area of Potential Effect (APE)? **No**

Historic/Architectural Concurrence:

Concurrence from the TN State Historic Preservation Office (TN-SHPO) was received on 06/12/2018.

TN-SHPO Concurrence letter states, "Considering the information provided, we find that no architectural resources eligible for listing in the National Register of Historic Places will be affected by this undertaking,"

Archaeology Concurrence:

Concurrence from the TN State Historic Preservation Office (TN-SHPO) was received on 07/24/2018.

TN-SHPO Concurrence letter states, "Considering the information provided, we find that no archaeological resources eligible for listing in the National Register of Historic Places will be affected by this undertaking,"

Native American Consultation

Does this project require Native American consultation? **Yes**

Native American Consultation was requested on 05/14/2018.

Native American Consultation

Sent	Response		Sent	Response	
<input type="checkbox"/>	<input type="checkbox"/>	Absentee Shawnee Tribe of Oklahoma	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Muscogee (Creek) Nation
<input type="checkbox"/>	<input type="checkbox"/>	Cherokee Nation	<input type="checkbox"/>	<input type="checkbox"/>	Poarch Band of Creek Indians
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Chickasaw Nation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Quapaw Tribe of Oklahoma
<input type="checkbox"/>	<input type="checkbox"/>	Choctaw Nation of Oklahoma	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Shawnee Tribe
<input type="checkbox"/>	<input type="checkbox"/>	Eastern Band of Cherokee Indians	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Thlopthlocco Tribal Town
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Eastern Shawnee Tribe of Oklahoma	<input checked="" type="checkbox"/>	<input type="checkbox"/>	United Keetoowah Band of Cherokee Indians
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Kialegee Tribal Town	<input type="checkbox"/>	<input type="checkbox"/>	Other

Chickasaw Nation:

The response was received on 08/31/2018.

Correspondence from the Chickasaw Nation states, "The Chickasaw Nation supports the proposed undertakings and is presently unaware of any specific historic properties, including those of traditional religious and cultural significance, in the project area."

Shawnee Tribe:

The response was received on 06/12/2018.

The Shawnee Tribe correspondence states, "The Shawnee Tribe's Tribal Historic Preservation Department concurs that no known historic properties will be negatively impacted by this project."

Environmental Justice

Are there any disproportionately high or adverse effects on low-income or minority populations?

No

The proposed project does not have the potential to cause disproportionately high or adverse effects on low-income or minority populations.

Hazardous Materials

Does the project involve any asbestos containing materials?

No

Does the project involve any other hazardous material sites?

No

Bicycle and Pedestrian

Does this project include accommodations for bicycles and pedestrians?

Yes

Coordination from the TDOT Multimodal Transportation Resources Division dated 06/08/2018 states, "This bridge project accommodates bicyclists with 6' wide shoulders in a rural area."

Environmental Commitments

Does this project involve any environmental commitments?

No

Additional Environmental Issues

Are there any additional environmental concerns involved with this project?

No

Conclusion

Review Determination

Determination: Programmatic Categorical Exclusion

This federal-aid highway project qualifies for a Categorical Exclusion under 23 C.F.R 771.117(d) and does not exceed the thresholds listed in Section IV(A)(1)(b) of the 2016 Programmatic Agreement between the Federal Highway Administration, Tennessee Division and the Tennessee Department of Transportation. The Department has determined that the specific conditions and criteria for these CEs are satisfied and that significant environmental impacts will not result from this action. This project is therefore designated as a Programmatic Categorical Exclusion and does not require Administration approval.

Reference Material

All source material used in support of the information and conclusions presented in this document are included in the attachments and technical appendices. The attachments are located at the end of the environmental document and include information on funding, agency concurrence, applicable agency agreements, and special commitment support. The technical appendices are compiled as a separate document and include the project plans, technical reviews, reports and any other additional information.

Preparer Certification

By signing below, you certify that this document has been prepared in compliance with all applicable environmental laws, regulations and procedures. You can attest to the document's quality, accuracy, and completeness, and that all source material has been compiled and included in the attachments and technical appendices.

Crystal M. Alfaro Digitally signed by Crystal M. Alfaro
DN: cn=Crystal M. Alfaro, o=TN Dept. of
Transportation, ou=Environmental Division - NEPA,
email=crystal.alfaro@tn.gov, c=US
Date: 2018.10.11 11:48:55 -05'00'

Document Preparer

Document Approval

By signing below, you officially concur that this document is in compliance with all applicable environmental laws, regulations and procedures. You have reviewed and verified the document's quality, accuracy, and completeness and that all source material has been compiled and included in the attachments and technical appendices.

Joseph D. Santangelo Digitally signed by Joseph D. Santangelo
Date: 2018.10.11 12:47:10 -05'00'

Tennessee Department of Transportation

Attachments

Acronyms

AADT	Annual Average Daily Traffic	NRCS	Natural Resources Conservation Service
ADA	Americans with Disabilities Act	NRHP	National Register of Historic Places
APE	Area of Potential Effect	PCE	Programmatic Categorical Exclusion
BMP	Best Management Practice	PIN	Project Identification Number
CAA	Clean Air Act	PM	Particulate Matter
CE	Categorical Exclusion	PND	Pond
CEQ	Council on Environmental Quality	RCRA	Resource Conservation and Recovery Act
CFR	Code of Federal Regulations	ROW	Right-of-Way
CMAQ	Congestion Mitigation and Air Quality	ROD	Record of Decision
DEIS	Draft Environmental Impact Statement	RPO	Rural Planning Organization
FEMA	Federal Emergency Management Agency	SIP	State Implementation Plan
FONSI	Finding of No Significant Impact	SNK	Sinkhole
EA	Environmental Assessment	SR	State Route
EIS	Environmental Impact Statement	STIP	State Transportation Improvement Program
EJ	Environmental Justice	STR	Stream
EPA	Environmental Protection Agency	TDEC	TN Department of Environment and Conservation
EPH	Ephemeral Stream	TDOT	Tennessee Department of Transportation
FHWA	Federal Highway Administration	TIP	Transportation Improvement Program
FIRM	Flood Insurance Rate Map	SHPO	State Historic Preservation Office
FPPA	Farmland Protection Policy Act	TPO	Transportation Planning Organization
GHG	Greenhouse Gas	TVA	Tennessee Valley Authority
GIS	Geographic Information System	TWRA	Tennessee Wildlife Resources Agency
IAC	Interagency Consultation	USDOT	U.S. Department of Transportation
LWCF	Land and Water Conservation Fund	USACE	U.S. Army Corps of Engineers
LOS	Level of Service	USFWS	U.S. Fish and Wildlife Service
MOA	Memorandum of Agreement	UST	Underground Storage Tank
MOU	Memorandum of Understanding	VMT	Vehicle Miles Traveled
MPO	Metropolitan Planning Organization	VPD	Vehicles Per Day
MSAT	Mobile Source Air Toxics	WWC	Wet Weather Conveyance
NEPA	National Environmental Policy Act		

State Transportation Improvement Program

STIP Project List

STIP # 1799001 **TDOT PIN #** **LENGTH IN MILES** **LEAD AGENCY** TDOT

COUNTY STATEWIDE - RURAL **TOTAL PROJECT COST** \$426,000,000

ROUTE

TERMINI SURFACE TRANSPORTATION BLOCK GRANT PROGRAM (STBGP) - GROUPING

PROJECT DESCRIPTION SEE APPENDIX STATE GROUPING DESCRIPTION FOR A COMPREHENSIVE LISTING OF ACTIVITIES INCLUDED BUT NOT LIMITED FOR ELIGIBILITY

REMARKS



COUNTY MAP

FY	PHASE	FUNDING	TOTAL FUNDS	FED FUNDS	STATE FUNDS	LOCAL FUNDS
2017	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2018	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2019	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	
2020	PE, ROW, CONST	STBG	106,500,000	85,200,000	21,300,000	



VICINITY MAP

ALL SCHEDULES SUBJECT TO AVAILABILITY OF FUNDS.

Grouping Category	Function of Grouping Activities	Allowable Work Types
<p>Surface Transportation Block Grant Program (STBG) Grouping</p> <p>STIP# 1799001</p>	<p>Projects and programs for the preservation and improvement of the conditions and performance of Federal-aid highways and public roads, including:</p> <ul style="list-style-type: none"> • Rehabilitation, resurfacing, restoration, preservation, and operational improvements on Federal-aid highways and designated routes of the Appalachian Development Highway System (ADHS) and local access roads under 40 USC 14501, • Traffic operations on Federal-aid highways, • Bridge and tunnel improvements on public roads, • Safety improvements on public roads, • Environmental mitigation • Scenic and historic highway programs, • Landscaping and scenic beautification, 	<p>Activities previously authorized under the Surface Transportation Program (STP):</p> <ul style="list-style-type: none"> • Minor rehabilitation, pavement resurfacing, preventative maintenance, restoration, and pavement preservation treatments to extend the service life of highway infrastructure, including pavement markings and improvements to roadside hardware or sight distance • Highway improvement work including slide repair, rock fall mitigation, drainage repairs, or other preventative work necessary to maintain or extend the service life of the existing infrastructure in a good operational condition • Minor operational and safety improvements to intersections and interchanges such as adding turn lanes, addressing existing geometric deficiencies, and extending on/off ramps • Capital and operating costs for intelligent transportation systems (ITS) and traffic monitoring, management, and control facilities and programs: <ul style="list-style-type: none"> ○ Infrastructure-based intelligent transportation systems (ITS) capital improvements ○ Traffic Management Center (TMC) operations and utilities ○ Freeway service patrols ○ Traveler information • Bridge and tunnel construction (no additional travel lanes), replacement, rehabilitation, preservation, protection, inspection, evaluation, and inspector training and inspection and evaluation of other infrastructure assets, such as signs, walls, and drainage structures • Development and implementation of a State Asset Management Plan including data collection, maintenance and integration, software costs, and equipment costs that support the development of performance-based management systems for infrastructure • Rail-highway grade crossing improvements • Highway safety improvements: <ul style="list-style-type: none"> ○ Installation of new or improvement of existing guardrail ○ Installation of traffic signs and signals/lights ○ Spot safety improvements • Sidewalk improvements • Pedestrian and/or bicycle facilities • Traffic calming and traffic diversion improvements • Transportation Alternatives as defined by 23 USC 213(B), 23 USC 101(A)(29), and Section 1122 of MAP-21 • Noise walls • Wetland and/or stream mitigation • Environmental restoration and pollution abatement • Control of noxious weeds and establishment of native species <p>Activities previously authorized under the Transportation Enhancement Program:</p>

Appendices

<p>Surface Transportation Block Grant Program (STBG) Grouping</p> <p>(continued)</p> <p>STIP# 1799001</p>	<ul style="list-style-type: none"> ● Historic preservation. ● On- and off-road pedestrian and bicycle facilities. ● Infrastructure projects for improving non-driver access to public transportation and enhanced mobility. ● Community improvement activities. ● Recreational Trail Program projects. ● Safe Routes to School (SRTS) projects. ● Transportation Enhancement projects. ● Transportation Alternatives projects. ● Projects for the creation, rehabilitation, and maintenance of multi-use recreational trails. 	<ul style="list-style-type: none"> ○ Pedestrian and bicycle facilities, safety, and educational activities ○ Acquisition of scenic easements and scenic or historic sites ○ Scenic or historic highway programs ○ Landscaping and other scenic beautification activities ○ Historic preservation ○ Rehabilitation and operation of historic transportation buildings, structures, or facilities ○ Preservation of abandoned railway corridors ○ Inventory, control, and removal of outdoor advertising ○ Archaeological planning and research ○ Environmental mitigation to address water pollution due to highway runoff or reduce vehicle-caused wildlife mortality while maintaining habitat connectivity ○ Establishment of transportation museums ○ Activities under the Tennessee Roadscapes grant program, including landscaping, irrigation, benches, trash cans, paths and signage <p>Activities previously authorized under the Safe Routes to School Program (SRTS):</p> <ul style="list-style-type: none"> ● Sidewalk improvements ● Traffic calming and speed reduction improvements ● Pedestrian and bicycle crossing improvements ● On-street bicycle facilities ● Off-street bicycle and pedestrian facilities ● Secure bicycle parking facilities ● Traffic diversion improvements approximately within 2 miles of a school location ● Non-infrastructure related activities: <ul style="list-style-type: none"> ○ Public awareness campaigns and outreach to press and community leaders ○ Traffic education and enforcement in the vicinity of schools <ul style="list-style-type: none"> ▪ Student sessions on bicycle and pedestrian safety, health, and environment ▪ Funding for training, volunteers, and managers of safe routes to school program <p>Activities previously authorized under the Transportation Alternatives Program (TAP):</p> <ul style="list-style-type: none"> ● Construction, planning, and design of on-road and off-road trail facilities for pedestrians, bicyclists, and other non-motorized forms of transportation, including: <ul style="list-style-type: none"> ○ Sidewalk improvements ○ Bicycle infrastructure ○ Pedestrian and bicycle signals ○ Traffic calming techniques ○ Lighting and other safety-related infrastructure
--	--	--

Appendices

<p>Surface Transportation Block Grant Program (STBG) Grouping (continued)</p> <p>STIP# 1799001</p>	<ul style="list-style-type: none"> • Projects for the planning, design or construction of boulevards and other roadways largely in the right-of-way of former Interstate System routes or other divided highways. 	<ul style="list-style-type: none"> ○ Transportation projects to achieve compliance with the Americans with Disabilities Act of 1990 • Construction, planning, and design of infrastructure-related projects and systems that will provide safe routes for non-drivers, including children, older adults, and individuals with disabilities to access daily needs • Conversion and use of abandoned railroad corridors for trails for pedestrians, bicyclists, or other non-motorized transportation users • Construction of turnouts, overlooks, and viewing areas • Community improvement activities, which include but are not limited to: <ul style="list-style-type: none"> ○ Inventory, control, or removal of outdoor advertising ○ Historic preservation and rehabilitation of historic transportation facilities ○ Vegetation management in transportation rights-of-way to improve roadwaysafety, prevent invasive species, and provide erosion control ○ Archaeological activities relating to impacts from implementation of atransportation project eligible under Title 23 of the USC • Any environmental mitigation activity, including pollution prevention and pollution abatement activities and mitigation to: <ul style="list-style-type: none"> ○ Address stormwater management, control, and water pollution prevention or abatement related to highway construction or due to highway runoff ○ Reduce vehicle-caused wildlife mortality or to restore and maintain connectivity among terrestrial or aquatic habitats • Recreational Trails Program activities under 23 USC 206 • SRTS Program infrastructure-related projects, non-infrastructure-related activities (such as pedestrian and bicycle safety and educational activities advanced under the SRTS program), and SRTS Coordinator positions. • Planning, designing, or constructing boulevards and other roadways largely in the right-of-way of former Interstate System routes or other divided highways <p>Activities previously authorized under the Recreational Trails Program (RTP):</p> <ul style="list-style-type: none"> • Maintenance and restoration of existing recreational trails • Development and rehabilitation of trailside and trailhead facilities and trail linkages for recreational trails • Purchase and lease of recreational trail construction and maintenance equipment • Construction of new recreational trails • Acquisition of easements and fee simple title to property for recreational trails or recreational trail corridors. • Assessment of trail conditions for accessibility and maintenance • Development and dissemination of publications and operation of educational programs to promote safety and environmental protection • Payment of costs to the State incurred in administering the program
---	--	--

U.S. Fish and Wildlife Service Coordination

From: [John Griffith](#)
To: [Eric Philipps](#)
Cc: [Randall E. Mann](#); [Lou Timms](#); [Jared McCoy](#); [Dustin Tucker](#); [Rita M. Thompson](#); [Greg Harris](#)
Subject: RE: [EXTERNAL] Fayette County, SR-193 (Macon Road) Bridge over Branch, PIN 124285.00
Date: Friday, July 13, 2018 3:36:33 PM
Attachments: [image001.png](#)

***** This is an EXTERNAL email. Please exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email - STS-Security. *****

Eric,

??

Thank you for requesting our review of the proposed SR-193 Bridge replacement over a tributary to Shaws Creek at LM 11.48 in Fayette County, Tennessee.?? Upon review of the information provided and our database, we would not anticipate impacts to any federally listed or proposed species as a result of the project.?? Therefore, based on the best information available at this time, we believe that the requirements of section 7 of the Endangered Species Act (Act) of 1973, as amended, are fulfilled for all species that currently receive protection under the Act.?? Obligations under section 7 of the Act must be reconsidered if (1) new information reveals impacts of the proposed action that may affect listed species or critical habitat in a manner not previously considered, (2) the proposed action is subsequently modified to include activities which were not considered during this consultation, or (3) new species are listed or critical habitat designated that might be affected by the proposed action.

??

TDOT's standard construction BMPs would be implemented during the project. Equipment staging and maintenance areas should be developed an adequate distance from the stream to avoid entry of petroleum-based pollutants into the water.?? Concrete and cement dust must be kept out of the water as they alter chemical properties and can be toxic to aquatic species. This email will serve as our official project response.?? Please let me know if we can offer further assistance.?? Thanks,

??

John Griffith

Transportation Biologist
U.S. Fish and Wildlife Service
Tennessee Field Office
931-525-4995 (office)
931-528-7075 (fax)
??

From: Eric Philipps <Eric.Philipps@tn.gov>

Sent: Thursday, June 21, 2018 2:07 PM

To: john_griffith@fws.gov

Cc: Randall E. Mann <Randall.E.Mann@tn.gov>; Lou Timms <Lou.Timms@tn.gov>; Jared McCoy <Jared.McCoy@tn.gov>; Dustin Tucker <Dustin.Tucker@tn.gov>; Rita M. Thompson <Rita.M.Thompson@tn.gov>; Greg Harris <Greg.Harris@tn.gov>

Subject: [EXTERNAL] Fayette County, SR-193 (Macon Road) Bridge over Branch, PIN 124285.00

??

John,

Tennessee Wildlife Resource Agency Coordination

From: [Casey Parker](#)
To: [Eric Philipps](#); [TDOT Env. Local Programs](#)
Cc: [Rob Todd](#)
Subject: RE: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00
Date: Wednesday, July 11, 2018 12:27:26 PM
Attachments: [image002.png](#)
[image003.png](#)

Subject: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00

Mr. Eric Philipps,

The Tennessee Wildlife Resources Agency has reviewed the information that you provided regarding the proposed SR-193 (Macon Drive) Bridge in Fayette County, Tennessee and we have no concerns regarding the project and do not anticipate adverse impacts to state listed species under our authority due to the project. Thank you for the opportunity to review and comment on this proposed project, please contact me if you need further assistance.

Casey Parker - Wildlife Biologist
Liaison to TDOT & Federal Highway Administration
Tennessee Wildlife Resources Agency
Environmental Services Division
Email: casey.parker@tn.gov



From: Eric Philipps
Sent: Thursday, June 21, 2018 2:41 PM
To: Casey Parker
Cc: Rob Todd; Randall E. Mann; Lou Timms; Jared McCoy; Dustin Tucker; Rita M. Thompson; Greg Harris
Subject: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00

Casey,


TDOT proposes to replace the subject bridge in Fayette County. Please find attached KMZ file, species maps, species list, and plan sheet. If you have any questions or require additional information, please do not hesitate to contact me.



Thanks,



Eric Philipps | Environmental Studies Specialist

PIN 128133.02
SR-193 (Macon Road)
Bridge over Branch, LM 11.48
Fayette County, Tennessee





PANEL 0315C

FIRM
FLOOD INSURANCE RATE MAP
FAYETTE COUNTY,
TENNESSEE
AND INCORPORATED AREAS

PANEL 315 OF 605
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
FAYETTE COUNTY	470382	0315	C
OKLAND, TOWN OF	470418	0315	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
47047C0315C

EFFECTIVE DATE
NOVEMBER 5, 2008

Federal Emergency Management Agency

NATIONAL FLOOD INSURANCE PROGRAM

PIN 128113.02
 SR-193 Bridge over Branch, LM 11.48
 Fayette County, TN

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov



TENNESSEE HISTORICAL COMMISSION
STATE HISTORIC PRESERVATION OFFICE
2941 LEBANON PIKE
NASHVILLE, TENNESSEE 37243-0442
OFFICE: (615) 532-1550
www.tnhistoricalcommission.org

June 12, 2018

Ms. Katherine Looney
Tennessee Department of Transportation
505 Deaderick St
Suite 900
Nashville, TN 37243-1402

RE: FHWA / Federal Highway Administration, Replacement of the SR 193 Bridge over Branch,
Log Mile 11.48/ PIN 124285.00, , Fayette County, TN

Dear Ms. Looney:

In response to your request, we have reviewed the architectural survey report and accompanying documentation submitted by you regarding the above-referenced undertaking. Our review of and comment on your proposed undertaking are among the requirements of Section 106 of the National Historic Preservation Act. This Act requires federal agencies or applicants for federal assistance to consult with the appropriate State Historic Preservation Office before they carry out their proposed undertakings. The Advisory Council on Historic Preservation has codified procedures for carrying out Section 106 review in 36 CFR 800 (Federal Register, December 12, 2000, 77698-77739).

Considering the information provided, we concur that no architectural resources eligible for listing in the National Register of Historic Places will be affected by this undertaking. If project plans are changed or archaeological remains are discovered during project construction, please contact this office to determine what further action, if any, will be necessary to comply with Section 106 of the National Historic Preservation Act. Questions or comments may be directed to Casey Lee (615 253-3163).

Your cooperation is appreciated.

Sincerely,



E. Patrick McIntyre
Executive Director and
State Historic Preservation Officer

EPM/cjl



TENNESSEE HISTORICAL COMMISSION
STATE HISTORIC PRESERVATION OFFICE
2941 LEBANON PIKE
NASHVILLE, TENNESSEE 37243-0442
OFFICE: (615) 532-1550
www.tnhistoricalcommission.org

July 24, 2018

Mr. Phillip R. Hodge
Tennessee Department of Transportation
Suite 900, James K. Polk Building
505 Deaderick Street
Nashville, TN 37243-1402

RE: FHWA / Federal Highway Administration, SR-193 (Macon Road) Bridge Replacement over Unknown Branch, Log Mile 11.48, Fayette County, TN

Dear Mr. Hodge:

In response to your request, we have reviewed the archaeological report of investigations and accompanying documentation submitted by you regarding the above-referenced undertaking. Our review of and comment on your proposed undertaking are among the requirements of Section 106 of the National Historic Preservation Act. This Act requires federal agencies or applicants for federal assistance to consult with the appropriate State Historic Preservation Office before they carry out their proposed undertakings. The Advisory Council on Historic Preservation has codified procedures for carrying out Section 106 review in 36 CFR 800 (Federal Register, December 12, 2000, 77698-77739).

Considering the information provided, we find that no archaeological resources eligible for listing in the National Register of Historic Places will be affected by this undertaking. If project plans are changed or archaeological remains are discovered during project construction, please contact this office to determine what further action, if any, will be necessary to comply with Section 106 of the National Historic Preservation Act. Complete and/or updated Tennessee Site Survey Forms should be submitted to the Tennessee Division of Archaeology for all sites recorded and/or revisited during the current investigation. Questions or comments may be directed to Jennifer Barnett (615) 687-4780.

Your cooperation is appreciated.

Sincerely,

E. Patrick McIntyre, Jr.
Executive Director and
State Historic Preservation Officer

EPM/jmb

Project Design

Index Of Sheets

PRELIMINARY INDEX OF SHEETS

TITLE SHEET.....	1
TYPICAL SECTIONS.....	2B
RIGHT-OF-WAY NOTES, UTILITY NOTES and UTILITY OWNERS.....	3
RIGHT-OF-WAY ACQUISITION TABLE(S) and PROPERTY MAP(S).....	3A
PRESENT LAYOUT(S).....	4
RIGHT OF WAY DETAILS.....	4A
PROPOSED LAYOUT(S).....	4B
PROPOSED PROFILE(S).....	4C
PRIVATE DRIVE, BUSINESS, AND FIELD ENTRANCE PROFILE(S).....	5
DRAINAGE MAP(S).....	6
CULVERT SECTION(S).....	7
ROADWAY CROSS SECTIONS.....	8-15

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING

FAYETTE COUNTY

S.R. 193 (MACON RD.) BRIDGE REPLACEMENT
OVER BRANCH AT L.M. 11.48

PRELIMINARY


STATE HIGHWAY NO. 193 U.S. ROUTE NO.

DOES THIS PROJECT QUALIFY FOR UTILITY CHAPTER 86	YES X	NO
--	-------	----

TENN.	YEAR	SHEET NO.
	2019	1
FED. AID PROJ. NO.	BR-STP-193(11)	
STATE PROJ. NO.	24029-0207-94	

PROJECT LOCATION

BRIDGE ID. # 24015420001



PROJECT LOCATION

BRIDGE ID. #

24029-0207-94
END PROJECT NO. BR-STP-193(11) PRELIMINARY

STA. 33+40.00
N 317293.6523 E 940246.0523

24029-0207-94
BEGIN PROJECT NO. BR-STP-193(11) PRELIMINARY

STA. 28+00.00
N 317457.4133 E 939732.1443

SPECIAL NOTES

PROPOSALS MAY BE REJECTED BY THE COMMISSIONER IF ANY OF THE UNIT PRICES CONTAINED THEREIN ARE OBVIOUSLY UNBALANCED, EITHER EXCESSIVE OR BELOW THE REASONABLE COST ANALYSIS VALUE.

THIS PROJECT TO BE CONSTRUCTED UNDER THE STANDARD SPECIFICATIONS OF THE TENNESSEE DEPARTMENT OF TRANSPORTATION DATED JANUARY 1, 2015 AND ADDITIONAL SPECIFICATIONS AND SPECIAL PROVISIONS CONTAINED IN THE PLANS AND IN THE PROPOSAL CONTRACT.


TDOT C.E. MANAGER 1 OR
TDOT TRANSPORTATION MANAGER 1 : STEPHANIE KISSELL

DESIGNED BY : HDR ENGINEERING, INC.

DESIGNER : GREG CLUCKER CHECKED BY KEVIN CAGLE

P.E. NO. 24029-0207-94 (NEPA)

PIN NO. 128113.02



SCALE: 1"= 1/2 MILES



R.O.W. LENGTH	0.102 MILES
ROADWAY LENGTH	0.091 MILES
BRIDGE LENGTH	0.000 MILES
BOX BRIDGE LENGTH	0.011 MILES
BOX BRIDGE LENGTH	0.000 MILES ▲
PROJECT LENGTH	0.102 MILES

▲ Not included in the project length (Non Riding Surface).

NO EXCLUSIONS

PRELIMINARY
PLANS

CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY

APPROVED: Paul D. Degges
PAUL D. DEGGES, CHIEF ENGINEER

DATE: _____

APPROVED: Clay Bright
CLAY BRIGHT, COMMISSIONER


S.R. 193	
SURVEY 02-14-18	TRAFFIC DATA
	ADT (2022) 1540
	ADT (2042) 1730
	DHV (2042) 190
	D 65 - 35
	T (ADT) 4 %
	T (DHV) 3 %
	V 45 MPH

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

APPROVED: _____
DIVISION ADMINISTRATOR DATE

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	2B




SUPERELEVATED SECTION
(BASED ON STD. DWG. RD11-TS-2)

STA. 28+00.00 TO STA. 33+40.00

(A) THE SLOPES OF THE SHOULDER AND ROADWAY PAVEMENT SHALL NOT EXCEED AN ALGEBRAIC DIFFERENCE OF 0.07.

BUSINESS
SURFACE - 1 1/4"
BINDER - 2"
BASE - 4"



FIELD OR RESIDENTIAL
SURFACE - 1 1/2"
BINDER - NONE
BASE - 4"



NOTE: DITCH TO BE CONSTRUCTED WHERE DIRECTED BY THE ENGINEER

TYPICAL SECTION
PRIVATE DRIVE TO BUSINESS,
FIELD, OR RESIDENTIAL PROPERTY

SPECIAL DITCHES



CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TYPICAL
SECTIONS

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	3

RIGHT-OF-WAY

- (1) ALL RAMPS MUST CONFORM TO THE DEPARTMENT'S "POLICY ON FINANCING CONSTRUCTION OF PUBLIC ROAD INTERSECTIONS AND DRIVEWAYS ON HIGHWAY RESURFACING, RECONSTRUCTION AND CONSTRUCTION PROJECTS ON NEW LOCATIONS", THE MANUAL ON RULES AND REGULATIONS FOR CONSTRUCTING DRIVEWAYS ON STATE HIGHWAY RIGHT-OF-WAY, STANDARD DRAWING RP-R-1, AND OTHER ACCEPTED DESIGN AND SAFETY STANDARDS.
- (2) EXISTING PAVED DRIVEWAY PER TRACT REMAINDER WILL BE REPLACED IN KIND TO A TOUCHDOWN POINT.
- (3) WHERE THE EXISTING DRIVEWAY IS UNPAVED AND THE PROPOSED DRIVEWAY EXCEEDS 7 PERCENT IN GRADE, EACH DRIVEWAY WILL BE PAVED TO A TOUCHDOWN POINT OR UNTIL THE GRADE IS LESS THAN 7 PERCENT.
- (4) WHERE THE EXISTING DRIVEWAY IS UNPAVED AND THE PROPOSED DRIVEWAY IS LESS THAN 7 PERCENT IN GRADE, EACH DRIVEWAY WILL BE PAVED A SHOULDER WIDTH FROM THE EDGE OF PAVEMENT AND THE REMAINDER OF THAT DRIVEWAY REPLACED IN KIND TO A TOUCHDOWN POINT.
- (5) ANY NECESSARY PAVING OF DRIVEWAYS WILL BE DONE DURING PAVING OPERATIONS ON THE MAIN ROADWAY.
- (6) NEW DRIVEWAYS PROVIDED IN THE PLANS WILL BE PAVED BASED ON THE 7 PERCENT CRITERIA. THOSE 7 PERCENT OR STEEPER IN GRADE WILL BE PAVED AND THOSE FLATTER THAN 7 PERCENT WILL BE COVERED WITH BASE STONE.
- (7) ON PROJECTS WITHOUT CURB AND GUTTER THAT ARE ON STATE ROUTES, IT WILL BE THE RESPONSIBILITY OF THE OWNER TO SECURE A PERMIT AND TO CONSTRUCT ADDITIONAL DRIVEWAYS AND FIELD ENTRANCES OTHER THAN THOSE PROVIDED IN THE PLANS.

UTILITY

- (1) THE LOCATIONS OF UTILITIES SHOWN WITHIN THESE PLANS ARE APPROXIMATE ONLY. EXACT LOCATIONS SHALL BE DETERMINED IN THE FIELD BY CONTACTING THE UTILITY COMPANIES INVOLVED. NOTIFICATION BY CALLING THE TENNESSEE ONE CALL SYSTEM, INC., AT 1-800-351-1111 AS REQUIRED BY TCA 65-31-106 WILL BE REQUIRED.
- (2) UNLESS OTHERWISE NOTED, ALL UTILITY ADJUSTMENTS WILL BE PERFORMED BY THE UTILITY OR ITS REPRESENTATIVE. THE CONTRACTOR AND UTILITY OWNERS WILL BE REQUIRED TO COOPERATE WITH EACH OTHER IN ORDER TO EXPEDITE THE WORK REQUIRED BY THIS CONTRACT. ON CONTRACTS WHERE CONSTRUCTION STAKES, LINES, AND GRADES ARE CONTRACT ITEMS, THE CONTRACTOR WILL BE REQUIRED TO PROVIDE RIGHT-OF-WAY OR SLOPE STAKES, DITCH OR STREAM BED GRADES, OR OTHER ESSENTIAL SURVEY STAKING TO PREVENT CONFLICTS WITH THE HIGHWAY CONSTRUCTION. FREQUENTLY, THIS WILL BE REQUIRED AS THE FIRST ITEM OF WORK AND AT ANY LOCATION ON THE PROJECT DIRECTED BY THE ENGINEER.
- (3) THE CONTRACTOR WILL PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION OF THIS PROJECT. IN THE EVENT THAT SPECIAL EQUIPMENT IS REQUIRED TO WORK OVER AND AROUND THE UTILITIES, THE CONTRACTOR WILL BE REQUIRED TO FURNISH SUCH EQUIPMENT. THE COST OF PROTECTING UTILITIES FROM DAMAGE AND FURNISHING SPECIAL EQUIPMENT WILL BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF CONSTRUCTION.
- (4) PRIOR TO SUBMITTING HIS BID, THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR CONTACTING OWNERS OF ALL AFFECTED UTILITIES IN ORDER TO DETERMINE THE EXTENT TO WHICH UTILITY RELOCATIONS AND/OR ADJUSTMENTS WILL HAVE UPON THE SCHEDULE OF WORK FOR THE PROJECT. WHILE SOME WORK MAY BE REQUIRED 'AROUND' UTILITY FACILITIES THAT WILL REMAIN IN PLACE, OTHER UTILITY FACILITIES MAY NEED TO BE ADJUSTED CONCURRENTLY WITH THE CONTRACTOR'S OPERATIONS. ADVANCE CLEAR CUTTING MAY BE REQUIRED BY THE ENGINEER AT ANY LOCATION WHERE CLEARING IS CALLED FOR IN THE SPECIFICATIONS AND CLEAR CUTTING IS NECESSARY FOR A UTILITY RELOCATION. ANY ADDITIONAL COST WILL BE INCLUDED IN THE UNIT PRICE BID FOR THE CLEARING ITEM SPECIFIED IN THE PLANS.
- (5) THE CONTRACTOR SHALL NOTIFY EACH INDIVIDUAL UTILITY OWNER OF HIS PLAN OF OPERATION IN THE AREA OF THE UTILITIES. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNERS AND REQUEST THEM TO PROPERLY LOCATE THEIR RESPECTIVE UTILITY ON THE GROUND. THIS NOTIFICATION SHALL BE GIVEN AT LEAST THREE (3) BUSINESS DAYS PRIOR TO COMMENCEMENT OF OPERATIONS AROUND THE UTILITY IN ACCORDANCE WITH TCA 65-31-106.

UTILITY OWNERS

CABLE:

AT&T - JACKSON

315 EAST COLLEGE ST.
JACKSON, TN 38301

CONTACT: COREY BARTHOLOMEW

OFFICE PHONE: 731 423 0521

CELL PHONE:

Email:

ELECTRIC:

CHICKASAW ELECTRIC COOPERATIVE

17970 HWY 64 EAST

SOMERVILLE, TN 38068

CONTACT: LLOYD MUNCY

OFFICE PHONE: 901 465 3591

CELL PHONE:

Email:

GAS:

SOMERVILLE LIGHT, GAS & WATER

13085 NORTH MAIN ST.

SOMERVILLE, TN 38068

CONTACT: AUSTIN EDMUNDSON

OFFICE PHONE: 901 465 7300

CELL PHONE:

Email:

TELEPHONE:

AT&T - JACKSON

315 EAST COLLEGE ST.

JACKSON, TN 38301

CONTACT: COREY BARTHOLOMEW

OFFICE PHONE: 731 423 0521

CELL PHONE:

Email:



**CAUTION !
PRELIMINARY
PLANS
SUBJECT TO
CHANGE**

SEALED BY

**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION**

RIGHT-OF-WAY
NOTES,
UTILITY NOTES
AND
UTILITY OWNERS

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	3A



CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

DISTURBED AREA	
IN BETWEEN SLOPE LINES	0.706 (AC)
15 FOOT WIDE STRIP (OUT SIDE SLOPE LINES)	0.415 (AC)
TOTAL DISTURBED AREA	1.121 (AC)

SEALED BY

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.

**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION**

PROPERTY MAP
AND
RIGHT-OF-WAY
ACQUISITION
TABLE

R.O.W. ACQUISITION TABLE

TRACT NO.	PROPERTY OWNERS	COUNTY RECORDS				TOTAL AREA (ACRES)			AREA TO BE ACQUIRED (ACRES)			AREA REMAINING (ACRES)				EASEMENT (ACRES)					
		TAX MAP NO.	PARCEL NO.	DEED DOCUMENT REFERENCE		LEFT	RIGHT	TOTAL	LEFT	RIGHT	TOTAL	LEFT	RIGHT	PERMANENT	SLOPE	CONSTRUCTION	AIR RIGHTS				
				BOOK	PAGE																
1	Senter Cawthon Crook, Jere Lawrence Crook, III, Russell E. Bloodworth, and John S. Evans, Trustees		9	060	06010			167.410	167.410			0.441	0.441			166.969					
2	Sherry B. Clayton		29.04	423	175			24.600	24.600							24.600					
3	Jacquelyn Simons		29.07	470	00865			7.170	7.170							7.170					
4	Shirley F. Hailey		29.03	641	124	42.370		42.370	42.370	0.459		0.459	41.911			21.200					
5	Rickey D. Hailey Sr and wife, Pamela J.		29.02	642	370			21.200	21.200							21.200					
ACQUISITION TOTALS (ACRES)																					

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	4

SR 193
 PI 28+47.18
 N 317,455.4183
 E 939,779.8372
 Δ 11° 47' 25" (RT)
 D 2° 56' 18"
 R 1,950.00
 L 401.27
 T 201.35
 SE 0.046 FT/FT
 DESIGN SPEED 45 MPH
 TRANS. LENGTH 134'

SR 193
 PI 33+24.74
 N 317,279.7464
 E 940,225.4387
 Δ 18° 22' 10" (LT)
 D 4° 09' 42"
 R 1,376.72
 L 441.39
 T 222.60
 SE 0.058 FT/FT
 DESIGN SPEED 45 MPH
 TRANS. LENGTH 159'

④
 SHIRLEY F. HAILEY

⑤
 RICKEY D. HAILEY, SR.
 AND WIFE,
 PAMELA J. HAILEY

②
 SHERRY B.
 CLAYTON

③
 JACQUELINE SIMONS

END PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 33+40.00
 N 317293.6523
 E 940246.0523

BEGIN PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 28+00.00
 N 317457.4133
 E 939732.1443

①
 SENTER CAWTHON CROOK,
 JERE LAWRENCE CROOK, III,
 RUSSELL E. BLOODWORTH,
 AND JOHN S. EVANS, TRUSTEES

CAUTION!
 PRELIMINARY
 PLANS
 SUBJECT TO
 CHANGE

SEALED BY

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.


STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION

PRESENT
 LAYOUT

STA. 28+00 TO STA. 33+40
 SCALE: 1"= 50'

6/12/2019 12:00:40 PM
 c:\pwworking\least01\0926577\004.sht

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	4A



BEGIN PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 28+00.00
 N 317457.4133
 E 939732.1443

END PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 33+40.00
 N 317293.6523
 E 940246.0523

CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.

STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION

RIGHT OF WAY
DETAILS

STA. 28+00 TO STA. 33+40
 SCALE: 1"= 50'

④
 SHIRLEY F. HAILEY

30

⑤
 RICKEY D. HAILEY, SR.
 AND WIFE,
 PAMELA J. HAILEY


②
 SHERRY B.
 CLAYTON

③
 JACQUELINE SIMONS

①
 SENTER CAWTHON CROOK,
 JERE LAWRENCE CROOK, III,
 RUSSELL E. BLOODWORTH,
 AND JOHN S. EVANS, TRUSTEES

6/12/2019 12:00:50 PM
 c:\pwworking\least01\0926577\004A.sht


TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	4B



25

30

35



END PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 33+40.00
 N 317293.6523
 E 940246.0523

BEGIN PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 28+00.00
 N 317457.4133
 E 939732.1443

CAUTION!
 PRELIMINARY
 PLANS
 SUBJECT TO
 CHANGE

SEALED BY


COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.

STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION

PROPOSED
 LAYOUT

STA. 28+00 TO STA. 33+40
 SCALE: 1"= 50'

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	4C



CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00000 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.


**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION**

**PROPOSED
PROFILE**
STA. 28+00 TO STA. 33+40
SCALE: 1"= 50' HORIZ.
1"= 5' VERT.

BOX \ SLAB BRIDGE or CULVERT	
STATION: 30+77.00	
STRUCTURE: 56' OF PROP. 2@ 18'X9' RCBB	
SKEW	45 DEG.
DRAINAGE AREA	736 AC.
DESIGN DISCHARGE (Q10)	794 CFS
DESIGN DISCHARGE (Q100)	560 CFS
OVERTOPPING	470.29 ELEV.
ALLOWABLE HEADWATER	ELEV.
Q10 HEADWATER	406.62 ELEV.
Q100 HEADWATER	407.73 ELEV.
VELOCITY (Q10)	7.59 FT/S
VELOCITY (Q100)	7.77 FT/S
INLET	398.79 ELEV.
OUTLET	398.79 ELEV.
STANDARD DRAWING NOS.:	
QUANTITIES:	
CLASS "A" CONCRETE	C.Y.
STEEL BAR REINFORCING	LB.
BACKFILL	TDNS
FOUNDATION FILL MATERIAL	C.Y.

6/12/2019 12:01:09 PM c:\pwworking\least01\0926577\004C.sht

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	5



CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE


SEALED BY

COORDINATES ARE NAD 83(1995), ARE DATUM ADJUSTED BY THE FACTOR OF 1.00005 AND TIED TO THE TGRN. ALL ELEVATIONS ARE REFERENCED TO THE NAVD 1988 WITH GEOID 03.

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PRIVATE DRIVE,
BUSINESS, AND
FIELD ENTRANCE
PROFILE

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	6



BEGIN PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 28+00.00
 N 317457.4133
 E 939732.1443

S 81° 21' 39" E S 80° 56' 21" E S 80° 16' 27" E
 SR 193 MACON RD S.R. 193

BEGIN EX. BRIDGE
 30+57.61

D.A. 1.22 SQ. MI.
 65% WOODED HILLS
 25% ROLLING CULT
 10% ASPH. ROAD

56' OF PROP. 2 @
 18'X9' RCBB
 STA. 30+77.00
 SKEW 45°

2 SPAN, CONC.
 BEAM BRIDGE
 NO. 24015420001

S 68° 29' 02" E
 BRANCH
 STR-1

END EX. BRIDGE
 30+94.90

END PROJ. NO. BR-STP-193(11) R.O.W.
 STA. 33+40.00
 N 317293.6523
 E 940246.0523

S 86° 51' 12" E

CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY


COORDINATES ARE NAD 83(1995), ARE
 DATUM ADJUSTED BY THE FACTOR
 OF 1.00000 AND TIED TO THE TGRN.
 ALL ELEVATIONS ARE REFERENCED
 TO THE NAVD 1988 WITH GEOID 03.

STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION

DRAINAGE
MAP

STA. 28+00 TO STA. 33+40
 SCALE: 1"=200'

TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	7



BOX \ SLAB BRIDGE or CULVERT	
STATION: 30+77.00	
STRUCTURE: 56' OF 2 @ 18' X 9' RCBB	
SKEW	45 DEG.
DRAINAGE AREA	736 AC.
DESIGN DISCHARGE (Q10)	794 CFS
DESIGN DISCHARGE (Q100)	560 CFS
OVERTOPPING	407.29 ELEV.
ALLOWABLE HEADWATER	ELEV.
Q10 HEADWATER	406.62 ELEV.
Q100 HEADWATER	407.73 ELEV.
VELOCITY (Q10)	7.59 FT/S
VELOCITY (Q100)	7.77 FT/S
INLET	398.79 ELEV.
OUTLET	398.79 ELEV.
STANDARD DRAWING NOS.:	
QUANTITIES:	
CLASS "A" CONCRETE	C.Y.
STEEL BAR REINFORCING	LB.
BACKFILL	TONS
FOUNDATION FILL MATERIAL	C.Y.

SR193
30+77.00


CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

SEALED BY

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

CULVERT
SECTION


6/12/2019 12:01:37 PM
c:\pwworking\least01\0926577\007.sht




28+50.00
CUT 54
FILL 9
TOPSOIL 23

28+25.00
CUT 54
FILL 6
TOPSOIL 20

28+00.00




6/12/2019 12:01:47 PM
 c:\pwworking\ecost01\d0926577\FASR93\XSSheets.sht



6/12/2019 12:01:48 PM
 c:\pwworking\ecst10\d0926577\FASR93\XSSheets.sht


430
420
410
400

430
420
410
400



430
420
410
400

430
420
410
400



430
420
410
400

430
420
410
400



SR 193
BEGIN STA. 30+25.00
END STA. 30+75.00

430
420
410
400

430
420
410
400

430
420
410
400

430
420
410
400

430
420
410
400

430
420
410
400

31+50.00
CUT 130
FILL 50
TOPSOIL 44

31+25.00
CUT 47
FILL 58
TOPSOIL 30

31+00.00
CUT 43
FILL 182
TOPSOIL 42

SR 193

BEGIN STA. 31+00.00
END STA. 31+50.00

6/12/2019 12:01:49 PM
c:\pwworking\ecos10\d0926577\FASR93\XSSheets.sht

140 120 100 80 60 40 20 0 20 40 60 80 100 120 140

430
420
410
400
390

430
420
410
400
390

430
420
410
400
390

430
420
410
400
390

430
420
410
400
390

430
420
410
400
390

390

390

32+25.00

CUT 94
FILL 20
TOPSOIL 37

32+00.00

CUT 117
FILL 29
TOPSOIL 41


31+75.00

CUT 130
FILL 41
TOPSOIL 43

SR 193

BEGIN STA. 31+75.00
END STA. 32+25.00

6/12/2019 12:04:50 PM
c:\pwworking\ecs\10\d0926577\FASR193\S\Sheets.sht



430
420
410
400
390

430
420
410
400
390

33+00.00

CUT 69
FILL 3
TOPSOIL 26

430
420
410
400
390

430
420
410
400
390

32+75.00

CUT 65
FILL 3
TOPSOIL 27

430
420
410
400
390

430
420
410
400
390

32+50.00


CUT 55
FILL 4
TOPSOIL 24

SR 193



BEGIN STA. 32+50.00
END STA. 33+00.00

6/12/2019 12:04:51PM c:\pwworking\egst01\d0926577\FASR193\XSSheets.sht

140 120 100 80 60 40 0 20 40 60 80 100 120 140



TYPE	YEAR	PROJECT NO.	SHEET NO.
PRELIM	2019	BR-STP-193(11)	15



CUT 68
FILL 2
TOPSOIL 26

SR 193

BEGIN STA. 33+25.00
END STA. 33+40.00

Ecology

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Ecology

Study Results

Based on the plans dated 6/12/2019, the environmental boundaries report dated 7/16/2018 for PIN 124285.00 is still valid for this project.

Commitments

Did the study of this project result in any environmental commitments?

Yes

Cliff swallow and barn swallow nests, eggs, or birds (young and adults) will not be disturbed between April 15 and July 31. From August 1 to April 14, nests can be removed or destroyed, and measures implemented to prevent future nest building at the site (e.g., closing off area using netting).

Additional Information

Is there any additional information or material included with this study?

Yes

Type: Environmental Boundaries Report (EBR)

Location: FileNet

Certification

Responder: Dustin Tucker

Title: TESS Advanced

Signature: Dustin
Tucker

Digitally signed by
Dustin Tucker
Date: 2019.07.03
08:44:44 -05'00'



Environmental Boundaries Report

SR-193 (Macon Drive) Bridge over Branch, LM 11.48

Project Number: 24029-0207-94

PIN: 124285.00

Fayette County, Tennessee

**Prepared by:
Tennessee Department of Transportation – TDOT
Region 4**

Environmental Boundaries Report Index

Memo	Page 3
Maps and Topos	Page 5
NEPA Impact Table	Page 7
Normal Rainfall Calculation	Page 8
Stream Data Sheets	Page 9
Wet Weather Conveyance Data Sheets	Page 10
Species Review	Page 13
Special Notes... ..	Page 20
Marked-up Plan Sheets	Page 21
Photo Log	Page 22



**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
REGION 4 ENVIRONMENTAL TECH OFFICE
300 BENCHMARK PLACE
JACKSON, TENNESSEE 38301
(731) 935-0139**

JOHN C. SCHROER
COMMISSIONER

BILL HASLAM
GOVERNOR

MEMORANDUM

To: Dennis Moultrie
Design Division

From: Eric Philipps
Environmental Tech Office, Region 4

Eric Philipps

Digitally signed by Eric Philipps
Date: 2018.07.20 15:22:59
-05'00'

Date: July 16, 2018

Subject: **Environmental Boundaries For:** Fayette County, SR-193 (Macon Drive),
Bridge over Branch, LM 11.48
PE: 24029-0207-94 **PIN:** 124285.00

An ecological evaluation of the subject project has been conducted with the following results:

SPRINGS/STREAMS

There is **one (1)** stream within the project limits.

- Information concerning the quality and amount of impact can be found in the attached impact table.

WET WEATHER CONVEYANCES/UPLAND DRAINAGE FEATURES

There is one (1) wet weather conveyance/upland drainage feature within the project limits.

WETLANDS

There are **no** wetlands within the project limits.

OTHER FEATURES

There are **no** other features noted within the project limits.



PROTECTED SPECIES

A search of the TDEC rare species database was performed on June 21, 2018. Coordination with TWRA and USFWS is included within this report.

Your assistance is appreciated. If you have any questions or comments, please contact Eric Philipps in the Region 4 Environmental Tech Office at 731-935-0174 or eric.philipps@tn.gov.

xc: Tabitha Cavaness
Rachel Webb
Gary Scruggs
Randall Mann
Lou Timms
Jared McCoy
Glen Blakenship
James Boyd
John Hewitt
D.J. Wiseman
Michael White
Khalid Ahmed
Sharon Sanders
Rita Thompson
Greg Harris

TDOT.ENV.NEPA
R4.ENVTechOffice
TDOT. Env. Ecology
TDOT.Env.Mitigation
TDOT.Env.Permits





Fayette County; SR-193 (Macon Road), Bridge over Unknown Branch, LM 11.48

**P.E. 24029-0207-94
PIN 124285.00**

07/03/2018





Fayette County; SR-193 (Macon Road), Bridge over Unknown Branch, LM 11.48

**P.E. 24029-0207-94
PIN 124285.00**

07/03/2018



Preliminary Impact Form

County: Fayette

Route: SR-193

PIN: 124285.00

Date Prepared: 7/17/2018

Prepared by:
 TDOT Region 4 - Environmental Tech Office

NOTE: *This document is for "preliminary" use only and will not be considered accurate until the time of permit application.*

Streams

Labels	Type *	Function	Quality	Impacts (feet)		
				Permanent	Temporary	Total
STR-1	Stream		Undetermined at this time	100		100
			Total	100		100

* Identification of features has not been reviewed by regulatory agencies. Determinations could change.

Table 1. Calculation of Normal Weather Conditions / Ames Plantation, TN - June 2018
 Source: AgAcis, 1988-2018 WETS, Ames Plantation

		Long-term Rainfall Records								
	Month	Minus one Std. Dev (DRY)	Normal (Mean Inches)	Plus One Std. Dev. (WET)	Actual Rainfall	Condition	Condition Value	Month Weight Value	Product of Previous two columns	
1st month prior	May	3.73	5.69	6.84	6.77	Normal	2	3	6	
2nd Month prior	Apr	4.01	5.46	6.42	6.37	Normal	2	2	4	
3rd month prior	Mar	4.07	5.59	6.58	7.86	Wet	3	1	3	
								Sum	13	

Note:	
If sum is:	
6-9	then prior period has been drier than normal
10-14	then prior period has been normal
15-18	then prior period has been wetter than normal

Condition Value	
Dry =	1
Normal =	2
Wet=	3

Conclusions:
 Prior period has been normal.

Ecology Field Data Sheet: Water Resources

Project:		Fayette County; SR-193 (Macon Drive) Bridge over Unknown Branch, LM 11.48					
Biologist:	Eric Philipps	Affiliation:	TDOT	Date:	06/13/2018		
1-Station: from plans	No stations						
2-Map label and name	STR-1						
3-Latitude/Longitude	Crossing SR-193 at approx. 35.155602, -89.441124						
4-Potential impact	Encapsulation/Fill						
5-Feature description:							
-channel identification	<input checked="" type="checkbox"/> perennial stream	<input type="checkbox"/> intermittent stream	<input type="checkbox"/> ephemeral stream	<input type="checkbox"/> wwc			
-HD score (if applicable)							
-OHWM indicators	bed & banks <input checked="" type="checkbox"/>	deposition <input checked="" type="checkbox"/>	presence of litter / debris <input checked="" type="checkbox"/>	scour <input checked="" type="checkbox"/>	veg absent, bent, matted <input checked="" type="checkbox"/>		
	change in plant community <input checked="" type="checkbox"/>	destruction of terrestrial veg <input checked="" type="checkbox"/>	multiple observed flow events <input type="checkbox"/>	sediment sorting <input checked="" type="checkbox"/>	water staining <input checked="" type="checkbox"/>		
	change in soil character <input checked="" type="checkbox"/>	leaf litter disturbed absent <input checked="" type="checkbox"/>	natural line impressed on bank <input checked="" type="checkbox"/>	shelving <input checked="" type="checkbox"/>	wracking <input checked="" type="checkbox"/>		
-sinuosity	<input type="checkbox"/> absent	<input checked="" type="checkbox"/> weak	<input type="checkbox"/> moderate	<input type="checkbox"/> strong			
-channel bottom width	~6 ft		-top of bank width	~15 ft			
- avg. gradient of stream (%)	Low						
-bank height and slope ratio	LDB - ~8 ft		RDB - ~8 ft				
-water flow	<input type="checkbox"/> fast	<input type="checkbox"/> moderate	<input checked="" type="checkbox"/> slow	<input type="checkbox"/> isolated pools	<input type="checkbox"/> none		
-water depth (riffles / pools)	~.5 ft		water width (riffles / pools)		~6 ft		
-bank stability: LDB, RDB	LDB:	Stable <input checked="" type="checkbox"/>	Eroding <input type="checkbox"/>	Undercutting <input type="checkbox"/>	Sloughing <input type="checkbox"/>	Exposed Roots <input type="checkbox"/>	
	RDB:	Stable <input checked="" type="checkbox"/>	Eroding <input type="checkbox"/>	Undercutting <input type="checkbox"/>	Sloughing <input type="checkbox"/>	Exposed Roots <input type="checkbox"/>	
-dominant riparian species: ------(LDB /RDB)-----	LDB: Boxelder, black walnut, elderberry, sumac						
	RDB: Boxelder, black walnut, elderberry, sumac						
-habitat assessment score	75						
	epifaunal substrate	3	channel alteration	5			
	channel substrate	3	channel sinuosity	4			
	pool variability	2	bank stability	LDB	6	RDB 6	
	sediment deposition	6	bank vegetative protection	LDB	6	RDB 6	
	channel flow status	18	riparian veg zone width	LDB	5	RDB 5	
-benthos	Assumed						
-fish	Observed						
-algae or other aquatic life	Periphyton observed						
6-photo numbers	1, 2						
7-rainfall information	1.74" in previous 7 days						
8-HUC -12 Code & Name	080102100303 Shaws Creek						
9-Confirmed by:							
10-Assessed	yes <input type="checkbox"/>	no <input checked="" type="checkbox"/>					
11-ETW	yes <input type="checkbox"/>	no <input checked="" type="checkbox"/>					
12-303 (d) List	yes <input type="checkbox"/>	siltation <input type="checkbox"/>	habitat: <input type="checkbox"/>	other: <input type="checkbox"/>			
	no <input checked="" type="checkbox"/>						
13-Notes	<p>Stream is listed on TDEC waterviewer as Misc. Tribs to Shaws Creek (TN08010210021_0999).</p> <p>2 barn swallow nests and 2 juveniles observed under bridge.</p>						

Ecology Field Data Sheet: Water Resources

Project:		Fayette County; SR-193 (Macon Drive) Bridge over Unknown Branch, LM 11.48					
Biologist:	Eric Philipps	Affiliation:	TDOT	Date:	06/13/2018		
1-Station: from plans	No stations						
2-Map label and name	WWC-1						
3-Latitude/Longitude	From 35.155518, -89.441048 (confluence with STR-1) to 35.155483, -89.440559 (field drive north of SR-193)						
4-Potential impact	Encapsulation/Fill						
5-Feature description:							
-channel identification	perennial stream	intermittent stream	ephemeral stream	WWC			
-HD score (if applicable)	13						
-OHWM indicators	bed & banks <input type="checkbox"/>	deposition <input type="checkbox"/>	presence of litter / debris <input type="checkbox"/>	scour <input type="checkbox"/>	veg absent, bent, matted <input type="checkbox"/>		
	change in plant community <input type="checkbox"/>	destruction of terrestrial veg <input type="checkbox"/>	multiple observed flow events <input type="checkbox"/>	sediment sorting <input type="checkbox"/>	water staining <input type="checkbox"/>		
	change in soil character <input type="checkbox"/>	leaf litter disturbed absent <input type="checkbox"/>	natural line impressed on bank <input type="checkbox"/>	shelving <input type="checkbox"/>	wracking <input type="checkbox"/>		
-sinuosity	absent <input type="checkbox"/>	weak <input checked="" type="checkbox"/>	moderate <input type="checkbox"/>	strong <input type="checkbox"/>			
-channel bottom width	~2 ft		-top of bank width	~5 ft			
- avg. gradient of stream (%)	Low						
-bank height and slope ratio	LDB - ~6 ft			RDB - ~6 ft			
-water flow	fast <input type="checkbox"/>	moderate <input type="checkbox"/>	slow <input type="checkbox"/>	isolated pools <input checked="" type="checkbox"/>	none <input type="checkbox"/>		
-water depth (riffles / pools)	~.5 ft		water width (riffles / pools)	~2 ft			
-bank stability: LDB, RDB	LDB: Stable <input checked="" type="checkbox"/>	Eroding <input type="checkbox"/>	Undercutting <input type="checkbox"/>	Sloughing <input type="checkbox"/>	Exposed Roots <input type="checkbox"/>		
	RDB: Stable <input checked="" type="checkbox"/>	Eroding <input type="checkbox"/>	Undercutting <input type="checkbox"/>	Sloughing <input type="checkbox"/>	Exposed Roots <input type="checkbox"/>		
-dominant riparian species: ------(LDB /RDB)-----	LDB: American sweetgum, sumac, elderberry, elm						
	RDB: American sweetgum, sumac, elderberry, elm						
-habitat assessment score	0						
	epifaunal substrate		channel alteration				
	channel substrate		channel sinuosity				
	pool variability		bank stability		LDB	RDB	
	sediment deposition		bank vegetative protection		LDB	RDB	
	channel flow status		riparian veg zone width		LDB	RDB	
-benthos	None observed						
-fish	None observed						
-algae or other aquatic life	None observed						
6-photo numbers	3, 4						
7-rainfall information	1.74" in previous 24 hours						
8-HUC -12 Code & Name	080102100303 Shaws Creek						
9-Confirmed by:							
10-Assessed	yes <input type="checkbox"/>	no <input type="checkbox"/>					
11-ETW	yes <input type="checkbox"/>	no <input type="checkbox"/>					
12-303 (d) List	yes <input type="checkbox"/>	siltation <input type="checkbox"/>	habitat: <input type="checkbox"/>	other: <input type="checkbox"/>			
	no <input type="checkbox"/>						
13-Notes	Single pool of water observed near field drive east of bridge.						

Species reported within 1 mile radius of project:

Species Scientific and common names, followed by (A) for animal or (P) for plant	Status		Species is potentially present in R-O-W because: (A) it is listed by TDEC within ROW (B) habitat is present (C) observed during site visit (D) critical habitat present within ROW	Species is considered likely NOT present in R-O-W because: (A) Present habitat unsuitable (B) Not observed during site visit (C) Original record questionable (D) Considered extinct/extirpated	Accommodations to minimize impacts: (A) BMPs are sufficient to protect species (B) Special Notes are included on project plans (C) Individuals will be impacted. (D) Accommodations not practical due to broad habitat description or mobility of species	Habitat (include blooming, breeding or other information; where found according to TDEC database; year last observed; reference)	Notes
	Fed	TN					
None							

Species reported within 1-mile to 4-mile radius of project:

Species Scientific and common names, followed by (A) for animal or (P) for plant	Status		Species is potentially present in R-O-W because: (A) it is listed by TDEC within ROW (B) habitat is present (C) observed during site visit (D) critical habitat present within ROW	Species is considered likely NOT present in R-O-W because: (A) Present habitat unsuitable (B) Not observed during site visit (C) Original record questionable (D) Considered extinct/extirpated	Accommodations to minimize impacts: (A) BMPs are sufficient to protect species (B) Special Notes are included on project plans (C) Individuals will be impacted. (D) Accommodations not practical due to broad habitat description or mobility of species	Habitat (include blooming, breeding or other information; where found according to TDEC database; year last observed; reference)	Notes
	Fed	TN					
<i>Hyla gratiosa</i> (Barking tree frog) (A)	-	T		A	A	Low wet woods and swamps esp. with ephemeral ponds. 1993-08. Austin Peay State University Department of Zoology.	

Migratory Birds

List **significant concentrations** of migratory birds encountered within the project area (rookeries, aggregations, nesting areas, etc).

Species (Scientific and Common Name)	Approximate No. of Nests (or Individuals)	Location of Nests (or Individuals) (Include Latitude & Longitude)	Nesting Dates and Reference	Photograph #
Barn Swallow (<i>Hirundo rustica</i>)	2 nests, 2 juveniles	Underneath bridge (35.155602, -89.441124)	April 15 – July 31	

USFWS letter: Yes X (attached) No (explain)

Biological Assessment: Yes (response letter attached; see below) No X

Species (scientific and common names)	USFWS conclusion ¹
None	

¹ Choose from “no effect”; “not likely to adversely affect;” or “likely to adversely affect;”. If “likely to adversely affect” is chosen, indicate “no jeopardy to species and no adverse modification to habitat” or “jeopardy to species, or adverse modification to habitat” based on FWS concurrence letter

4 Mile T&E Species

SCIENTIFIC_NAME	COMMON_NAME	LAST_OBS_DATE	FED_PROTECTION	ST_PROTECTION	EO_RANK
Hyla gratiosa	Barking Tree Frog	1993-08	--	D	Verified extant

From: [John Griffith](#)
To: [Eric Philipps](#)
Cc: [Randall E. Mann](#); [Lou Timms](#); [Jared McCoy](#); [Dustin Tucker](#); [Rita M. Thompson](#); [Greg Harris](#)
Subject: RE: [EXTERNAL] Fayette County, SR-193 (Macon Road) Bridge over Branch, PIN 124285.00
Date: Friday, July 13, 2018 3:36:33 PM
Attachments: [image001.png](#)

***** This is an EXTERNAL email. Please exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email - STS-Security. *****

Eric,
??

Thank you for requesting our review of the proposed SR-193 Bridge replacement over a tributary to Shaws Creek at LM 11.48 in Fayette County, Tennessee.?? Upon review of the information provided and our database, we would not anticipate impacts to any federally listed or proposed species as a result of the project.?? Therefore, based on the best information available at this time, we believe that the requirements of section 7 of the Endangered Species Act (Act) of 1973, as amended, are fulfilled for all species that currently receive protection under the Act.?? Obligations under section 7 of the Act must be reconsidered if (1) new information reveals impacts of the proposed action that may affect listed species or critical habitat in a manner not previously considered, (2) the proposed action is subsequently modified to include activities which were not considered during this consultation, or (3) new species are listed or critical habitat designated that might be affected by the proposed action.

??

TDOT's standard construction BMPs would be implemented during the project. Equipment staging and maintenance areas should be developed an adequate distance from the stream to avoid entry of petroleum-based pollutants into the water.?? Concrete and cement dust must be kept out of the water as they alter chemical properties and can be toxic to aquatic species. This email will serve as our official project response.?? Please let me know if we can offer further assistance.?? Thanks,

??

John Griffith
Transportation Biologist
U.S. Fish and Wildlife Service
Tennessee Field Office
931-525-4995 (office)
931-528-7075 (fax)
??

From: Eric Philipps <Eric.Philipps@tn.gov>
Sent: Thursday, June 21, 2018 2:07 PM
To: john_griffith@fws.gov
Cc: Randall E. Mann <Randall.E.Mann@tn.gov>; Lou Timms <Lou.Timms@tn.gov>; Jared McCoy <Jared.McCoy@tn.gov>; Dustin Tucker <Dustin.Tucker@tn.gov>; Rita M. Thompson <Rita.M.Thompson@tn.gov>; Greg Harris <Greg.Harris@tn.gov>
Subject: [EXTERNAL] Fayette County, SR-193 (Macon Road) Bridge over Branch, PIN 124285.00

??

John,

??

Please find attached the coordination request, including species maps and list, for the proposed bridge replacement in Fayette County.

??

Thanks,



Eric Philipps | Environmental Studies Specialist
Region 4 | Project Development

Environmental Tech Office | Building A, 1st floor
300 Benchmark Place, Jackson, TN 38301

p. 731-935-0174???? c. 731-513-0021

eric.philipps@tn.gov

tn.gov/tdot

??

From: [Casey Parker](#)
To: [Eric Philipps](#); [TDOT Env.LocalPrograms](#)
Cc: [Rob Todd](#)
Subject: RE: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00
Date: Wednesday, July 11, 2018 12:27:26 PM
Attachments: [image002.png](#)
[image003.png](#)

Subject: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00

Mr. Eric Philipps,

The Tennessee Wildlife Resources Agency has reviewed the information that you provided regarding the proposed SR-193 (Macon Drive) Bridge in Fayette County, Tennessee and we have no concerns regarding the project and do not anticipate adverse impacts to state listed species under our authority due to the project. Thank you for the opportunity to review and comment on this proposed project, please contact me if you need further assistance.

Casey Parker - Wildlife Biologist
Liaison to TDOT & Federal Highway Administration
Tennessee Wildlife Resources Agency
Environmental Services Division
Email: casey.parker@tn.gov



From: Eric Philipps
Sent: Thursday, June 21, 2018 2:41 PM
To: Casey Parker
Cc: Rob Todd; Randall E. Mann; Lou Timms; Jared McCoy; Dustin Tucker; Rita M. Thompson; Greg Harris
Subject: Request for Comment - Fayette, SR-193 (Macon Drive) Bridge over Branch, PIN 124285.00

Casey,

TDOT proposes to replace the subject bridge in Fayette County. Please find attached KMZ file, species maps, species list, and plan sheet. If you have any questions or require additional information, please do not hesitate to contact me.

Thanks,




Eric Philipps | Environmental Studies Specialist

Region 4 | Project Development
Environmental Tech Office | Building A, 1st floor
300 Benchmark Place, Jackson, TN 38301
p. 731-935-0174 c. 731-513-0021
eric.philipps@tn.gov
tn.gov/tdot

Special Notes

Cliff swallow and barn swallow nests, eggs, or birds (young and adults) will not be disturbed between April 15 and July 31. From August 1 to April 14, nests can be removed or destroyed, and measures implemented to prevent future nest building at the site (e.g., closing off area using netting).



3/8/2018 10:34:3 PM T:\1\DOT\131\DOT\2017 BIR\Fayette\6893-LM\48\FINAL\5893-Br\Logo TR-Fix.dgn

ENVIRONMENTAL TECHNICAL STUDY AREA

STATE ROUTE 193 (MACON DRIVE)
 L.M. 11.48
 FAYETTE COUNTY

STATE OF TENNESSEE
 DEPARTMENT OF TRANSPORTATION
 STRATEGIC TRANSPORTATION
 INVESTMENTS DIVISION

FIGURE 1A
 SR-193
 L.M. 11.48




Photo 1. STR-1 — Looking downstream from bridge



Photo 2. STR-1 — Looking upstream from bridge





Photo 3. WWC-1 — Looking up gradient from near confluence with STR-1



Photo 4. WWC-1 — Looking down gradient, toward confluence with STR-1

Flood Insurance Rate Map (FIRM)



NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0315C

FIRM
FLOOD INSURANCE RATE MAP
FAYETTE COUNTY,
TENNESSEE
AND INCORPORATED AREAS

PANEL 315 OF 605
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
FAYETTE COUNTY	470352	0315	C
OAKLAND, TOWN OF	470410	0315	C

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.



MAP NUMBER
47047C0315C

EFFECTIVE DATE
NOVEMBER 5, 2008

Federal Emergency Management Agency

PIN 128113.02
SR-193 Bridge over Branch, LM 11.48
Fayette County, TN

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

Air and Noise

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Air and Noise

Study Results

AIR QUALITY

Transportation Conformity

This project is in Fayette County which is in attainment for all regulated criteria pollutants. Therefore, conformity does not apply to this project.

Mobile Source Air Toxics (MSATs)

This project qualifies as a categorical exclusion under 23 CFR 771.117 and, therefore, does not require an evaluation of MSATs per FHWA's "Interim Guidance Update on Air Toxic Analysis in NEPA Documents" dated October 2016.

NOISE

This project is Type III in accordance with the FHWA noise regulation in 23 CFR 772 and TDOT's noise policy; therefore, a noise study is not needed.

Commitments

Did the study of this project result in any environmental commitments?

No

Additional Information

Is there any additional information or material included with this study?

No

Certification

Responder: Chasity L. Stinson

Title: TESS Advanced, TDOT Air and Noise Section

Signature: Chasity L.
Stinson

Digitally signed by
Chasity L. Stinson
Date: 2019.06.21
09:00:21 -05'00'

Cultural Resources

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Archaeology

Study Results

In a letter dated July 24, 2018 the TN SHPO concurred that no NRHP listed, eligible, or potentially eligible properties would be affected by this undertaking.

Commitments

Did the study of this project result in any environmental commitments?

No

Additional Information

Is there any additional information or material included with this study?

No

Certification

Responder: Sarah Kate McKinney

Title: TESS Archaeology

Signature: Sarah Kate McKinney
Digitally signed by Sarah Kate McKinney
Date: 2019.06.19 08:39:42 -05'00'



TENNESSEE HISTORICAL COMMISSION
STATE HISTORIC PRESERVATION OFFICE
2941 LEBANON PIKE
NASHVILLE, TENNESSEE 37243-0442
OFFICE: (615) 532-1550
www.tnhistoricalcommission.org

July 24, 2018

Mr. Phillip R. Hodge
Tennessee Department of Transportation
Suite 900, James K. Polk Building
505 Deaderick Street
Nashville, TN 37243-1402

RE: FHWA / Federal Highway Administration, SR-193 (Macon Road) Bridge Replacement over Unknown Branch, Log Mile 11.48, Fayette County, TN

Dear Mr. Hodge:

In response to your request, we have reviewed the archaeological report of investigations and accompanying documentation submitted by you regarding the above-referenced undertaking. Our review of and comment on your proposed undertaking are among the requirements of Section 106 of the National Historic Preservation Act. This Act requires federal agencies or applicants for federal assistance to consult with the appropriate State Historic Preservation Office before they carry out their proposed undertakings. The Advisory Council on Historic Preservation has codified procedures for carrying out Section 106 review in 36 CFR 800 (Federal Register, December 12, 2000, 77698-77739).

Considering the information provided, we find that no archaeological resources eligible for listing in the National Register of Historic Places will be affected by this undertaking. If project plans are changed or archaeological remains are discovered during project construction, please contact this office to determine what further action, if any, will be necessary to comply with Section 106 of the National Historic Preservation Act. Complete and/or updated Tennessee Site Survey Forms should be submitted to the Tennessee Division of Archaeology for all sites recorded and/or revisited during the current investigation. Questions or comments may be directed to Jennifer Barnett (615) 687-4780.

Your cooperation is appreciated.

Sincerely,

E. Patrick McIntyre, Jr.
Executive Director and
State Historic Preservation Officer

EPM/jmb

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Historic Preservation

Study Results

Based on a review of the 06/12/2019 Preliminary Plans, the TN-SHPO letter dated 06/12/2018 remains valid. The project APE does not contain historic properties listed or eligible for listing in the National Register of Historic Places as currently proposed.

Commitments

Did the study of this project result in any environmental commitments?

No

Additional Information

Is there any additional information or material included with this study?

No

Certification

Responder: Haley Seger

Title: TESS - Historic Preservation

Signature:

Haley Seger

Digitally signed by Haley
Seger
Date: 2019.06.18
15:04:49 -05'00'



TENNESSEE HISTORICAL COMMISSION
STATE HISTORIC PRESERVATION OFFICE
2941 LEBANON PIKE
NASHVILLE, TENNESSEE 37243-0442
OFFICE: (615) 532-1550
www.tnhistoricalcommission.org

June 12, 2018

Ms. Katherine Looney
Tennessee Department of Transportation
505 Deaderick St
Suite 900
Nashville, TN 37243-1402

RE: FHWA / Federal Highway Administration, Replacement of the SR 193 Bridge over Branch,
Log Mile 11.48/ PIN 124285.00, , Fayette County, TN

Dear Ms. Looney:

In response to your request, we have reviewed the architectural survey report and accompanying documentation submitted by you regarding the above-referenced undertaking. Our review of and comment on your proposed undertaking are among the requirements of Section 106 of the National Historic Preservation Act. This Act requires federal agencies or applicants for federal assistance to consult with the appropriate State Historic Preservation Office before they carry out their proposed undertakings. The Advisory Council on Historic Preservation has codified procedures for carrying out Section 106 review in 36 CFR 800 (Federal Register, December 12, 2000, 77698-77739).

Considering the information provided, we concur that no architectural resources eligible for listing in the National Register of Historic Places will be affected by this undertaking. If project plans are changed or archaeological remains are discovered during project construction, please contact this office to determine what further action, if any, will be necessary to comply with Section 106 of the National Historic Preservation Act. Questions or comments may be directed to Casey Lee (615 253-3163).

Your cooperation is appreciated.

Sincerely,

E. Patrick McIntyre
Executive Director and
State Historic Preservation Officer

EPM/cjl

Native American Consultation

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Native American Coordination

Study Results

Letters were sent to the Absentee Shawnee Tribe and the Thlopthlocco Tribal Town on July 16, 2019 to bring MAC into compliance. Neither tribe responded.

Commitments

Did the study of this project result in any environmental commitments?

No

Additional Information

Is there any additional information or material included with this study?

No

Certification

Responder: Sarah Kate McKinney

Title: TESS Archaeology

Signature: Sarah Kate
McKinney

Digitally signed by
Sarah Kate McKinney
Date: 2019.08.27
12:35:40 -05'00'



**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION**

ENVIRONMENTAL DIVISION
SUITE 900, JAMES K. POLK BUILDING
505 DEADERICK STREET
NASHVILLE, TENNESSEE 37243-1402
(615) 741-3655

CLAY BRIGHT
COMMISSIONER

BILL LEE
GOVERNOR

July 15, 2019

Ms. Janet Maylen
Thlopthlocco Tribal Town
PO Box 188
Okemah, OK 74859

SUBJECT: Section 106 Initial Consultation for Proposed Bridge Replacement of State Route 193 Bridge over Unknown Branch in Fayette County, Tennessee (TDOT PIN 124285.00).

Dear Ms. Maylen,

The Tennessee Department of Transportation (TDOT), in coordination with the Federal Highway Administration (FHWA), is proposing to replace the State Route 193 (Macon Road) bridge over unnamed branch, log mile 11.48, in Fayette County, Tennessee (maps attached). The proposed bridge replacement will remain on the same alignment, however, approximately 0.16 acres of right-of-way is expected. Both underground and overhead utilities will need to be relocated and there will be ground disturbance in the area of potential effects.

The National Historic Preservation Act (NHPA) recognizes that federally funded undertakings, like the subject project, can affect historic properties to which your tribe attaches religious, cultural, and historic significance. In accordance with 36 CFR 800 regulations implementing compliance with Section 106 of the NHPA, we are providing general project information so that you can determine if your tribe has an interest in the project area or nature of the work proposed and so you have an opportunity to bring to our attention any interests and concerns about the potential for impacts to properties of religious and cultural significance. In addition, do you wish to be a consulting party on the project? Early awareness of your concerns can serve to protect historic properties valued by your tribe.

If you act as a consulting party you will receive archaeological assessment reports and related documentation, be invited to attend project meetings with FHWA, TDOT, and the Tennessee State Historic Preservation Office (TN-SHPO), if any are held, and be asked to provide input throughout the process. If you choose to not act as a consulting party at this time, you can do so at a later date simply by notifying me.


Please respond to me via letter, telephone (615-741-0977), fax (615-741-1098), or E-mail (Phillip.Hodge@tn.gov). I respectfully request responses (email is preferred) to project reports and other materials within thirty (30) days of receipt if at all possible. Thank you for your assistance.

Sincerely,

Phillip R. Hodge
Cultural Resources Manager

Enclosure


cc
Devon Frazier, Absentee Shawnee Tribe



Project Vicinity Map

Fayette County, TN. PIN 124285.00

TDOT PIN 124285.00
Fayette County
USGS TOPO Macon 424 NW



USGS Quad Map

Fayette County, TN. PIN 124285.00

TDOT PIN 124285.00
Fayette County
USGS TOPO Macon 424 NW



Project Location: Aerial View

Hazardous Materials

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Hazardous Materials

Study Results

Based on the Preliminary Plans dated 12 June 2019, no known hazardous materials sites appear to affect this project as it is currently planned and no additional hazardous material studies are recommended at this time. The asbestos bridge survey has been completed, no asbestos was detected and the following project commitment has been submitted but is not shown in these plans.

In the event hazardous substances/wastes are encountered within the right-of-way, their disposition shall be subject to all applicable regulations, including the applicable sections of the Federal Resource Conservation and Recovery Act, as amended; the Comprehensive Environmental Response, Compensation, and Liability Act, as amended; and the Tennessee Hazardous Waste Management Act of 1983, as amended. Databases reviewed include: Google Earth imagery, EPA National Priorities List, EPA EnviroMapper, TDEC Registered UST database, TDEC Division of Water Resources Public Data Viewer, TDOT IBIS, and others as necessary.

Commitments

Did the study of this project result in any environmental commitments?

Yes

EDHZ001. An Asbestos Containing Material (ACM) survey was conducted on Bridge No. 24015420001, SR-193 over Branch LM 11.48 (24-SR193-11.48).. No ACM was detected. No special accommodations for demolition and waste disposal are anticipated for these structures and the material can be deposited in a C&D landfill. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2015) Sections 107.08 D and 202.03).

Additional Information

Is there any additional information or material included with this study?

No

Certification

Responder: Kyle Kirschenmann

Signature:

Kyle Kirschenmann

Title: Transportation Manager 1, Hazardous Materials Section

Digitally signed by Kyle Kirschenmann
DN: cn=Kyle Kirschenmann, o=TDOT,
ou=Hazardous Materials Section,
email=kyle.kirschenmann@tn.gov,
c=US
Date: 2019.06.18 14:07:06 -04'00'

13-April-2018
Barge File Number: 3637862

Mr. Kyle Kirschenmann, PG
Environmental Program Manager – Hazardous Materials Section
State of Tennessee, Department of Transportation
TDOT Environmental Division
James K. Polk Building, Suite 900
505 Deaderick Street
Nashville, TN 37243-0334

RE: Asbestos Assessment Report
SR-193 Macon Road Bridge over Branch, LM 11.48 (IA)
PE-N: 24029-0207-94, PIN: 124285.00
Bridge Number: 24015420001
Fayette County, Tennessee

Dear Mr. Kirschenmann:

Enclosed is the asbestos assessment report for the above-referenced bridge. A total of 12 samples were obtained during the assessment for asbestos analyses. Asbestos minerals were not detected in any of the samples collected.

If you have any questions, please contact me by phone at 615-252-4349 or via email at Tom.McComb@bargedesign.com.

Sincerely,



Thomas McComb, PG, CPG
Contract Manager / Project Manager
Barge Design Solutions, Inc.

Enclosure



TENNESSEE DEPARTMENT OF TRANSPORTATION ASBESTOS ASSESSMENT REPORT

SR-193 Macon Road Bridge over Branch, LM 11.48 (IA)
PE-N: 24029-0207-94, PIN: 124285.00
Bridge Number: 24015420001
Fayette County, Tennessee



PREPARED BY



615 3rd Avenue South, Suite 700
Nashville, TN 37210
Barge Project #: 36378-62

13-April-2018

A handwritten signature in blue ink that reads "Brandon Page".

Brandon Page (Signature)
Tennessee Asbestos Inspector Accreditation No: A-I-100428-64307

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1 TDOT Bridge Identification	1
1.2 General Description	1
2.0 ASSESSMENT	1
2.1 Personnel and Date(s) of Assessment	2
2.2 Visual Survey	2
2.3 Access to Bridge Components	2
2.3.1 Top of Bridge Deck (Homogeneous Area 1 & 2)	2
2.3.2 Underside of Bridge Deck (Homogeneous Area 3)	2
2.3.3 Bridge Beams	2
2.3.4 Bridge Piers/Bents and Support	2
2.3.5 Bridge Rails	2
2.3.6 Abutments (Homogeneous Area 4)	2
2.3.7 Bridge Drainage	3
2.3.8 Other	3
3.0 ANALYTICAL PROCEDURES	3
3.1 Asbestos Analysis Procedures	3
3.2 Laboratory Name and Accreditation	3
4.0 REGULATORY OVERVIEW	3
4.1 National Emission Standards for Hazardous Air Pollutants	3
4.1.1 Definitions	4
5.0 RESULTS	5
5.1 Results of Asbestos Bulk Sample Analysis	5
6.0 QUALIFICATIONS	5

TABLES

Table 1	Analytical Laboratory	3
---------	-----------------------	---

FIGURES

Figure 1	Site Location Map	8
Figure 2	Sample Location Depiction	9

APPENDICES

Appendix A	Asbestos Assessment Credentials	10
Appendix B	Photographs	13
Appendix C	Asbestos Sample Laboratory Analysis Data	18
Appendix D	Health and Safety Plan	22

1.0 INTRODUCTION

This report presents the findings of an assessment for asbestos-containing materials (ACM) completed on the bridge identified in Section 1.1. The assessment was completed by Barge Design Solutions, Inc. (Barge) in accordance with the State of Tennessee, Department of Transportation Environmental Division, Social and Cultural Resources Office, Hazardous Materials Section requirements.

1.1 TDOT Bridge Identification

The bridge is identified in the TDOT Project System/Bridge Management System as:

Termini: SR-193 Macon Road Bridge over Branch, LM 11.48 (IA)

PE-N: 24029-0207-94

PIN: 124285.00

Bridge Number: 24015420001

County: Fayette

1.2 General Description

Bridge Number 24015420001 is located on SR-193 over Branch LM 11.48 (24-SR193-11.48), is a 38-foot, two-lane, two-span bridge constructed of pre-stressed concrete channel beams with a concrete deck and asphalt wearing surface. The bridge was constructed in 1965. The bridge location is shown on Figure 1.

2.0 ASSESSMENT

The identification of ACM is performed by collecting bulk samples of suspect materials and having those samples analyzed by a laboratory. ACM are those materials found to contain greater than 1% asbestos by calibrated visual area estimation by Polarized Light Microscopy (PLM).

Bulk sampling is a procedure in which representative homogeneous sampling areas in a structure are identified and then sampled. A homogeneous sampling area is defined as an area that contains material of the same type (uniform in color and texture) and was applied during the same general time. Once the homogeneous sampling areas are identified, bulk samples of suspect materials were obtained from the homogeneous areas at the discretion of our inspectors, based on site conditions and experience.

2.1 Personnel and Date(s) of Assessment

The sampling and field activities were performed on April 5, 2018, by Brandon Page, Accredited State of Tennessee Asbestos Inspector. Copies of the inspector's and Barge's current accreditation from the State of Tennessee are included in Appendix A.

2.2 Visual Survey

Barge's survey began with a walk-through and visual survey of the structures located on the property. The visual survey consisted of:

- Sketching the structure and/or verifying the plans provided
- Locating and identifying homogeneous areas (HAs) of suspect materials that may contain asbestos minerals
- Determining applicable sampling locations

2.3 Access to Bridge Components

Individual bridge components were accessed by the following methods:

2.3.1 Top of Bridge Deck (Homogeneous Area 1 & 2)

Three samples labeled 01-01-01, 01-01-02, and 01-01-03 were collected from the curb. Samples were collected using hammers and chisels. Three samples labeled 01-02-04, 01-02-05, and 01-02-06 were collected from the road stripe. Samples were obtained using a razor knife.

2.3.2 Underside of Bridge Deck (Homogeneous Area 3)

The bottom of the deck was concrete. Three samples labeled 01-03-07, 01-03-08, and 01-03-09 were collected from the bottom of the deck. Samples were collected using hammers and chisels.

2.3.3 Bridge Beams

No bridge beam samples were collected.

2.3.4 Bridge Piers/Bents and Support

No bridge pier samples were collected.

2.3.5 Bridge Rails

No bridge rail samples were collected.

2.3.6 Abutments (Homogeneous Area 4)

Three samples labeled 01-04-10, 01-04-11, and 01-04-12 were collected from the abutment. Samples were obtained using hammers and chisels.

2.3.7 Bridge Drainage

No bridge drains were observed. No bridge drain samples were collected.

2.3.8 Other

No other samples were collected.

3.0 ANALYTICAL PROCEDURES

3.1 Asbestos Analysis Procedures

The bulk samples are analyzed in the laboratory using PLM coupled with dispersion staining (EPA Method 600/R-93/116). PLM is an analytical method for asbestos identification, which identifies the specific asbestos minerals by their unique optical properties. The optical properties are a result of the mineral's chemical composition, physical atomic structure, and visual morphology. This is the U.S. Environmental Protection Agency (EPA) recommended method of analysis for asbestos identification in bulk samples.

Samples which contain multiple layers, or that have associated mastic or adhesive backing, are analyzed as two or more separate samples when possible.

3.2 Laboratory Name and Accreditation

The bulk samples collected for this assessment were analyzed by a laboratory that has received certification from the American Industrial Hygiene Association's (AIHA) Laboratory Accreditation Program. The name and laboratory number of the analytical laboratory that analyzed the samples for this assessment is indicated in Table 1.

Table 1 - Analytical Laboratory

Laboratory Name	Frost Environmental Services, LLC
Laboratory ID Number	198214

4.0 REGULATORY OVERVIEW

4.1 National Emission Standards for Hazardous Air Pollutants

The EPA's National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations (40 CFR 61, Subpart B) requires that all regulated asbestos-containing materials (RACM) be properly removed prior to any renovation or demolition activities that will disturb them. These regulations define RACM as:

- Friable ACM.
- Category I non-friable ACM that has become friable.
- Category I non-friable ACM that will be or has been subject to sanding, grinding, cutting, or abrading.
- Category II non-friable ACM that has a high probability of becoming, or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material during demolition or renovation operations.

4.1.1 Definitions

Significant definitions related to regulation of asbestos under NESHAPS regulations include:

Friable asbestos-containing material (ACM), is defined by the Asbestos NESHAP, as any material containing more than one percent (1%) asbestos as determined using the method specified in Appendix A, Subpart F, 40 CFR Part 763, Section 1, Polarized Light Microscopy (PLM), that, when dry, can be crumbled, pulverized or reduced to powder by hand pressure. (Sec. 61.141).

Non-friable ACM is any material containing more than one percent (1%) asbestos as determined using the method specified in Appendix A, Subpart F, 40 CFR Part 763, Section 1, Polarized Light Microscopy (PLM), that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure. EPA also defines two categories of non-friable ACM, Category I and Category II non-friable ACM, which are described as follows:

Category I non-friable ACM is any asbestos-containing packing, gasket, resilient floor covering or asphalt roofing product which contains more than one percent (1%) asbestos as determined using polarized light microscopy (PLM) according to the method specified in Appendix A, Subpart F, 40 CFR Part 763. (Sec. 61.141).

Category II non-friable ACM is any material, excluding Category I non-friable ACM, containing more than one percent (1%) asbestos as determined using polarized light microscopy according to the methods specified in Appendix A, Subpart F, 40 CFR Part 763 that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure. (Sec. 61.141).

"Regulated Asbestos-Containing Material" (RACM) is (a) friable asbestos material, (b) Category I non-friable ACM that has become friable, (c) Category I non-friable ACM that will be or has been subjected to sanding, grinding, cutting or abrading, or (d)

Category II non-friable ACM that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations.

Friable materials are defined as those which can be crumbled, pulverized, or reduced to powder by hand pressure when dry. The NESHAP regulations also establish specific notification and control requirements for renovation and demolition work.

5.0 RESULTS

The results of the asbestos assessment are presented in the following section.

5.1 Results of Asbestos Bulk Sample Analysis

A total of 12 samples were obtained from the bridge. A depiction of the sample locations is shown on Figure 2. Multiple samples of each homogeneous area were collected in accordance with State of Tennessee, Department of Transportation Environmental Division, Social and Cultural Resources Office, Hazardous Materials Section requirements and delivered to the laboratory for visual observation and microscopic analysis. The samples were selected based on homogeneous areas of suspect materials, as described in Section 2.3.

No asbestos was detected in any of the samples collected.


6.0 QUALIFICATIONS

The information presented herein is based on information obtained during the site visit(s) and from previous experience. If additional information becomes available, which might impact our conclusions or recommendations, Barge requests the opportunity to review the information, reassess the potential concerns, and modify opinions, if warranted.

This report has been prepared on behalf of the Tennessee Department of Transportation. This document is not a Bid Document or a Contract Document. Use of this report or reliance upon information contained in this report by any other party implies an agreement by that party to the same terms and conditions under which service was provided. Furthermore, any party, other than our Client, relying on this document is cautioned that all conclusions made or decisions arrived at based on their

review of this document are those solely of the third party, without warranty, guarantee or promise by the author. These findings are relevant to the dates of our services and should not be relied upon to represent conditions at substantially earlier or later dates.

Figures





Copyright © 2015 National Geographic Society, Inc.

Tennessee Department Of Transportation - Asbestos Assessment Report
 April 2018

SR-193 Macon Road Bridge over Branch, LM 11.48 (IA)
PE-N: 24029-0207-94, PIN: 124285.00
Bridge Number: 24015420001
Fayette County, Tennessee

Figure 1 - Site Location Map





Notes:
Locations are typical of the homogeneous area, some sample locations were not visible from the angle of the photo therefore a representative location was labeled.

HA = Homogeneous Area



Tennessee Department of Transportation - Asbestos Assessment Report
April 2018

SR-193 Macon Road Bridge over Branch, LM 11.48 (IA)
PE-N: 24029-0207-94, PIN: 124285.00
Bridge Number: 24015420001
Fayette County, Tennessee

**Figure 2 -
Sample Location Depiction**

Appendix A: Asbestos Assessment Credentials



THE STATE OF TENNESSEE

Department of Environment and Conservation Division of Solid Waste Management
Toxic Substances Program

William R. Snodgrass Tennessee Tower
312 Rosa L. Parks Avenue, 14th Floor Nashville TN 37243

By virtue of the authority vested by the Division of Solid Waste Management, the Company named below is hereby accredited to offer and/or conduct Asbestos activities pursuant to Rule 1200-01-20:

Barge Waggoner Sumner and Cannon, Inc

211 Commerce Street Suite 600 Nashville TN, 37201

to conduct ASBESTOS ACTIVITIES in schools or public and commercial buildings in Tennessee.
This firm is responsible for compliance with the applicable requirements of Rule 1200-01-20.

Discipline	Type	Accreditation Number	Effective Date	Expiration Date
Accreditation	Re-Accreditation	A-F-410-52467	September 01, 2017	September 30, 2018



Given under the Seal of the State of Tennessee in Nashville.

This 8th Day of September 2017

Division of Solid Waste Management
Toxic Substance Program

CN-1324 (Rev 6/13)

RDA-3020

THE STATE OF TENNESSEE

Department of Environment and Conservation
Division of Solid Waste Management
Toxic Substances Program



Date issued: 3/5/2018
Initial


Brandon T Page


DOB	Sex	HGT	WGT
14-May-1990	M	6'4"	185


Discipline	Accreditation	Expiration
Inspector	A-I-100428-64307	Jan-31-2019
Project Designer	A-PD-100428-66330	Mar-31-2019


Asbestos Accreditation


Appendix B: Photographs

Photographer: Brandon Page	
Date: 4/5/2018	
Description: Photograph 1 – Bridge Number	

Photographer: Brandon Page	
Date: 4/5/2018	
Description: Photograph 2 – Homogeneous Area 1 Curb 01-01-01 01-01-02 01-01-03	

Photographer: Brandon Page	
Date: 4/5/2018	
Description: Photograph 3 – Homogeneous Area 2 Road Stripe Sample Locations 01-02-04 01-02-05 01-02-06	

Photographer: Brandon Page	
Date: 4/5/2018	
Description: Photograph 4 – Homogeneous Area 3 Bottom of Deck Sample Locations 01-03-07 01-03-08 01-03-09	


<p>Photographer: Brandon Page</p>	
<p>Date: 4/5/2018</p>	
<p>Description: Photograph 5 – Homogeneous Area 4 Abutment Sample Locations 01-04-10 01-04-11 01-04-12</p>	

Appendix C: Asbestos Sample Laboratory Analysis Data

FROST ENVIRONMENTAL SERVICES, LLC

339 ROCKLAND ROAD, SUITE E, HENDERSONVILLE, TENNESSEE 37075

(615) 562-2669 office - (615) 473-9047 cell - email: lab@frostenvironmental.com



POLARIZED LIGHT MICROSCOPY (PLM) LABORATORY ANALYSIS REPORT (EPA/600/R-93/116 (JUNE 1993))

CLIENT: BWSC
PROJECT: SR-193 Over Branch
LOCATION: Fayette County TN

Date Received: 4/6/2018
Date Analyzed: 4/9/2018
Date Reported: 4/9/2018

ANALYST: Jody Wilkins

Sample Number	Location	Material Description	Binder (Non-Fibrous) Material	Non-Asbestos Fiber	Asbestos Type & Percent
01-01-01	Curb	Tan Cementitious Material	100	None Detected	None Detected
01-01-02	Curb	Tan Cementitious Material	100	None Detected	None Detected
01-02-03	Curb	Tan Cementitious Material	100	None Detected	None Detected
01-02-04	Road Stripe	Yellow Beaded Material	100	None Detected	None Detected
01-02-05	Road Stripe	Yellow Beaded Material	100	None Detected	None Detected
01-02-06	Road Stripe	Yellow Beaded Material	100	None Detected	None Detected
01-03-07	Bottom of Deck/Beam	Tan Cementitious Material	100	None Detected	None Detected
01-03-08	Bottom of Deck/Beam	Tan Cementitious Material	100	None Detected	None Detected
01-03-09	Bottom of Deck/Beam	Tan Cementitious Material	100	None Detected	None Detected
01-04-10	Abutment	Tan Cementitious Material	100	None Detected	None Detected
		Tan Coating	100	None Detected	None Detected
01-04-11	Abutment	Tan Cementitious Material	100	None Detected	None Detected
		Tan Coating	100	None Detected	None Detected
01-04-12	Abutment	Tan Cementitious Material	100	None Detected	None Detected
		Tan Coating	100	None Detected	None Detected

Asbestos Containing Material (ACM) is defined as any material containing more than one percent asbestos. Analysis was performed using EPA/600/R-93/116 (June 1993)), Test Method for the Determination of Asebstos in Bulk Building Materials.

Appendix D: Health and Safety Plan

Health and Safety Plan



Project: TDOT SR193	Location: FayetteCounty	Date: 12/15/17	Job No. 3637862
----------------------------	--------------------------------	-----------------------	------------------------


Project Manager	Office Number	Cell Number
Tom McComb	615-252-4349	615-210-8936

Onsite Contact	Office Number	Cell Number

Description of Field Activities

ACM Sampling

ACTIVITY	WEATHER	BOTANY	TOOLS	JOB BRIEFING
<input type="checkbox"/> Soil Sampling	<input type="checkbox"/> Hot	<input type="checkbox"/> Poison Ivy/Oak	<input type="checkbox"/> Machete	<input type="checkbox"/> Evaluate Surroundings
<input type="checkbox"/> Sediment Sampling	<input type="checkbox"/> Cold	<input type="checkbox"/> Poison Sumac	<input type="checkbox"/> Brush hook	<input type="checkbox"/> Communications
<input type="checkbox"/> Surface-Water Sampling	<input type="checkbox"/> Mild	<input type="checkbox"/> Thistle	<input type="checkbox"/> Pick	<input type="checkbox"/> Safety Plan
<input type="checkbox"/> Ground-Water Sampling	<input type="checkbox"/> Sunny	<input type="checkbox"/> Thorns	<input type="checkbox"/> Ax	<input type="checkbox"/> Emergency Numbers
<input type="checkbox"/> Fish Sampling	<input type="checkbox"/> Fair	<input type="checkbox"/> Needle-like	<input type="checkbox"/> Hammer	<input type="checkbox"/> Lockout/Tagout
<input type="checkbox"/> Macroinvertebrate Sampling	<input type="checkbox"/> Rain	<input type="checkbox"/> Other:	<input type="checkbox"/> Knife	<input type="checkbox"/> Client Requirements
<input type="checkbox"/> Drilling	<input type="checkbox"/> Lightning		<input type="checkbox"/> Drill Rig	<input type="checkbox"/> Insect Repellent
<input type="checkbox"/> Trenching	<input type="checkbox"/> Hail		<input type="checkbox"/> Boat	<input type="checkbox"/> Reflective/Colored Vests
<input checked="" type="checkbox"/> Other: <i>ACM Sampling</i>	<input type="checkbox"/> Sleet/Snow/Ice		<input type="checkbox"/> Truck/ATV	<input type="checkbox"/> Chemical Information
	<input type="checkbox"/> Night		<input type="checkbox"/> Electrical Equipment	<input type="checkbox"/> Tool Check
	TERRAIN	WILDLIFE	<input type="checkbox"/> Other:	<input type="checkbox"/> Equipment Check
CONSTITUENTS	<input type="checkbox"/> River	<input type="checkbox"/> Ticks		<input type="checkbox"/> First Aid Kit Check
<input type="checkbox"/> Strong Acids/Bases	<input type="checkbox"/> Creek	<input type="checkbox"/> Spiders	TRAFFIC	<input type="checkbox"/> Gloves
<input type="checkbox"/> Metals	<input type="checkbox"/> Lake	<input type="checkbox"/> Chiggers	<input type="checkbox"/> Heavy	<input type="checkbox"/> PFD
<input type="checkbox"/> PCBs	<input type="checkbox"/> Swamp	<input type="checkbox"/> Ants/Fireants	<input type="checkbox"/> Light	<input type="checkbox"/> Waders
<input type="checkbox"/> Pesticides	<input type="checkbox"/> Sinkholes/Collapses	<input type="checkbox"/> Wasps/Bees	<input type="checkbox"/> Boats	<input type="checkbox"/> Steel Toe Boots
<input type="checkbox"/> Asbestos	<input type="checkbox"/> Woods	<input type="checkbox"/> Hornets	<input type="checkbox"/> Railroad	<input type="checkbox"/> Hard Hat
<input type="checkbox"/> VOCs	<input type="checkbox"/> Open & Clear	<input type="checkbox"/> Dogs	<input type="checkbox"/> Planes	<input type="checkbox"/> Eye Protection



Imagery ©2017 Google, Map data ©2017 Google 2 mi

14597 US-79

Stanton, TN 38069

- ↑ 1. Head southwest on US-70 W/US-79 S toward Gene Johnson Rd 6.0 mi
- ↘ 2. Turn right onto TN-59 W/Main St 10.3 mi
 ⓘ Continue to follow TN-59 W 0.9 mi
- ↙ 3. Turn left onto Hastings Way 1.2 mi
- ↑ 4. Continue onto Mueller Brass Rd 0.5 mi
- ↙ 5. Turn left onto U.S. 51 S 171 ft
- ↘ 6. Turn right 0.2 mi
- ↗ 7. Slight right 0.2 mi
 ⓘ Destination will be on the left

Baptist Memorial Hospital- Tipton

1995 Highway 51 S, Covington, TN 38019

These directions are for planning purposes only. You may find that construction projects, traffic, weather, or other events may cause conditions to differ from the map results, and you should plan your route accordingly. You must obey all signs or notices regarding your route.

Multimodal

Environmental Studies Request

Project Information

Route: SR-193
Termini: (Macon Road), Bridge over Branch, LM 11.48 (IA)
County: Fayette
PIN: 128113.02


Request

Request Type: Environmental Study Reevaluation
Project Plans: Preliminary
Date of Plans: 06/12/2019
Location: Email Attachment

Certification

Requestor: Payton Croak
Title: TDOT Environmental Studies Specialist

Signature: Payton
Croak

 Digitally signed by
Payton Croak
Date: 2019.06.18
12:31:34 -05'00'

Environmental Study

Technical Section

Section: Multimodal

Study Results

This project accommodates bicycle and pedestrian traffic with a 6' shoulder in a rural area.

Commitments

Did the study of this project result in any environmental commitments?

No

Additional Information

Is there any additional information or material included with this study?


No

Certification

Responder: Jessica Wilson

Title: Transportation Program Supervisor

Signature: Jessica
Wilson

 Digitally signed by
Jessica Wilson
Date: 2019.06.19
13:04:15 -05'00'



MULTIMODAL ACCESS POLICY

EFFECTIVE DATE:

July 31, 2015

AUTHORITY:

TCA 4-3-2303

If any portion of this policy conflicts with applicable state or federal laws or regulations, that portion shall be considered void. The remainder of this policy shall not be affected thereby and shall remain in full force and effect.

PURPOSE:

To create and implement a multimodal transportation policy that encourages safe access and mobility for users of all ages and abilities through the planning, design, construction, maintenance, and operation of new construction, reconstruction and retrofit transportation facilities that are federally or state funded. Users include, but are not limited to, motorists, transit-riders, freight-carriers, bicyclists and pedestrians.

APPLICATION:

The policy applies to Department of Transportation employees, consultants and contractors involved in the planning, design, construction, maintenance, and operation of state and federally funded projects, and local governments managing and maintaining transportation projects with funding through TDOT's Local Programs Development Office.

DEFINITIONS:

- Highway:** A main road or thoroughfare, such as a street, boulevard, or parkway, available to the public for use for travel or transportation.
- Multimodal:** For the purposes of this policy, multimodal is defined as the movement of people and goods on state and functionally-classified roadways. Users include, but are not limited to, motorists, transit-riders, freight-carriers, bicyclists and pedestrians, including those with disabilities.
- Reconstruction:** Complete removal and replacement of the pavement structure or the addition of new continuous traffic lanes on an existing roadway.

- Retrofit:** Changes to an existing highway within the general right-of-way, such as adding lanes, modifying horizontal and vertical alignments, structure rehabilitation, safety improvements, and maintenance.
- Roadway:** The portion of a highway, including shoulders, that is available for vehicular, bicycle or pedestrian use.

POLICY:

The Department of Transportation recognizes the benefits of integrating multimodal facilities into the transportation system as a means to improve the mobility, access and safety of all users. The intent of this policy is to promote the inclusion of multimodal accommodations in all transportation planning and project development activities at the local, regional and statewide levels, and to develop a comprehensive, integrated, and connected multimodal transportation network. TDOT will collaborate with local government agencies and regional planning agencies through established transportation planning processes to ensure that multimodal accommodations are addressed throughout the planning, design, construction, maintenance, and operation of new construction, reconstruction and retrofit transportation facilities as outlined in TDOT's Multimodal Access Policy Implementation Plan.

TDOT is committed to the development of a transportation system that improves conditions for multimodal transportation users through the following actions:

1. Provisions for multimodal transportation shall be given full consideration in new construction, reconstruction and retrofit roadway projects through design features appropriate for the context and function of the transportation facility.
2. The planning, design and construction of new facilities shall give full consideration to likely future demand for multimodal facilities and not preclude the provision of future improvements. If all feasible roadway alternatives have been explored and suitable multimodal facilities cannot be provided within the existing or proposed right of way due to environmental constraints, an alternate route that provides continuity and enhances the safety and accessibility of multimodal travel should be considered.
3. Existing multimodal provisions on roadways shall not be made more difficult or impossible by roadway improvements or routine maintenance projects.
4. Intersections and interchanges shall be designed (where appropriate based on context) to accommodate the mobility of bicyclists and pedestrians to cross corridors as well as travel along them in a manner that is safe, accessible, and convenient.
5. While it is not the intent of resurfacing projects to expand existing facilities, opportunities to provide or enhance bicycle and pedestrian facilities shall be given full consideration during the program development stage of resurfacing projects.
6. Pedestrian facilities shall be designed and built to accommodate persons with disabilities in accordance with the access standards required by the Americans with Disabilities Act

(ADA). Sidewalks, shared use paths, street crossings (including over- and under-crossings) and other infrastructure shall be constructed so that all pedestrians, including those with disabilities, can travel independently.

7. Provisions for transit-riders, pedestrians, and bicyclists shall be included when closing roads, bridges or sidewalks for construction projects where pedestrian, bicycle, or transit traffic is documented or expected.

EXCEPTIONS:

It is TDOT's expectation that full consideration of multimodal access will be integrated in all appropriate new construction, reconstruction and retrofit infrastructure projects. However, there are conditions where it is generally inappropriate to provide multimodal facilities. Examples of these conditions include, but are not limited to:


1. Controlled access facilities where non-motorized users are prohibited from using the roadway. In this instance, a greater effort may be necessary to accommodate these users elsewhere within the same transportation corridor.
2. The cost of accommodations would be excessively disproportionate to the need and probable use. Excessively disproportionate is defined as exceeding twenty percent (20%) of the total cost of the project. The twenty percent figure should be used in an advisory rather than an absolute sense, especially in instances where the cost may be difficult to quantify. Compliance with ADA requirements may require greater than 20% of project cost to accommodate multimodal access. Costs associated with ADA requirements are NOT an exception.
3. Areas in which the population and employment densities or level of transit service around the facility, both existing and future, does not justify the incorporation of multimodal alternatives.
4. Inability to negotiate and enter into an agreement with a local government to assume the operational and maintenance responsibility of the facility.
5. Other factors where there is a demonstrated absence of need or prudence, or as requested by the Commissioner of the Department of Transportation.

Exceptions for not accommodating multimodal transportation users on State roadway projects in accordance with this policy shall be documented describing the basis and supporting data for the exception, and must be approved by TDOT's Chief Engineer and Chief of Environment and Planning or their designees.


DESIGN GUIDANCE:

The Department recognizes that a well-planned and designed transportation network is responsive to its context and meets the needs of its users. Therefore, facilities will be designed and constructed in accordance with current applicable laws and regulations, using best practices and guidance, including but not limited to the following: TDOT Standard Drawings and guidelines, American Association of State Highway and Transportation Officials (AASHTO) publications, Institute of Transportation Engineers (ITE) publications, the Manual on Uniform Traffic Control Devices (MUTCD), National Association of City Transportation Officials (NACTO) publications, the Public Rights-of-Ways Accessibility Guidelines (PROWAG), and the Americans with Disabilities Act Accessibility Guidelines (ADAAG).

Signed:



PAUL DEGGES
Chief Engineer/Deputy Commissioner



TOKS OMISHAKIN
Chief of Planning/Deputy Commissioner



JOHN SCHROER
Commissioner