

Concept Report Form

The Concept Report Form develops an initial project vision, basis of design and report (e.g., the Concept Report) to transition into the subsequent design stages (Stages 1 through 4 in the Project Delivery Network [PDN]). This form summarizes all project components using information to complete the Concept Report.

General Project Information


| | | | | | | | | | | |
|---|---|---------------------|-------------------------|---|----------------------------|---------------------------|---------------------------|------------------|--------------------|-----------------|
| Project Name | SR 353 (Bailey Bridge Road) – Bridge over Nolichucky River | | | | | | | | | |
| PIN | 132623.00 | | | | | | | | | |
| Route Information | Route | NHS (Y/N) | Functional Class | | City | | County | | | |
| | SR353 | No | Rural Major Collector | | N/A | | Washington | | | |
| Project Information | Begin Log Mile | End Log Mile | AADT¹ | Design Hour Vol. (DHV)¹ | Truck %¹ | Design Speed (MPH) | Posted Speed (MPH) | Base Year | Design Year | |
| | 0.36 | 0.71 | 1,880 | 207 | 3.00 | 50 | 45 | 2028 | 2048 | |
| Project Description & Standard Drawings Used | <p>A field review was held April 19, 2023. The proposed bridge is to be a 4 span concrete box beam bridge 380' in length. The typical section for the approach and bridge will be 2-11' foot travel lanes with 6' shoulders. The out-to-out width based on the above recommendations will be 35'3". The proposed bridge will raise the grade 3' and will be constructed in phases. A single lane will remain open during construction and be controlled by a temporary signal. Superstructure depth is 47"= 33" (beam)+10" (deck)+ 4" (width (in inches) x0.02/2).</p> <p>RD11-TS-2</p> | | | | | | | | | Project Details |
| Important Project History or Related Projects | <p>The existing structure, built in 1958 is a 9 span concrete tee beam bridge, 354' long with an out-to-out width of 28'6". The existing structure has 2-11' travel lanes with 1' shoulders. The listed weight limit on the inspection report is 12 tons for 2 axle vehicles and 21 tons for vehicles with 3 or more axles. There is bridge maintenance scheduled under TDOT PIN 132623.01. The discharges for the drainage basin (StreamStats Version 4.10.1) for drainage area of 884.31 square miles: Q10 is 34,300 cfs, Q50 is 49,400 cfs, and Q100 is 56,500 cfs. This project is expected to utilize federal funding.</p> | | | | | | | | | |
| Project Purpose/Need | <p>The need to replace this bridge is due to the present condition of the existing bridge:</p> <ul style="list-style-type: none"> -Bridge built in 1958 -Sufficiency rating is 37.0 - October 25, 2021 -Typical section does not meet current TDOT Standards | | | | | | | | | |
| Major Environmental Considerations | <p>A noise study is not required. There is a perennial stream within the project limits. There are cliff swallows present and potential for bats. There are 10 endangered/threatened species within 4 miles of the project. There are no known hazardous materials sites near the project. The bridge has asbestos in 116 deck drains. There is a possible canoe launch near the bridge as the Nolichucky River is used frequently for rafting, coordination will be required. Washington County is in attainment for all regulated criteria pollutants. This project does not require an evaluation of MSATs under 23 CFR 771.117.</p> | | | | | | | | | |

| | | | | |
|--------------------------------------|--|--|--|-----------------------|
| Multi-Modal Considerations | Sidewalks were considered but cannot be provided at a reasonable cost due to the required increase in bridge width over 20% which will result in an increase in project cost over 20%. TDOT Multimodal Project Scoping Manual section 1.2 states that accommodations that are excessively disproportionate (exceeding 20%) to the need and probable use of the project are inappropriate locations to provide multimodal facilities. | | | |
| Major Project Risks | Approximately 3.6 acres of right of way are expected to be acquired. Overhead electric/communication and possibly underground water are present. NEPA mitigation may be required if ROW is acquired. There are no section 4(f) resources adjacent to the project site. No minority environmental justice (EJ) populations were identified. A Low-Income EJ population was identified. This document is covered by 23 USC § 407 and its production pursuant to fulfilling public planning requirements does not waive the provisions of § 407. | | | |
| Concept Estimate and Timeline | Total Current Project Cost | | Construction Year Estimate | Preliminary Estimates |
| | \$ 16,100,000 | | \$ 22,700,000 | |
| | Proposed Construction Year | | Estimated Construction Duration | |
| | 2028 | | TBD | |

¹ Traffic numbers reflect identified design year

Approvals

Executed for approval of this Concept Report


Steve Allen (Jan 24, 2024 11:25 CST)

Jan 24, 2024

STID Director

Date

The following individuals to execute if a bridge concept report:



Jan 24, 2024

Structures Director

Date



Jan 26, 2024

Regional Project Development Director

Date



Jan 30, 2024

Bureau Chief of Engineering

Date



Jan 29, 2024

Bureau Chief of Planning

Date

Ty Tucker

From: Dexter Justis
Sent: Tuesday, January 23, 2024 8:12 AM
To: Ty Tucker
Cc: James D. Kelley; Steve Allen; Jim Waters; Michael Gilbert; Emily Burgess
Subject: RE: Washington County Bridge over Nolichucky River SR 353 PIN 132623.00

No additional comments, looks good.



Dexter Justis, P.E. | Director
TDOT - Region One Project Management
7345 Region Lane, Knoxville, TN 37914
865-594-2400
Dexter.Justis@tn.gov
tn.gov/tdot

From: Ty Tucker <Ty.Tucker@tn.gov>
Sent: Wednesday, January 17, 2024 8:51 AM
To: Dexter Justis <Dexter.Justis@tn.gov>
Cc: James D. Kelley <James.D.Kelley@tn.gov>; Steve Allen <Steve.Allen@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>; Emily Burgess <Emily.Burgess@tn.gov>
Subject: Washington County Bridge over Nolichucky River SR 353 PIN 132623.00

Dexter,

As a part of the Project Delivery Network (PDN) Stage OSD3 Request Concept Report Signatures, please see attached pdf to access the draft report for your final review. We request that you provide your concurrence or any comments by COB **January 31st**. Below is the project information as well as a Google Maps link to the project location:

- PIN 132623.00
- Washington County
- SR 353 Bridge over Nolichucky River
- Project Location:
<https://www.google.com/maps/place/36%C2%B009'21.9%22N+82%C2%B035'25.8%22W/@36.1560782,-82.592429,17z/data=!3m1!4b1!4m4!3m3!8m2!3d36.156075!4d-82.5905?entry=ttu>
- Draft Report: Attached

Please feel free to reach out if you have any questions or issues accessing this report.
Thank you,



Ty Tucker, P.E. | TRANSPORTATION ENGINEERING S3
Strategic Transportation Investments Division
James K. Polk Building, 10th Floor

505 Deaderick Street
Nashville, TN 37243
p. 615-532-7459
ty.tucker@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

| Action Checklist | | | |
|---|----|---|----------------|
| OSD1 Initiate Concept Report and Request Funding | | | |
| Complete | NA | | Date Completed |
| ✓ | | Request and Finalize Safety Data | 10/14/2022 |
| ✓ | | Request Project Number, PIN, and Task Profile Numbers | 03/29/2022 |
| | ✓ | Coordinate with Long Range Planning | |
| ✓ | | Request and Finalize Traffic Data | 07/08/2022 |
| | ✓ | Request Preliminary Survey Data | |
| ✓ | | Initiate Division Reviews | 03/22/2023 |
| ✓ | | Schedule Site Review (with appropriate Divisions) | 03/22/2023 |
| 0EN1 Conduct Environmental Desktop Review | | | |
| Complete | NA | | Date Completed |
| ✓ | | Confirm Environmental Desktop Review is Complete | 04/20/2023 |
| 0MM1 Conduct Multimodal Review | | | |
| Complete | NA | | Date Completed |
| ✓ | | Confirm Multimodal Review is Complete | 04/04/2023 |
| ✓ | | Review Multimodal Considerations & Recommendations | 04/27/2023 |
| 0TO1 Conduct Initial Traffic Ops/TSMO Review <i>(include HQ Traffic Ops and Regional Traffic Office)</i> | | | |
| Complete | NA | | Date Completed |
| ✓ | | Confirm Transportation Systems Management & Operations (TSMO) Alignment & Operations Review is Complete | 04/04/2023 |
| ✓ | | Request Concept Report Review | 03/22/2023 |
| 0ST1 Develop Structures Recommendations | | | |
| Complete | NA | | Date Completed |
| ✓ | | Confirm Recommended Structure Type for Concept Report is Complete | 08/12/2022 |
| ✓ | | Confirm Hydraulic Recommendations for Concept Report is Complete | 08/12/2022 |
| 0SY1 Provide Preliminary Survey Data | | | |
| Complete | NA | | Date Completed |
| | ✓ | Confirm Control Ground Survey Set | |
| | ✓ | Review Preliminary Survey Data | |
| | ✓ | Determine Time to Complete the Aerial Survey | |
| 0GT1 Conduct Preliminary Geotechnical Assessment | | | |
| Complete | NA | | Date Completed |
| | ✓ | Confirm Geotechnical Division Review is Complete | |
| 0RD1 Provide Roadway Desktop Review | | | |
| Complete | NA | | Date Completed |
| ✓ | | Confirm Roadway Division Review is Complete | 04/19/2023 |

| Action Checklist | | | |
|--|----|--|----------------|
| OSD2 Develop Draft Concept Report | | | |
| Complete | NA | | Date Completed |
| | ✓ | Conduct Intersection and Interchange Evaluation (IIE) | |
| | ✓ | Complete Conceptual Signal Warrants | |
| ✓ | | Develop Draft Conceptual Layouts/Crash Figures for Site Visit | 12/07/2022 |
| ✓ | | Compile Initial Divisional Reviews for Site Visit | 04/13/2023 |
| ✓ | | Prepare & Send Site Visit Packet | 03/22/2023 |
| ✓ | | Lead Site Visit | 04/19/2023 |
| | ✓ | Initiate Interstate Access Requests (IAR) Concept Coordination with FHWA (if applicable) | |
| ✓ | | Develop, Compile, and Distribute the Draft Concept Report | 05/01/2023 |
| OTO2 Develop TSMO Scope Items <i>(include HQ Traffic Ops and Regional Traffic Office)</i> | | | |
| Complete | NA | | Date Completed |
| | ✓ | Confirm Signal Warrants Analysis is Complete | |
| | ✓ | Confirm Lighting Warrants Analysis is Complete | |
| | ✓ | Review and Confirm TSMO & ITS Scope and Budget | |
| ORW1 Complete Preliminary Right-of-Way Estimates | | | |
| Complete | NA | | Date Completed |
| | ✓ | Review and Confirm Preliminary Right-of-Way Cost Estimates | |
| OUT1 Complete Utility Preliminary Estimates | | | |
| Complete | NA | | Date Completed |
| | ✓ | Review and Confirm Preliminary Utility Estimate | |
| | ✓ | Review and Confirm Preliminary Railroad Cost Estimate | |
| OSD3 Finalize Concept Report | | | |
| Complete | NA | | Date Completed |
| | ✓ | Compile and Review Initial Risk Assessment | |
| ✓ | | Finalize Conceptual Layouts | 12/08/2023 |
| ✓ | | Develop Environmental Technical Study Area (ETSA) | 04/28/2023 |
| ✓ | | Address Comments and Finalize Concept Report | 12/08/2023 |
| | ✓ | Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable) | |
| | ✓ | Develop Roadway Safety Audit (RSA) No Plans Document | |
| ✓ | | Submit the final Concept Report for Review and Signatures (as needed; see OSD3 for additional information) | 12/27/2023 |
| ✓ | | Finalize Document and Upload All Needed Electronic Files | 01/19/2024 |
| ✓ | | Notify the Project Management Director or Assigned Project Manager to Set Up Project (1PM1) | 01/19/2024 |

NA Justification

Coordinate with Long Range Planning-Long Range Planning coordination not needed for STID BCR document
Request Preliminary Survey Data- survey data not needed for STID BCR document
OTO1 Conduct Initial Traffic Ops/TSMO Review-Traffic Ops had no comments
OSY1 Provide Preliminary Survey Data- survey data not needed for STID BCR document
OGT1 Conduct Preliminary Geotechnical Assessment- geotechnical data not received for STID BCR document
Conduct Intersection and Interchange Evaluation (IIE)-no interchange within project limits
Complete Conceptual Signal Warrants-signal not warranted due to low AADT
Initiate Interstate Access Requests (IAR) Concept Coordination with FHWA (if applicable)-no interstate within project limits
OTO2 Develop TSMO Scope Items-no signals or lighting needed within project limits
ORW1 Complete Preliminary Right-of-Way Estimates-ROW estimate calculated in cost estimate
OUT1 Complete Utility Preliminary Estimates-utility cost calculated in cost estimate
Compile and Review Initial Risk Assessment-Risk Assessment not needed for STID BCR document
Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable)-no interstate within project limits
Develop Roadway Safety Audit (RSA) No Plans Document- no plans document not needed for STID BCR document


Concept Report Table of Contents/Attachments

| | Included | NA |
|---|----------|----|
| One-Page Summary (with project location map) | ✓ | |
| Conceptual Layout(s) and Cross Section | ✓ | |
| Environmental Technical Study Area (ETSA) Layout | ✓ | |
| Concept Cost Estimate (Construction Year Estimate) | ✓ | |
| TSMO & ITS Scope and Budget ¹ | | ✓ |
| ROW Form 44-A ¹ | | ✓ |
| Crash Packet ¹ | ✓ | |
| Crash Prediction Analysis ¹ | | ✓ |
| Site Visit Attendee List | ✓ | |
| Environmental Desktop Review Form ¹ | ✓ | |
| Multimodal Considerations & Recommendations ¹ | ✓ | |
| Existing Structure Summary ¹ | ✓ | |
| Email or memo containing Structure Type Recommendations ¹ | | ✓ |
| Email or memo containing Hydraulic Recommendations ¹ | ✓ | |
| Hydraulic Data | ✓ | |
| Intersection and Interchange Evaluation (IIE) Analysis and Summary Form | | ✓ |
| Traffic Analysis Summary/Tables | ✓ | |
| Forecasted Traffic Sheets ¹ | ✓ | |
| Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output) ¹ | | ✓ |
| Signal Warrant ¹ | | ✓ |
| Lighting Warrant ¹ | | ✓ |
| Initial Risk Assessment using the Risk Assessment Form | | ✓ |
| Final Interstate Access Request (IAR) Document and Memo with Letter from STID Director | | ✓ |
| Road Safety Audit (RSA) No Plans ¹ | | ✓ |

NA Justification


TSMO & ITS Scope and Budget-no ITS within project limits; ROW Form 44-A-form not needed for STID BCR document
 Crash Prediction Analysis- only 3 crashes occurred within the project limits, crash prediction analysis not needed
 Email or memo containing Structure Type Recommend-structures recommendations came from Hydraulics
 Intersection and Interchange Evaluation (IIE) Analysis and Summary Form- AADT is too low for IIE Analysis
 Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output)- AADT too low to model
 Signal Warrant-no signals warranted within project limits; Lighting Warrant-no lighting warranted within project limits
 Initial Risk Assessment using the Risk Assessment Form-Risk Assessment not needed for STID BCR document
 Final IAR Document and Memo with Letter from STID Director-no interstate access within project limits
 Road Safety Audit (RSA) No Plans-RSA no plans document not needed for STID BTIR document

¹ External document to STID






AREA MAP
 STATE ROUTE 353 (BAILEY BRIDGE RD.)
 BRIDGE OVER NOLICHUCKY RIVER
 L.M. 0.45
 WASHINGTON COUNTY
 PIN 132623.00






| | | |
|--|---|--|
| | <p>TOPOGRAPHIC MAP STATE ROUTE 353 (BAILEY BRIDGE RD.) BRIDGE OVER NOLICHUCKY RIVER L.M. 0.45 WASHINGTON COUNTY PIN 132623.00</p> | |
|--|---|--|




| | | |
|---|---|---|
|  | <p><u>LOCATION MAP</u> STATE ROUTE 353 (BAILEY BRIDGE RD.) BRIDGE OVER NOLICHUCKY RIVER L.M. 0.45 WASHINGTON COUNTY PIN 132623.00</p> |  |
|---|---|---|

| TYPE | YEAR | COUNTY | FIGURE NO. |
|------|------|------------|------------|
| BCR | 2023 | WASHINGTON | 1 |



11/20/2023 9:30:06 AM
X:\Projects\Washington\SR 353\Bridge over Nolichucky River, LM 0.45\Project Files\Microstation\DGN Files\Existing Alignment Sheets\SHT_01.dgn



BRIDGE CONCEPT REPORT


STATE ROUTE 353 (BAILEY BRIDGE RD.)
LOG MILE 0.45
WASHINGTON COUNTY

CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
S.T.I.D.

FIGURE 1
STATE ROUTE 353
(BAILEY BRIDGE RD.)
LOG MILE 0.45

| TYPE | YEAR | COUNTY | FIGURE NO. |
|------|------|------------|------------|
| ETSA | 2023 | WASHINGTON | 2 |



ENVIRONMENTAL TECHNICAL STUDY AREA


STATE ROUTE 353 (BAILEY BRIDGE RD.)
LOG MILE 0.45
WASHINGTON COUNTY

CAUTION!
PRELIMINARY
PLANS
SUBJECT TO
CHANGE


STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
S.T.I.D.

FIGURE 2
STATE ROUTE 353
(BAILEY BRIDGE RD.)
LOG MILE 0.45


EXISTING STRUCTURE



PHASE CONSTRUCTION




PROPOSED STRUCTURE




TOTAL WIDTH = 35'3"

CROSS SECTION DETAIL AND CONSTRUCTION
SE 353 (BAILEY BRIDGE RD.) WASHINGTON COUNTY
BRIDGE OVER NOLICHUCKY RIVER L.M. 0.45
BRIDGE ID 90S23860001

EXISTING PROFILE



PROPOSED PROFILE



BRIDGE PROFILES

SR 353 (BAILEY BRIDGE RD.) WASHINGTON COUNTY
BRIDGE OVER NOLICHUCKY RIVER L.M. 0.45
BRIDGE ID 90S23860001

COST ESTIMATE SUMMARY

| COST ESTIMATE SUMMARY | | | | |
|-----------------------|-----------------------------|--|--|--|
| Route: | SR 353 | | | |
| Termini: | From L.M. 0.36 to L.M. 0.71 | | | |
| Scope of Work: | Replace bridge | | | <div style="border: 1px solid black; padding: 5px; background-color: #f0f0f0;"> Estimate Developed By Initial/Organization TT/TDOT </div> |
| Project Type of Work: | Bridge Replacement | | | |
| County: | Washington | | | |
| Length: | 0.50 Miles | | | |
| Date: | December 13, 2023 | | | |
| Estimate Type: | Design-Bid-Build | | | <div style="border: 1px solid black; padding: 5px; background-color: #f0f0f0;"> Estimate Developed By Initial/Organization TT/TDOT </div> |
| Years Inflated: | 0 | | | |

| DESCRIPTION | LOCAL | STATE | FEDERAL | TOTAL |
|--|-------|--------------------|----------------|----------------------|
| | 0% | 0% | 0% | |
| Construction Items | | | | |
| Removal Items | \$0 | \$0 | \$0 | \$81,500 |
| Asphalt Paving | \$0 | \$0 | \$0 | \$668,000 |
| Concrete Pavement | \$0 | \$0 | \$0 | \$0 |
| Drainage | \$0 | \$0 | \$0 | \$154,000 |
| Appurtenances | \$0 | \$0 | \$0 | \$0 |
| Structures & Contingency | \$0 | \$0 | \$0 | \$5,330,000 |
| Fencing | \$0 | \$0 | \$0 | \$0 |
| Signalization & Lighting | \$0 | \$0 | \$0 | \$0 |
| Railroad Crossing | \$0 | \$0 | \$0 | \$0 |
| Earthwork | \$0 | \$0 | \$0 | \$724,000 |
| Clearing and Grubbing | \$0 | \$0 | \$0 | \$8,900 |
| Seeding & Sodding | \$0 | \$0 | \$0 | \$26,000 |
| Rip-Rap or Slope Protection | \$0 | \$0 | \$0 | \$0 |
| Guardrail | \$0 | \$0 | \$0 | \$73,800 |
| Signing | \$0 | \$0 | \$0 | \$7,100 |
| Pavement Markings | \$0 | \$0 | \$0 | \$22,200 |
| Maintenance of Traffic | \$0 | \$0 | \$0 | \$121,000 |
| Construction Lines and Stakes | \$0 | \$0 | \$0 | \$131,000 |
| DESIGN-BID-BUILD & DESIGN-BUILD PERCENTAGES | | | | |
| Mobilization | 10% | \$0 | \$0 | \$722,000 |
| Additional Items | 20% | \$0 | \$0 | \$1,440,000 |
| Const. Contingency (Structures Not Included) | 50% | \$0 | \$0 | \$2,020,000 |
| Const. Eng. & Inspec. | 15% | \$0 | \$0 | \$1,710,000 |
| Construction Estimate - DBB & DB | | \$0 | \$0 | \$13,200,000 |
| Right-of-Way & Utilities | | | | |
| | 0% | 0% | 0% | TOTAL |
| Right-of-Way | | \$0 | \$0 | \$472,000 |
| Utilities | | \$0 | \$0 | \$1,120,000 |
| Preliminary Engineering | | | | |
| | 0% | 0% | 0% | TOTAL |
| Prelim. Eng. (Design-Bid-Build) 10.0% | | \$0 | \$0 | \$1,320,000 |
| Design-Bid-Build Project Cost | | \$0 | \$0 | \$ 16,100,000 |
| ESTIMATE REVIEW TEAM | | | | |
| Review Process Applies to Bridge, Legislative, and Economic Development Projects | | | | |
| | ROLE | NAME/ORGANIZATION | DATE COMPLETED | |
| Primary Cost Estimate (Before Draft Report): | | Ty Tucker/TDOT | 11/20/2023 | |
| Independent Cost Estimate: | | Emily Burgess/TDOT | 11/21/2023 | |
| Manager Review: | | Caleb Smith/TDOT | 12/11/2023 | |
| QA/QC performed by: | | John Davey/TDOT | 12/13/2023 | |

PAY ITEM SUMMARY


| TDOT PAY ITEM | TDOT DESCRIPTION | UNIT | TOOL QUANTITIES | ADDITIONAL QUANTITIES | TOOL QUANTITIES + ADDITIONAL | Unit Price | TOTAL COST |
|---|--|------|-----------------|-----------------------|------------------------------|--------------|-----------------|
| Pavment Removal | | | | | | | |
| 202-03.01 | REMOVAL OF ASPHALT PAVEMENT | SY | 4974 | | 4974 | \$ 16.37 | \$ 81,422.56 |
| PAVEMENT REMOVAL TOTAL (ROUNDED) | | | | | | | \$ 81,500 |
| Asphalt Roads | | | | | | | |
| 303-01 | MINERAL AGGREGATE, TYPE A BASE, GRADING D | TON | 8527 | | 8527 | \$ 37.18 | \$ 317,049.93 |
| 307-(01, 02, 03).01 | ASPHALT CONCRETE MIX (All Grades) (BPMB-HM) GRADING A | TON | 1008 | | 1008 | \$ 112.37 | \$ 113,311.64 |
| 307-01 (20 & 21 & 22) | AGGREGATE (BPMB-HM) GRADING A-S MIX | TON | 436 | | 436 | \$ 122.73 | \$ 53,460.38 |
| 307-(01 & 02 & 03).08 | ASPHALT CONCRETE MIX (ALL GRADES) (BPMB-HM) GRADING B-M2 | TON | 859 | | 859 | \$ 105.33 | \$ 90,525.11 |
| 402-01 | BITUMINOUS MATERIAL FOR PRIME COAT (PC) | TON | 11 | | 11 | \$ 1,064.94 | \$ 11,220.04 |
| 402-02 | AGGREGATE FOR COVER MATERIAL (PC) | TON | 38 | | 38 | \$ 89.00 | \$ 3,384.47 |
| 403-01 | BITUMINOUS MATERIAL FOR TACK COAT (TC) | TON | 6 | | 6 | \$ 924.09 | \$ 5,403.59 |
| 411-01.07 | ACS MIX (PG64-22) GRADING E SHOULDER | TON | 142 | | 142 | \$ 124.81 | \$ 17,710.54 |
| 411-(01 & 02 & 03).10 | ACS MIX(ALL GRADES) GRADING D | TON | 420 | | 420 | \$ 133.70 | \$ 56,173.79 |
| PAVING TOTAL (ROUNDED) | | | | | | | \$ 668,300 |
| Concrete Roads | | | | | | | |
| CONCRETE RAMPS AND ROADWAYS TOTAL (ROUNDED) | | | | | | | \$ - |
| Drainage | | | | | | | |
| 607-05.02 | 24" CONCRETE PIPE CULVERT (CLASS III) | LF | 274 | | 274 | \$ 172.02 | \$ 47,123.16 |
| 611-07.01 | CLASS A CONCRETE (PIPE ENDWALLS) | CY | 16 | | 16 | \$ 1,888.61 | \$ 30,285.03 |
| 611-07.02 | STEEL BAR REINFORCEMENT (PIPE ENDWALLS) | LB | 1524 | | 1524 | \$ 3.96 | \$ 6,034.56 |
| 710-02 | Aggregate Underdrains (with pipe) | LF | 5259 | | 5259 | \$ 13.48 | \$ 70,889.70 |
| DRAINAGE TOTAL (ROUNDED) | | | | | | | \$ 154,400 |
| Appurtenances | | | | | | | |
| ROADWAY AND PAVEMENT APPURTENANCES TOTAL (ROUNDED) | | | | | | | \$ - |
| Earthwork & Mineral | | | | | | | |
| 203-01 | ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED) | CY | 17610 | | 17610 | \$ 14.81 | \$ 260,798.97 |
| 203-02.01 | BORROW EXCAVATION (GRADED SOLID ROCK) | TON | 9705 | | 9705 | \$ 32.33 | \$ 313,766.54 |
| 203-03 | BORROW EXCAVATION (UNCLASSIFIED) | CY | 5503 | | 5503 | \$ 13.27 | \$ 73,049.62 |
| 203-50 | CONSTRUCTION OF HAUL ROAD | LS | | 1 | 1 | \$ 75,814.63 | \$ 75,814.63 |
| EARTHWORK & MINERAL TOTAL (ROUNDED) | | | | | | | \$ 723,500 |
| Construction Lines and Stakes | | | | | | | |
| 105-01 | Construction Lines and Stakes | LS | 1 | | 1 | | \$ 131,000.00 |
| | | | | | | | \$ 131,000 |
| Structures | | | | | | | |
| N/A | Removal of Bridge | SF | 10089 | | 10089 | \$ 30.00 | \$ 302,670.00 |
| N/A | New Bridge (Concrete Box Beam): | SF | 13395 | | 13395 | \$ 250.00 | \$ 3,348,750.00 |
| N/A | Contingency - New Bridge (Concrete Box Beam): | % | 50.0% | | | \$ 50.0% | \$ 1,674,375.00 |
| STRUCTURES TOTAL (ROUNDED) | | | | | | | \$ 5,325,800 |
| Interchanges and Unique Intersections | | | | | | | |
| INTERCHANGES AND UNIQUE INTERSECTIONS TOTAL (ROUNDED) | | | | | | | \$ - |
| Lighting & Signalization | | | | | | | |
| LIGHTING & SIGNALIZATION TOTAL (ROUNDED) | | | | | | | \$ - |
| Guardrail | | | | | | | |
| 705-01.01 | GUARDRAIL AT BRIDGE ENDS | LF | 100 | 500 | 600 | \$ 99.88 | \$ 59,928.69 |
| 705-06.20 | Tangent Energy Absorbing Term Mash TL-3 | EA | 8 | -4 | 4 | \$ 3,457.56 | \$ 13,830.24 |
| GUARDRAIL TOTAL (ROUNDED) | | | | | | | \$ 73,800 |
| Seeding and Sodding | | | | | | | |
| 801-01 | SEEDING (WITH MULCH) | UNIT | 230 | | 230 | \$ 54.58 | \$ 12,557.55 |
| 801-01.07 | TEMPORARY SEEDING (WITH MULCH) | UNIT | 173 | | 173 | \$ 35.33 | \$ 6,096.44 |
| 801-02 | SEEDING (WITHOUT MULCH) | UNIT | 173 | | 173 | \$ 42.37 | \$ 7,311.24 |
| SODDING TOTAL (ROUNDED) | | | | | | | \$ 26,000 |
| Maintenance of Traffic | | | | | | | |
| N/A | Traffic Control | LS | 1 | | 1 | | \$ 115,344.90 |
| 712-02.02 | INTERCONNECTED PORTABLE BARRIER RAIL | LF | 131 | | 131 | \$ 46.05 | \$ 6,054.29 |
| MAINTENANCE OF TRAFFIC TOTAL (ROUNDED) | | | | | | | \$ 121,400 |
| Signs | | | | | | | |
| Not Listed | Signs (Construction) | LS | 1 | | 1 | \$ - | \$ 7,100 |
| SIGNING TOTAL (ROUNDED) | | | | | | | \$ 7,100 |
| Pavement Markings | | | | | | | |
| 716-12.02 | ENHANCED FLAT THERMO P.M. (6IN) | LM | 2,988 | | 2,988 | \$ 7,419.17 | \$ 22,174.42 |
| PAVEMENT MARKINGS TOTAL (ROUNDED) | | | | | | | \$ 22,200 |
| Fencing | | | | | | | |
| FENCE TOTAL (ROUNDED) | | | | | | | \$ - |
| Rip-Rap | | | | | | | |
| RIP-RAP & SLOPE PROTECTION TOTAL (ROUNDED) | | | | | | | \$ - |
| Clearing and Grubbing | | | | | | | |
| 201-01 | Clearing and Grubbing | LS | | | 1 | \$ 8,900.00 | \$ 8,900.00 |
| CLEAR AND GRUBBING TOTAL (ROUNDED) | | | | | | | \$ 8,900.00 |
| Railroad At-Grade Crossing | | | | | | | |
| RAILROAD CROSSING OR SEPARATION TOTAL (ROUNDED) | | | | | | | \$ - |
| Utilities | | | | | | | |
| N/A | Overhead Distribution | LM | 0.35 | | 0.35 | \$ 900,000 | \$ 315,000 |
| N/A | Underground Gas | LM | 0.35 | | 0.35 | \$ 1,452,000 | \$ 508,200 |
| N/A | Underground Water | LM | 0.35 | | 0.35 | \$ 840,000 | \$ 294,000 |
| UTILITIES TOTAL (ROUNDED) | | | | | | | \$ 1,117,200.00 |
| Right-of-Way | | | | | | | |
| N/A | Right-of-Way | LS | 1 | | 1 | \$ 472,000 | \$ 472,000.00 |
| RIGHT-OF-WAY TOTAL (ROUNDED) | | | | | | | \$ 472,000.00 |

| COST ESTIMATE SUMMARY (2023) - DESIGN-BID-BUILD | | | | | | |
|---|----------------------|--------------------------|---------------|--------------|---------------|----------------------------|
| PIN | Project Type of Work | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Project Cost (2023): |
| 132623.00 | Replace bridge | \$ 1,320,000 | \$ 472,000 | \$ 1,120,000 | \$ 13,200,000 | \$ 16,200,000 |
| COST ESTIMATE SUMMARY (2023) - DESIGN-BUILD | | | | | | |
| PIN | Project Type of Work | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Project Cost (2023): |
| 132623.00 | Replace bridge | \$ 2,650,000 | \$ 472,000 | \$ 1,120,000 | \$ 13,200,000 | \$ 17,400,000 |
| COST ESTIMATE SUMMARY (2023) - CMGC & HIGH RISK SCENARIOS | | | | | | |
| PIN | Project Type of Work | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Project Cost (2023): |
| 132623.00 | Replace bridge | \$ 4,100,000 | \$ 472,000 | \$ 1,120,000 | \$ 16,400,000 | \$ 22,100,000 |

| DESIGN-BID-BUILD - INFLATED COST | | | | | | |
|----------------------------------|------|--------------------------|---------------|--------------|---------------|-----------------------------|
| No. of Years | Year | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Inflated Project Cost |
| 0 | 2023 | \$ 1,320,000 | \$ 472,000 | \$ 1,120,000 | \$ 13,200,000 | \$ 16,200,000 |
| 1 | 2024 | \$ 1,410,000 | \$ 505,000 | \$ 1,200,000 | \$ 14,100,000 | \$ 17,300,000 |
| 2 | 2025 | \$ 1,510,000 | \$ 540,000 | \$ 1,280,000 | \$ 15,100,000 | \$ 18,500,000 |
| 3 | 2026 | \$ 1,620,000 | \$ 578,000 | \$ 1,370,000 | \$ 16,200,000 | \$ 19,800,000 |
| 4 | 2027 | \$ 1,730,000 | \$ 619,000 | \$ 1,470,000 | \$ 17,300,000 | \$ 21,200,000 |
| 5 | 2028 | \$ 1,850,000 | \$ 662,000 | \$ 1,570,000 | \$ 18,500,000 | \$ 22,700,000 |
| 6 | 2029 | \$ 1,980,000 | \$ 708,000 | \$ 1,680,000 | \$ 19,800,000 | \$ 24,300,000 |
| 7 | 2030 | \$ 2,120,000 | \$ 758,000 | \$ 1,800,000 | \$ 21,200,000 | \$ 26,000,000 |
| 8 | 2031 | \$ 2,270,000 | \$ 811,000 | \$ 1,920,000 | \$ 22,700,000 | \$ 27,800,000 |
| 9 | 2032 | \$ 2,430,000 | \$ 868,000 | \$ 2,060,000 | \$ 24,300,000 | \$ 29,800,000 |
| 10 | 2033 | \$ 2,600,000 | \$ 928,000 | \$ 2,200,000 | \$ 26,000,000 | \$ 31,900,000 |
| DESIGN-BUILD - INFLATED COST | | | | | | |
| No. of Years | Year | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Inflated Project Cost |
| 5 | 2028 | \$ 3,720,000 | \$ 662,000 | \$ 1,570,000 | \$ 18,500,000 | \$ 24,400,000 |
| 10 | 2033 | \$ 5,210,000 | \$ 928,000 | \$ 2,200,000 | \$ 26,000,000 | \$ 34,200,000 |
| CMGC (HIGH RISK) - INFLATED COST | | | | | | |
| No. of Years | Year | Preliminary Engineering: | Right-of-Way: | Utilities: | Construction: | Total Inflated Project Cost |
| 5 | 2028 | \$ 5,750,000 | \$ 662,000 | \$ 1,570,000 | \$ 23,000,000 | \$ 31,000,000 |
| 10 | 2033 | \$ 8,070,000 | \$ 928,000 | \$ 2,200,000 | \$ 32,300,000 | \$ 43,500,000 |

| INFLATION INPUTS | |
|------------------|-------|
| Inflation Rate: | 7.00% |

12/7/2022 14:24:44 AM
X:\Projects\Washington\SR 353\Bridge over Nolichucky River, LM 0.45\Project Files\Microstation\DCN Files\Bridge over Nolichucky River SHI_0.dgn



CRASH DIAGRAM
BRIDGE OVER NOLICHUCKY RIVER
STATE ROUTE 353 (BAILEY BRIDGE RD.) LOG MILE 0.45
WASHINGTON COUNTY

APPENDIX

1.0 Site Visit Attendee List

BRIDGE CONCEPT REPORT (BCR)WASHINGTON COUNTY
SR 353 (Bailey Bridge Rd.)

| SITE VISIT ATTENDEES | | | DATE: 4/19/2023 |
|----------------------|----------------------|--|-----------------|
| Name | Organization | Email | |
| Ty Tucker | TDOT - STID | ty.tucker@tn.gov | |
| Konner Spradlin | TDOT - STID | konner.spradlin@tn.gov | |
| Amy Rauch | TDOT - STID | amy.rauch@tn.gov | |
| Stephanie Wallis | TDOT - Design | stephanie.wallis@tn.gov | |
| Keven Brown | TDOT - Environmental | keven.brown@tn.gov | |
| Matt Beeler | TDOT - Environmental | matthew.beeler@tn.gov | |
| Brittney Hensley | TDOT - Environmental | brittney.hensley@tn.gov | |
| Nicholas Barnard | TDOT - Traffic | nicholas.barnard@tn.gov | |
| Emily Burgess | TDOT - STID | emily.burgess@tn.gov | |
| John Davey | TDOT- STID | john.davey@tn.gov | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

2.0 Environmental Desktop Review

0EN1 Environmental Desktop Review Form

Part 1 – Project Information

| | |
|--------------------------------------|---------------------------------------|
| PIN | 132623.00 |
| Project Number (if available) | |
| County | Washington |
| Route | SR-353 |
| Termini | Bridge over Nolichucky River, LM 0.45 |
| Type of Document | |
| Date ENV DIV Comments are Due | April 7, 2023 @ noon |

Part 2: Provide information identifying known Environmental Resources within the proposed project area using the attached information. If no known resources are identified, each study area should note that none were identified.

Air & Noise

AIR QUALITY

Transportation Conformity

This project is in Washington County which is in attainment for all regulated criteria pollutants. Therefore, conformity does not apply to this project.

Mobile Source Air Toxics (MSATs)

This project qualifies as a categorical exclusion under 23 CFR 771.117 and, therefore, does not require an evaluation of MSATs per FHWA's "Interim Guidance Update on Air Toxic Analysis in NEPA Documents" dated January 2023.

NOISE

The new bridge will be located southeast of the existing structure. However, the relocation will not halve the distance between the center of the near travel lane and an adjacent noise-sensitive land use. Therefore, the project is Type III in accordance with the FHWA noise regulation in 23 CFR 772 and TDOT's noise policy and a noise study is not needed.

Cultural Resources

[Add comments Here]

Ecology

- There is one perennial stream within project limits.
- There are several cliff swallow nests on existing bridge
- There are 10 endangered/threatened species with 4 miles of project

HazMat

No known hazardous materials sites impact this bridge replacement as shown in the TIR. An Asbestos Containing Material (ACM) survey was completed on Bridge No. 90S23860001 SR-353 over Nolichucky River LM 0.45 (90-SR353-00.45). The bridge has asbestos in 116 deck drains at 6% chrysotile and 4% crocidolite, and 2000 square feet of bearing pads at 20% chrysotile. Please see the report for further details and photographs. The State of Tennessee asbestos accreditation requirements (TDEC Rules Chapter 1200-01-20) mandates that ACM abatement work be performed by an accredited firm (contractor) using accredited abatement workers and supervisors. Abatement of this material shall be accomplished per SP202ACM Special Provision Regarding Removal of Asbestos-Containing Materials. ACM abatement should be completed prior to any demolition activities if possible. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Sections 107.08.D and 202.03).

NEPA

[Add comments Here]

Ty Tucker

From: TDOT.Env HazmatOffice
Sent: Monday, April 10, 2023 11:44 AM
To: TDOT.ENV SpecialProjects; Amy Rauch; K.Brandon Chance
Subject: HazMat Review OSD1 Cocke and Washington County Bridges 124254.00, 124272.00, 124279.00, and 132623.00

The following comments have been submitted:

For 124254.00. No known hazardous materials sites impact this bridge replacement as shown in the TIR. An asbestos bridge survey is required.

For 124272.00. No known hazardous materials sites impact this bridge replacement as shown in the TIR. An asbestos bridge survey is required.

For 124279.00. No known hazardous materials sites impact this bridge replacement as shown in the TIR. An Asbestos Containing Material (ACM) survey was completed on Bridge No. 150A4470001 Ball Park Rd over Cosby Creek LM 0.28 (15-0A447-00.28). No asbestos was detected. Please see the report for further details and photographs. No special accommodations for demolition and waste disposal are anticipated for these structures and the material can be deposited in a C&D landfill. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Sections 107.08.D and 202.03).

For 132623.00. No known hazardous materials sites impact this bridge replacement as shown in the TIR. An Asbestos Containing Material (ACM) survey was completed on Bridge No. 90S23860001 SR-353 over Nolichucky River LM 0.45 (90-SR353-00.45). The bridge has asbestos in 116 deck drains at 6% chrysotile and 4% crocidolite, and 2000 square feet of bearing pads at 20% chrysotile. Please see the report for further details and photographs. The State of Tennessee asbestos accreditation requirements (TDEC Rules Chapter 1200-01-20) mandates that ACM abatement work be performed by an accredited firm (contractor) using accredited abatement workers and supervisors. Abatement of this material shall be accomplished per SP202ACM Special Provision Regarding Removal of Asbestos-Containing Materials. ACM abatement should be completed prior to any demolition activities if possible. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Sections 107.08.D and 202.03).



Kyle Kirschenmann, P.G. | Environmental Manager
Environmental Division | Hazardous Materials / Air and Noise Section
James K. Polk Building, Suite 900
505 Deaderick Street, Nashville, TN 37243
(615) 598-1522
kyle.kirschenmann@tn.gov

Ty Tucker

From: Troy J. Ebbert
Sent: Friday, March 24, 2023 2:32 PM
To: Amy Rauch
Subject: Re: Call for Comments (OSD1) - Cocke and Washington County Bridges (PINs 124254.00, 124272.00, 124279.00, and 132623.00)
Attachments: PIN 124254, Cocke County, Bridge over Sinking Creek Field Review.pdf; Cocke 0A407 (Caney Creek Rd.) Field Review Packet.pdf; Cocke (Ball Park Rd.) Field Review Packet.pdf; Washington SR 353 Field Review Packet.pdf; Site Visit -Cocke and Washington Counties Bridges (PINs 124254.00, 124272.00, 124279.00, and 132623.00).eml

Follow Up Flag: Follow up
Flag Status: Flagged

Amy,

The Washington county project at Baileys Bridge has a TWRA canoe launch near the bridge. I believe it is on the south west quadrant

Troy J. Ebbert, Region 1 Planning Supervisor
Long Range Planning Division
Office of Community Transportation
7345 Region Lane
Knoxville, TN 37914
O: (865) 594-2662 C: (865) 253-1436
Troy.J.Ebbert@TN.Gov
TN.Gov/tdot

On Mar 22, 2023, at 11:13 AM, Amy Rauch <Amy.Rauch@tn.gov> wrote:

All,

As a part of the Project Delivery Network (PDN) Stage OSD1 Early Coordination process, please see the attached PDFs to access the site visit packet for early comments. The purpose of receiving comments is to have initial input compiled from the different functional areas prior to the site visit to identify areas of interests. The proposed improvements are subject to change based on feedback we receive. We will compile all the comments we receive and discuss at the site visit. Below is the project information as well as a Google Maps link to the project location:

124254.00
Cocke
Chemwood Dr (0A055)
Bridge over Sinking Creek
<https://www.google.com/maps/dir//35.988267,-83.2063959/@35.9883247,-83.2070674,322m/data=!3m1!1e3!4m2!4m1!1e0?hl=en><https://urldefense.com/v3/__https://www.goo

Ty Tucker

From: Rachel Head
Sent: Tuesday, April 11, 2023 12:26 PM
To: Amy Rauch
Cc: Sharon Sanders
Subject: RE: Call for Comments (OSD1) - Cocke and Washington County Bridges (PINs 124254.00, 124272.00, 124279.00, and 132623.00)
Attachments: FM47029C0155E_124254.00.pdf; FM47029C0265E_124272.00.pdf; FM47029C0255E_124279.00.pdf; FM47179C0240D_132623.00.pdf

Good morning Amy,

I was unable to access the linked comment sheets on Sharepoint.

Please see NEPA's initial comments for the 4 bridge projects:

1. Cocke, PIN 124254.00: It is not indicated whether ROW acquisition or permanent easements will be required on this project. The addition of ROW and/or permanent acquisitions could alter NEPA's concerns. Based on a visual inspection of the project location through Google Earth and Google Maps, it does not appear that any know Section 4(f)resources are adjacent to the project site. A desktop search of LWCF-funded projects in Cocke County shows no projects close to the project location. A desktop search of FEMA floodplains in the area confirmed that the bridge project spans a 100-year floodplain (Zone AE). Please see the attached National Flood Hazard Layer FIRM map for confirmation.
2. Cocke, 124272.00: It is not indicated whether ROW acquisition or permanent easements will be required on this project. It is assumed that Option 2 would result in more acquisition. The addition of ROW and/or permanent acquisitions could alter NEPA's concerns. Based on a visual inspection of the project location through Google Earth and Google Maps, it does not appear that any know Section 4(f)resources are adjacent to the project site. A desktop search of LWCF-funded projects in Cocke County shows no projects close to the project location. A desktop search of FEMA floodplains in the area confirmed that the bridge project spans a 100-year floodplain (Zone AE). Please see the attached National Flood Hazard Layer FIRM map for confirmation.
3. Cocke, 124279.00: It is not indicated whether ROW acquisition or permanent easements will be required on this project. The addition of ROW and/or permanent acquisitions could alter NEPA's concerns. Based on a visual inspection of the project location through Google Earth and Google Maps, it does not appear that any know Section 4(f)resources are adjacent to the project site. A desktop search of LWCF-funded projects in Cocke County shows no projects close to the project location. A desktop search of FEMA floodplains in the area confirmed that the bridge project spans a 100-year floodplain (Zone AE). Please see the attached National Flood Hazard Layer FIRM map for confirmation.
4. Washington, 132623.00: It is not indicated whether ROW acquisition or permanent easements will be required on this project. The addition of ROW and/or permanent acquisitions could alter NEPA's concerns. Currently, this project is showing state-only funding in PPRM. Therefore, Section 4(f) is not applicable. Based on a visual inspection of the project location through Google Earth and Google Maps, it does not appear that any know Section 4(f)resources are adjacent to the project site. A desktop search of LWCF-funded projects in Washington County shows no projects close to the project location. . A desktop search of FEMA floodplains in the area confirmed that the bridge project spans a 100-year floodplain (Zone A). Please see the attached National Flood Hazard Layer FIRM map for confirmation.

Thank you,
Rachel

| Environmental Justice Analysis Tables | | | | |
|--|-------------------|--|--|--------------------|
| Minority Populations | | | | |
| Census Tract (CT)/ Block Group (BG) | CT 619.04 BG 1 | | | Washin gton Co. |
| % Minority/Non- White | 0.0% | | | 12.3% |
| Exceeds County Average by 10% or More | No | | | |
| Is BG Population Avg. >50% | No | | | |
| Meet EJ Criteria? | No | | | |
| Low-Income Populations | | | | |
| Census Tract (CT)/ Block Group (BG) | CT 619.04 BG 1 | | | Washin gton Co. |
| % Low-Income/Below Poverty Line | 31.5% | | | 15.3% |
| Exceeds County Average by 10% or More | Yes | | | |
| Is BG Population Avg. >50% | No | | | |
| Meet EJ Criteria? | Yes | | | |
| Source: U.S. Census Bureau, 2017-2021 American Community Survey (ACS) 5-Year Estimates. ACS data was accessed and reviewed on 04/12/2023 via the U.S. Census Bureau website. | | | | |

3.0 Multimodal Considerations and Recommendations

OMM1 MM Review



Introduction

No purpose and need was given for any bridge. It is assumed the low bridge structural ratings and typical sections not following TDOT standards initiated the bridge replacements.

Planning literature review used for this OMM1 review:

No local plans were found.

Summary of Recommendations

132623.00

At this 35 mph speed on the bridge, 6' shoulders as written will accommodate cyclists. It will not accommodate pedestrians. This is not a state bike route, but cyclist volume is high along this bridge. On both sides, 5' sidewalks with curb and gutter are requested.



4.0 Existing Structure Summary

BRIDGE MAINTENANCE RECOMMENDATIONS

COUNTY: WASHINGTON

LOCATION: 90-SR353-00.45-

CO. SEQ.: 1

SPEC. CASE: 0

Tennessee Department
of Transportation

CROSSING: NOLICHUCKY RIVER

FED. BRIDGE NO.: 90S23860001

MAINT. DIST.: 90

REPAIR LIST NO.: 1

DATE ADDED: 11/18/2019

REVISED: 10/25/2021

| | | | |
|---------------------------------|---------------------|---------------------------|------|
| FACILITY CARRIED: | FAS 353 | NUMBER OF MAIN SPANS: | 9 |
| HIGHWAY SYSTEM: | 05-STP RURAL, STATE | NUMBER OF APPROACH SPANS: | 0 |
| BRIDGE WIDTH (CURB TO CURB): | 23 FT 11 IN | BRIDGE LENGTH (FT): | 354 |
| BRIDGE WIDTH (OUT TO OUT): | 28 FT 6 IN | MAXIMUM SPAN LENGTH (FT): | 53 |
| APPROACH ROADWAY (W/SHOULDERS): | 25 FT 11 IN | SKEW ANGLE (DEGREES): | 90 |
| MAINTAINED BY: | | STATE HIGHWAY AGENCY | |
| MAIN SPAN MATERIAL: | | CONCRETE | |
| MAIN SPAN DESIGN TYPE: | | TEE BEAM | |
| APPROACH SPAN MATERIAL: | | OTHER OR NOT APPLICABLE | |
| APPROACH SPAN DESIGN TYPE: | | OTHER OR NOT APPLICABLE | |
| INSPECTION DATE: | 10/25/2021 | GENERAL CONDITION: | POOR |
| EVALUATION DATE: | 11/18/2019 | STRUCTURALLY DEFICIENT: | YES |
| PPRM PIN NUMBER: | | | |
| H TRUCK RATING @ INV.: | 12 TONS | SUFFICIENCY RATING: | 37.0 |

| No. | RECOMMENDATIONS | REPAIR DATE | REPAIRED BY |
|-----|--|-------------|-------------|
| 1. | PATCH CONCRETE SPALLS, CRACKS & DELAMINATIONS THROUGHOUT STRUCTURE | | |
| 2. | REPAIR BEAM "D" SPAN NO. 3 AND NO. 6 | | |
| 3. | REMOVE ASPHALT FROM BRIDGE | | |

SUGGESTED ROUTINE MAINTENANCE AND COMMENTS

CLEAN & PAINT BEARING - ALL

DECK DRAINS NEED DRAIN EXTENSIONS INSTALLED

FILL VOIDS BETWEEN FOOTING AND BEDROCK AT ABUTMENT NO. 1 AND 2

REPAIR RIP RAP AT ABUTMENT NO. 1

PATCH CRACKS IN WEARING SURFACE AT ALL JOINTS

REMOVE DRIFT

BRIDGERAILS ARE SUBSTANDARD

GENERAL COMMENTS:

BRIDGE APPEARS TO BE OVERLOADED WITH ASPHALT. THERE IS CURRENTLY 5" OF ASPHALT MEASURED ON THE STRUCTURE. IN SPAN NO. 6 THERE IS A 1 7/16 DEAD LOAD SAG IN THE SUPERSTRUCTURE. WHEN THE BRIDGE WAS LOADED WITH 20 TONS, THIS DEFLECTION WAS MEASURED AT 1 3/4". ALL BEAMS NOW EXHIBIT TRANSVERSE AND LONGITUDINAL CRACKING THROUGHOUT. BEAM "D" IN SPAN NO. 3 AND

LARGE RUPTURE DUE TO EXCESSIVE FLEXURE.

NOT REPRODUCED PURSUANT TO
PUBLIC RECORDS REQUEST
This document is covered by 23 USC §409
And its production pursuant to a public
document records request does not
waive the provisions of §409



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

Bridge Condition Coding Form

Revised 10/25/2021

Bridge Number: 90S238600011
(Includes Item 5A)

Feature Intersected: NOLICHUCKY RIVER

Evaluation Status: CONDITION ITEM CHANGE

County: 90

Route: SR353

Special Case: 0

County Sequence: 1

Log Mile: 0.45

CODE ONLY THOSE VALUES WHICH HAVE CHANGED

| ITEM # | DESCRIPTION | VALUE | CONDITION CODING GUIDELINES (Values for Coding Items 58, 59, 60 and 62) |
|-----------------------|---|--|--|
| 90 | LAST INSPECTION DATE | 10/25/2021 | N NOT APPLICABLE 9 EXCELLENT CONDITION 8 VERY GOOD CONDITION - NO PROBLEMS NOTED. 7 GOOD CONDITION - SOME MINOR PROBLEMS. 6 SATISFACTORY CONDITION - MINOR DETERIORATION OF STRUCTURAL ELEMENTS. 5 FAIR CONDITION - ALL PRIMARY STRUCTURAL ELEMENTS ARE SOUND BUT MAY HAVE MINOR SECTION LOSS, CRACKING, SPALLING OR SCOUR. 4 POOR CONDITION - ADVANCED SECTION LOSS, DETERIORATION, SPALLING OR SCOUR. 3 SERIOUS CONDITION - LOSS OF SECTION, DETERIORATION, SPALLING OR SCOUR HAVE SERIOUSLY AFFECTED PRIMARY STRUCTURAL COMPONENTS. LOCAL FAILURES ARE POSSIBLE. FATIGUE CRACKS IN STEEL OR SHEAR CRACKS IN CONCRETE MAY BE PRESENT. 2 CRITICAL CONDITION - ADVANCED DETERIORATION OF PRIMARY STRUCTURAL ELEMENTS. FATIGUE CRACKS IN STEEL OR SHEAR CRACKS IN CONCRETE MAY BE PRESENT OR SCOUR MAY HAVE REMOVED SUBSTRUCTURE SUPPORT. UNLESS CLOSELY MONITORED IT MAY BE NECESSARY TO CLOSE THE BRIDGE UNTIL CORRECTIVE ACTION IS TAKEN. 1 "IMMINENT" FAILURE CONDITION - MAJOR DETERIORATION OR SECTION LOSS PRESENT IN CRITICAL STRUCTURAL COMPONENTS OR OBVIOUS VERTICAL OR HORIZONTAL MOVEMENT AFFECTING STRUCTURAL STABILITY. BRIDGE IS CLOSED TO TRAFFIC BUT CORRECTIVE ACTION MAY PUT IT BACK IN LIGHT SERVICE. |
| | EARLIEST DATE OF NEXT REGULAR INSPECTION | 08/26/2023 | |
| 10 | MINIMUM V.C. OVER DECK (ROADWAY + SHOULDERS) | 99 FT. 99 IN. | |
| 520 | MINIMUM V.C. OVER DECK (EXCLUDES SHOULDERS) | 99 FT. 99 IN. | |
| 36 | TRAFFIC SAFETY FEATURES | | |
| | Br. Rail Trans. Appr. Rail Terminal SPEED LIMIT | 0 0 1 1 45 | |
| 41 | STRC OPEN/CLOSED/POSTED | P | |
| | A K P | | |
| 58 | DECK | 5 | |
| 59 | SUPERSTRUCTURE | 3 | |
| 60 | SUBSTRUCTURE | 5 | |
| 61 | CHANL/CHANL PROTECTION | 7 | |
| 62 | CULVERT AND RETAIN WALL | N | |
| 71 | WATERWAY ADEQUACY | 7 | |
| 72 | APPROACH RDWY ALIGNMENT | 8 | |
| 521 | OVERALL CONDITION | POOR | |
| 16 | LATITUDE | N 36° 9.3400' | |
| 17 | LONGITUDE | W 82° 35.4330' | |
| Adam Wallen | | Digitally signed by Adam Wallen Date: 2021.10.26 06:07:38 -04'00' | |
| TEAM LEADER SIGNATURE | | REVIEW DATE | |

PRODUCED PURSUANT TO
PUBLIC RECORDS REQUEST
This document is covered by 25 USC § 552
and its production pursuant to a public
document records request does not
waive the provisions of § 409




Upstream




Downstream




Looking east along SR 353 at intersection



Looking west along SR 353 at intersection



Looking west from structure



Looking east from structure



Looking west along edge of structure



Looking east along edge of roadway



Looking underneath structure




Potential water pipe underneath structure



Looking north along O O Moore Rd.



Looking south along O O Moore Rd.



Looking north along Bill Mauk Rd.



Looking south along Bill Mauk Rd.



Drainage along Bill Mauk Rd. near intersection



Existing property near intersection

5.0 Hydraulic Recommendations and Data

- 380 ft, 4 span, box beam. Raise grade 3 ft.

National Flood Hazard Layer FIRMette



82°35'46"W 36°9'35"N



0 250 500 1,000 1,500 2,000 Feet 1:6,000 44 82°35'8"W 36°9'6"N
Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

| | | |
|-----------------------------|--|---|
| SPECIAL FLOOD HAZARD AREAS | | Without Base Flood Elevation (BFE) Zone A, V, A99 |
| | | With BFE or Depth Zone AE, AO, AH, VE, AR |
| OTHER AREAS OF FLOOD HAZARD | | 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X |
| | | Future Conditions 1% Annual Chance Flood Hazard Zone X |
| | | Area with Reduced Flood Risk due to Levee. See Notes. Zone X |
| | | Area with Flood Risk due to Levee Zone D |
| OTHER AREAS | | NO SCREEN Area of Minimal Flood Hazard Zone X |
| | | Effective LOMRs |
| GENERAL STRUCTURES | | Area of Undetermined Flood Hazard Zone D |
| | | Channel, Culvert, or Storm Sewer |
| OTHER FEATURES | | Levee, Dike, or Floodwall |
| | | Cross Sections with 1% Annual Chance Water Surface Elevation |
| MAP PANELS | | Coastal Transect |
| | | Base Flood Elevation Line (BFE) |
| OTHER FEATURES | | Limit of Study |
| | | Jurisdiction Boundary |
| OTHER FEATURES | | Coastal Transect Baseline |
| | | Profile Baseline |
| OTHER FEATURES | | Hydrographic Feature |
| | | Digital Data Available |
| MAP PANELS | | No Digital Data Available |
| | | Unmapped |



The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.


This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **8/12/2022 at 9:14 AM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

StreamStats Report

Region ID: TN
Workspace ID: TN20220812125528613000
Clicked Point (Latitude, Longitude): 36.15610, -82.59052
Time: 2022-08-12 07:55:49 -0500



Collapse All

Basin Characteristics

| Parameter Code | Parameter Description | Value | Unit |
|----------------|---|--------|---------------|
| CLIMFAC2YR | Two-year climate factor from Lichy and Karlinger (1990) | 2.178 | dimensionless |
| CONTDA | Area that contributes flow to a point on a stream | 884.31 | square miles |
| CSL10_85 | Change in elevation divided by length between points 10 and 85 percent of distance along main channel to basin divide - main channel method not known | 16.86 | feet per mi |

| Parameter Code | Parameter Description | Value | Unit |
|----------------|---|--------|--------------------|
| DRNAREA | Area that drains to a point on a stream | 884.31 | square miles |
| PERMGTE2IN | Percent of area underlain by soils with permeability greater than or equal to 2 inches per hour | 67.712 | percent |
| RECESS | Number of days required for streamflow to recede one order of magnitude when hydrograph is plotted on logarithmic scale | 140 | days per log cycle |
| SOILPERM | Average Soil Permeability | 3.099 | inches per hour |

➤ Peak-Flow Statistics

Peak-Flow Statistics Parameters [100.0 Percent (884 square miles) MultiVariable Area 1]

| Parameter Code | Parameter Name | Value | Units | Min Limit | Max Limit |
|----------------|---------------------------------|--------|---------------|-----------|-----------|
| CONTDATA | Contributing Drainage Area | 884.31 | square miles | 0.2 | 9000 |
| CSL10_85 | Stream Slope 10 and 85 Method | 16.86 | feet per mi | 3.29 | 950 |
| CLIMFAC2YR | Tennessee Climate Factor 2 Year | 2.178 | dimensionless | 2.06 | 2.32 |

Peak-Flow Statistics Flow Report [100.0 Percent (884 square miles) MultiVariable Area 1]

Pll: Prediction Interval-Lower, Plu: Prediction Interval-Upper, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

| Statistic | Value | Unit | Pll | Plu | ASEp | Equiv. Yrs. |
|----------------------|-------|--------------------|-------|--------|------|-------------|
| 50-percent AEP flood | 18700 | ft ³ /s | 10100 | 34800 | 39.2 | 1.7 |
| 20-percent AEP flood | 27800 | ft ³ /s | 15000 | 51500 | 38.2 | 2.6 |
| 10-percent AEP flood | 34300 | ft ³ /s | 18200 | 64600 | 40.1 | 3.4 |
| 4-percent AEP flood | 42900 | ft ³ /s | 21900 | 83900 | 42.7 | 4.3 |
| 2-percent AEP flood | 49400 | ft ³ /s | 24400 | 100000 | 45.2 | 4.9 |

| Statistic | Value | Unit | PII | Plu | ASEp | Equiv. Yrs. |
|-----------------------|-------|--------------------|-------|--------|------|-------------|
| 1-percent AEP flood | 56500 | ft ³ /s | 26800 | 119000 | 47.9 | 5.3 |
| 0.2-percent AEP flood | 73400 | ft ³ /s | 31500 | 171000 | 55.2 | 5.8 |

Peak-Flow Statistics Citations

Law, G.S., and Tasker G.D., 2003, Flood-Frequency Prediction Methods for Unregulated Streams of Tennessee, 2000: U.S. Geological Survey Water-Resources Investigations Report 03-4176, 79p. (<http://pubs.usgs.gov/wri/wri034176/>)

➤ Low-Flow Statistics

Low-Flow Statistics Parameters [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

| Parameter Code | Parameter Name | Value | Units | Min Limit | Max Limit |
|----------------|--------------------------------------|--------|--------------------|-----------|-----------|
| DRNAREA | Drainage Area | 884.31 | square miles | 1.3 | 14441 |
| RECESS | Recession Index | 140 | days per log cycle | 32 | 175 |
| CLIMFAC2YR | Tennessee Climate Factor 2 Year | 2.178 | dimensionless | 2.056 | 2.46 |
| SOILPERM | Average Soil Permeability | 3.099 | inches per hour | 0.45 | 9.72 |
| PERMGTE2IN | Percent permeability gte 2 in per hr | 67.712 | percent | 2 | 100 |

Low-Flow Statistics Flow Report [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

PII: Prediction Interval-Lower, Plu: Prediction Interval-Upper, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

| Statistic | Value | Unit | ASEp |
|------------------------|-------|--------------------|------|
| 7 Day 10 Year Low Flow | 291 | ft ³ /s | 89 |
| 30 Day 5 Year Low Flow | 361 | ft ³ /s | 70.2 |

Low-Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009–5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

➤ Flow-Duration Statistics

Flow-Duration Statistics Parameters [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

| Parameter Code | Parameter Name | Value | Units | Min Limit | Max Limit |
|----------------|--------------------------------------|--------|--------------------|-----------|-----------|
| DRNAREA | Drainage Area | 884.31 | square miles | 1.3 | 14441 |
| RECESS | Recession Index | 140 | days per log cycle | 32 | 175 |
| CLIMFAC2YR | Tennessee Climate Factor 2 Year | 2.178 | dimensionless | 2.056 | 2.46 |
| SOILPERM | Average Soil Permeability | 3.099 | inches per hour | 0.45 | 9.72 |
| PERMGTE2IN | Percent permeability gte 2 in per hr | 67.712 | percent | 2 | 100 |

Flow-Duration Statistics Flow Report [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

PIl: Prediction Interval-Lower, Plu: Prediction Interval-Upper, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

| Statistic | Value | Unit | ASEp |
|-----------------------|-------|--------------------|------|
| 99.5 Percent Duration | 271 | ft ³ /s | 86.4 |
| 99 Percent Duration | 290 | ft ³ /s | 78 |
| 98 Percent Duration | 322 | ft ³ /s | 72.2 |
| 95 Percent Duration | 385 | ft ³ /s | 66.3 |
| 90 Percent Duration | 464 | ft ³ /s | 60.2 |
| 80 Percent Duration | 585 | ft ³ /s | 54 |
| 70 Percent Duration | 721 | ft ³ /s | 50.7 |
| 60 Percent Duration | 872 | ft ³ /s | 48.7 |
| 50 Percent Duration | 1070 | ft ³ /s | 42.9 |

| Statistic | Value | Unit | ASEp |
|---------------------|-------|--------------------|------|
| 40 Percent Duration | 1300 | ft ³ /s | 36.1 |
| 30 Percent Duration | 1580 | ft ³ /s | 28.3 |
| 20 Percent Duration | 1990 | ft ³ /s | 23.3 |
| 10 Percent Duration | 2940 | ft ³ /s | 20.8 |

Flow-Duration Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009–5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

➤ Annual Flow Statistics

Annual Flow Statistics Parameters [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

| Parameter Code | Parameter Name | Value | Units | Min Limit | Max Limit |
|----------------|---------------------------------|--------|-----------------|-----------|-----------|
| DRNAREA | Drainage Area | 884.31 | square miles | 1.3 | 14441 |
| CLIMFAC2YR | Tennessee Climate Factor 2 Year | 2.178 | dimensionless | 2.056 | 2.46 |
| SOILPERM | Average Soil Permeability | 3.099 | inches per hour | 0.45 | 9.72 |

Annual Flow Statistics Flow Report [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

PIl: Prediction Interval-Lower, Plu: Prediction Interval-Upper, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

| Statistic | Value | Unit | ASEp |
|------------------|-------|--------------------|------|
| Mean Annual Flow | 1430 | ft ³ /s | 25.6 |

Annual Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009–5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

➤ Seasonal Flow Statistics

Seasonal Flow Statistics Parameters [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

| Parameter Code | Parameter Name | Value | Units | Min Limit | Max Limit |
|----------------|---------------------------------|--------|--------------------|-----------|-----------|
| DRNAREA | Drainage Area | 884.31 | square miles | 1.3 | 14441 |
| RECESS | Recession Index | 140 | days per log cycle | 32 | 175 |
| CLIMFAC2YR | Tennessee Climate Factor 2 Year | 2.178 | dimensionless | 2.056 | 2.46 |
| SOILPERM | Average Soil Permeability | 3.099 | inches per hour | 0.45 | 9.72 |

Seasonal Flow Statistics Flow Report [100.0 Percent (884 square miles) Low Flow Central and East Regions 2009 5159]

PII: Prediction Interval-Lower, Plu: Prediction Interval-Upper, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

| Statistic | Value | Unit | ASEp |
|------------------|-------|--------------------|------|
| Summer Mean Flow | 1110 | ft ³ /s | 43.1 |

Seasonal Flow Statistics Citations

Law, G.S., Tasker, G.D., and Ladd, D.E., 2009, Streamflow-characteristic estimation methods for unregulated streams of Tennessee: U.S. Geological Survey Scientific Investigations Report 2009–5159, 212 p., 1 pl. (<http://pubs.usgs.gov/sir/2009/5159/>)

USGS Data Disclaimer: Unless otherwise stated, all data, metadata and related materials are considered to satisfy the quality standards relative to the purpose for which the data were collected. Although these data and associated metadata have been reviewed for accuracy and completeness and approved for release by the U.S. Geological Survey (USGS), no warranty expressed or implied is made regarding the display or utility of the data for other purposes, nor on all computer systems, nor shall the act of distribution constitute any such warranty.

USGS Software Disclaimer: This software has been approved for release by the U.S. Geological Survey (USGS). Although the software has been subjected to rigorous review, the USGS reserves the right to update the software as needed pursuant to further analysis and review. No warranty, expressed or implied, is made by the USGS or the U.S. Government as to the

functionality of the software and related material nor shall the fact of release constitute any such warranty. Furthermore, the software is released on condition that neither the USGS nor the U.S. Government shall be held liable for any damages resulting from its authorized or unauthorized use.

USGS Product Names Disclaimer: Any use of trade, firm, or product names is for descriptive purposes only and does not imply endorsement by the U.S. Government.

Application Version: 4.10.1

StreamStats Services Version: 1.2.22

NSS Services Version: 2.2.1

Ty Tucker

From: Ty Tucker
Sent: Monday, November 20, 2023 11:42 AM
To: Ty Tucker
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

From: Ted Kniazewycz <Ted.Kniazewycz@tn.gov>
Sent: Wednesday, November 8, 2023 9:36 AM
To: Emily Burgess <Emily.Burgess@tn.gov>
Cc: Ty Tucker <Ty.Tucker@tn.gov>
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

If you are raising the grade three feet, will these be below the new bridge such that they could be demolished in the second phase?



Ted A. Kniazewycz, P.E., F.ASCE | Director
Structures Division
p. 615-741-3351
c. 615-574-1220
ted.kniazewycz@tn.gov

From: Emily Burgess <Emily.Burgess@tn.gov>
Sent: Wednesday, November 8, 2023 9:34 AM
To: Ted Kniazewycz <Ted.Kniazewycz@tn.gov>
Cc: Ty Tucker <Ty.Tucker@tn.gov>
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

Ted,

It looks like there are a few piers that can't be phase constructed (see below). What are your thoughts on these?

ID#: 90S23860001
Job #: 90-SR353-00.45



Thanks,



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

From: Ted Kniazewycz <Ted.Kniazewycz@tn.gov>
Sent: Wednesday, November 8, 2023 9:14 AM
To: Emily Burgess <Emily.Burgess@tn.gov>
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

Emily –

Is the ADT too high to keep the alignment and do a single lane with a signal? There seems to be a lot of roadway work plus the bridge ends up skewed across the river.

Thanks,



Ted A. Kniazewycz, P.E., F.ASCE | Director
Structures Division
p. 615-741-3351
c. 615-574-1220
ted.kniazewycz@tn.gov

From: Emily Burgess <Emily.Burgess@tn.gov>

Sent: Tuesday, November 7, 2023 1:55 PM

To: K.Brandon Chance <K.Brandon.Chance@tn.gov>; Lisa Dunn <Lisa.Dunn@tn.gov>; TDOT MultimodalPlanning <TDOT.MultimodalPlanning@tn.gov>; Daniel Pallme <Daniel.Pallme@tn.gov>; Stacy Morrison <Stacy.Morrison@tn.gov>; Brian Hurst <Brian.Hurst@tn.gov>; Jay Lanius <Jay.Lanius@tn.gov>; Wesley Peck <Wesley.Peck@tn.gov>; TDOT.TrafficOps TSMO-Reviews <TDOT.TrafficOps.TSMO-Reviews@tn.gov>; TDOT ADA <TDOT.ADA@tn.gov>; Lori Fiorentino <Lori.Fiorentino@tn.gov>; Troy J. Ebbert <Troy.J.Ebbert@tn.gov>; Christie Brown <Christie.Brown@tn.gov>; Andrew Padgett <Andrew.Padgett@tn.gov>; TDOT R1.Traffic <TDOT.R1.Traffic@tn.gov>; Andrew Barlow <Andrew.Barlow@tn.gov>; Adam Price <Adam.Price@tn.gov>; Kathleen McLaughlin <Kathleen.McLaughlin@tn.gov>

Cc: Brian Egan <Brian.Egan@tn.gov>; Jamie Fitzpatrick <Jamie.Fitzpatrick@tn.gov>; Susannah Kniazewycz <Susannah.Kniazewycz@tn.gov>; Tammy Sellers <Tammy.Sellers@tn.gov>; Matt Meservy <Matt.Meservy@tn.gov>; James D. Kelley <James.D.Kelley@tn.gov>; Sharon Schutz <Sharon.Schutz@tn.gov>; Jeff Hoge <Jeff.Hoge@tn.gov>; Amy Rauch <Amy.Rauch@tn.gov>; Antonia Hayes <Antonia.Hayes@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Loren McWright <Loren.McWright@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>; Steve Allen <Steve.Allen@tn.gov>; Terry Gladden <Terry.Gladden@tn.gov>; Ted Kniazewycz <Ted.Kniazewycz@tn.gov>; Lee J. Smith <Lee.J.Smith@tn.gov>; Mickey Hamilton <Mickey.Hamilton@tn.gov>; Steve Borden <Steve.Borden@tn.gov>; Amanda Snowden <Amanda.Snowden@tn.gov>; Dexter Justis <Dexter.Justis@tn.gov>; Sheena A. Foster <Sheena.A.Foster@tn.gov>; Ty Tucker <Ty.Tucker@tn.gov>

Subject: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

All,

As a part of the Project Delivery Network (PDN) Stage OSD2 Draft Concept Report Review, please see attached pdf to access the draft report for your review. We would like all stage zero information provided back in addition to any comments on the report. Below is the project information as well as a Google Maps link to the project location:

- PIN 132623.00
- Washington County
- SR 353 Bridge over Nolichucky River
- Project Location: <https://maps.app.goo.gl/4AoW2xDo83T3xQhBA>
- Draft Report: Attached

We request that each division identified within the PDN process provide their comments or confirmation of no comments by **COB November 21st**.

Please feel free to reach out if you have any questions or issues accessing this report.

Thanks,



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

Ty Tucker

From: Emily Burgess
Sent: Wednesday, November 22, 2023 6:26 AM
To: Ty Tucker
Subject: FW: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

File please.




Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

From: C.David Lewis <C.David.Lewis@tn.gov>
Sent: Wednesday, November 22, 2023 5:28 AM
To: Emily Burgess <Emily.Burgess@tn.gov>
Cc: Adam Price <Adam.Price@tn.gov>; Ali Omar <Ali.Omar@tn.gov>
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

Emily,

Structures' comments are listed below:

1. Proposed travel lanes are planned to be 11ft. Typical lane widths for new generation bridges are 12ft. Please verify if proposed lanes should be kept 11ft.
2. Planned or assumed superstructure beam type is 33" (height) prestressed concrete box beams for 4 span bridge. Planned span lengths are about 95ft long with possibly 75 degree pier skew. This beam size (height) is structurally not feasible for 95-100 ft long spans. Minimum of 39" may handle such long spans. Or 5 span bridge may be structurally fine with 33" box beams.
3. Utility conflict at proposed beginning bridge location. See picture below:



4. Existing begin of bridge – Abutment footings are on very steep slope. Looking at plans, it looks like planned proposed abutment shall be parallel to existing abutment. I would suggest to bring proposed abutment (beginning of bridge) further back and have at least 4ft to 6 ft berm and have 2:1 slope rip-rap. This may increase the planned bridge length by at least 10ft to 15 ft. See picture below:



C. DAVID LEWIS, P.E. | Civil Engineering Manager 1

Structures Division

James K. Polk Building, Suite 1100

505 Deaderick Street, Nashville, TN 37243

p. 615-532-3815

c.david.lewis@tn.gov

tn.gov/tdot

From: Adam Price <Adam.Price@tn.gov>

Sent: Tuesday, November 7, 2023 3:56 PM

To: C.David Lewis <C.David.Lewis@tn.gov>

Subject: FW: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353



Adam Price, P.E. | Manager

Engineering Division – Structural Design Section

James K. Polk Building, Suite 1100

505 Deaderick Street, Nashville, TN 37243

p. 615-741-5390

adam.price@tn.gov

tn.gov/tdot



Take teamwork to the next level.

Right Work | Right Focus | Right Tool

From: Emily Burgess <Emily.Burgess@tn.gov>

Sent: Tuesday, November 7, 2023 1:55 PM

To: K.Brandon Chance <K.Brandon.Chance@tn.gov>; Lisa Dunn <Lisa.Dunn@tn.gov>; TDOT MultimodalPlanning <TDOT.MultimodalPlanning@tn.gov>; Daniel Pallme <Daniel.Pallme@tn.gov>; Stacy Morrison <Stacy.Morrison@tn.gov>; Brian Hurst <Brian.Hurst@tn.gov>; Jay Lanius <Jay.Lanius@tn.gov>; Wesley Peck <Wesley.Peck@tn.gov>; TDOT.TrafficOps TSMO-Reviews <TDOT.TrafficOps.TSMO-Reviews@tn.gov>; TDOT ADA <TDOT.ADA@tn.gov>; Lori Fiorentino <Lori.Fiorentino@tn.gov>; Troy J. Ebbert <Troy.J.Ebbert@tn.gov>; Christie Brown <Christie.Brown@tn.gov>; Andrew Padgett <Andrew.Padgett@tn.gov>; TDOT R1.Traffic <TDOT.R1.Traffic@tn.gov>; Andrew Barlow <Andrew.Barlow@tn.gov>; Adam Price <Adam.Price@tn.gov>; Kathleen McLaughlin <Kathleen.McLaughlin@tn.gov>

Cc: Brian Egan <Brian.Egan@tn.gov>; Jamie Fitzpatrick <Jamie.Fitzpatrick@tn.gov>; Susannah Kniazewycz <Susannah.Kniazewycz@tn.gov>; Tammy Sellers <Tammy.Sellers@tn.gov>; Matt Meservy <Matt.Meservy@tn.gov>; James D. Kelley <James.D.Kelley@tn.gov>; Sharon Schutz <Sharon.Schutz@tn.gov>; Jeff Hoge <Jeff.Hoge@tn.gov>; Amy Rauch <Amy.Rauch@tn.gov>; Antonia Hayes <Antonia.Hayes@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Loren McWright <Loren.McWright@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>; Steve Allen <Steve.Allen@tn.gov>;

Terry Gladden <Terry.Gladden@tn.gov>; Ted Kniazewycz <Ted.Kniazewycz@tn.gov>; Lee J. Smith <Lee.J.Smith@tn.gov>; Mickey Hamilton <Mickey.Hamilton@tn.gov>; Steve Borden <Steve.Borden@tn.gov>; Amanda Snowden <Amanda.Snowden@tn.gov>; Dexter Justis <Dexter.Justis@tn.gov>; Sheena A. Foster <Sheena.A.Foster@tn.gov>; Ty Tucker <Ty.Tucker@tn.gov>

Subject: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

All,

As a part of the Project Delivery Network (PDN) Stage OSD2 Draft Concept Report Review, please see attached pdf to access the draft report for your review. We would like all stage zero information provided back in addition to any comments on the report. Below is the project information as well as a Google Maps link to the project location:

- PIN 132623.00
- Washington County
- SR 353 Bridge over Nolichucky River
- Project Location: <https://maps.app.goo.gl/4AoW2xDo83T3xQhBA>
- Draft Report: Attached

We request that each division identified within the PDN process provide their comments or confirmation of no comments by **COB November 21st**.

Please feel free to reach out if you have any questions or issues accessing this report.

Thanks,



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

6.0 Traffic Analysis

**TENNESSEE DEPARTMENT OF TRANSPORTATION
STRATEGIC TRANSPORTATION INVESTMENTS DIVISION**

PROJECT NO.: 90S353-S0-002 ROUTE: S.R. 353
COUNTY: WASHINGTON CITY: _____
PROJECT PIN NUMBER: 132623.00
PROJECT DESCRIPTION: BRIDGE AND APPROACHES OVER THE NOLICHUCKY RIVER
@ L.M. 0.45.

DIVISION REQUESTING:

| | |
|---|--|
| MAINTENANCE <input type="checkbox"/> | PAVEMENT DESIGN <input type="checkbox"/> |
| S.T.I.D. <input checked="" type="checkbox"/> | STRUCTURES <input type="checkbox"/> |
| PROG. DEVELOPMENT & ADM. <input type="checkbox"/> | SURVEY & ROADWAY DESIGN <input type="checkbox"/> |
| PUBLIC TRANS. & AERO. <input type="checkbox"/> | TRAFFIC SIGNAL DESIGN <input type="checkbox"/> |
| | OTHER _____ <input type="checkbox"/> |

YEAR PROJECT PROGRAMMED FOR CONSTRUCTION: _____
PROJECTED LETTING DATE: _____

TRAFFIC ASSIGNMENT:

| BASE YEAR | | DESIGN YEAR | | | | | DESIGN ROADWAY % TRUCKS | | DESIGN AVERAGE DAILY LOADS | |
|-----------|------|-------------|-----|----|------|-----------|----------------------------|------|-------------------------------|-------|
| AADT | YEAR | AADT | DHV | % | YEAR | DIR.DIST. | DHV | AADT | FLEX | RIGID |
| 1,470 | 2028 | 1,880 | 207 | 11 | 2048 | 65-35 | 3 | 5 | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

REQUESTED BY: NAME KONNER SPRADLIN DATE 7/28/22
DIVISION S.T.I.D.
ADDRESS 1000 J. K. POLK BUILDING
NASHVILLE TN 37243

REVIEWED BY: RANDY BOGUSKIE *Randy Boguskie* DATE 7/29/2022
TRANSPORTATION MANAGER 1
SUITE 1000, JAMES K. POLK BUILDING

APPROVED BY: TONY ARMSTRONG *Tony Armstrong* DATE 7/29/2022
TRANSPORTATION MANAGER 2
SUITE 1000, JAMES K. POLK BUILDING

COMMENTS:

THIS TRAFFIC IS BASED ON 2021 CYCLE COUNTS. THE DESIGN YEAR TRAFFIC IS BASED ON GROWTH RATE FROM THE JOHNSON CITY MPO COMPUTER ASSIGNMENT MODEL. AADT's ARE INCLUDED.

Cc: MIKE GILBERT, S.T.I.D.

DHV'S ARE NOT REQUIRED FOR SIDE ROADS LESS THAN 1000 AADT.

NOTE: FOR BRIDGE REPLACEMENT PROJECTS, ADLs ARE NOT REQUIRED FOR ADTs OF 1000 OR LESS AND PERCENTAGE OF TRUCKS OF 7% OR LESS.

SEE ATTACHMENTS FOR TURNING MOVEMENTS AND/OR OTHER DETAILS.

(REV. 6/9/21)

Ty Tucker

From: TDOT.TrafficOps TSMO-Reviews
Sent: Monday, March 27, 2023 8:58 AM
To: Amy Rauch
Subject: RE: Call for Comments (OSD1) - Cocke and Washington County Bridges (PINs 124254.00, 124272.00, 124279.00, and 132623.00)

Follow Up Flag: Follow up
Flag Status: Flagged

No comments from TOD.

From: Amy Rauch <Amy.Rauch@tn.gov>
Sent: Wednesday, March 22, 2023 10:13 AM
To: K.Brandon Chance <K.Brandon.Chance@tn.gov>; TDOT.ENV SpecialProjects <TDOT.ENV.SpecialProjects@tn.gov>; Lisa Dunn <Lisa.Dunn@tn.gov>; TDOT MultimodalPlanning <TDOT.MultimodalPlanning@tn.gov>; Daniel Pallme <Daniel.Pallme@tn.gov>; Stacy Morrison <Stacy.Morrison@tn.gov>; Brian Hurst <Brian.Hurst@tn.gov>; Jay Lanius <Jay.Lanius@tn.gov>; Gregory Dyer <Greg.Dyer@tn.gov>; TDOT.TrafficOps TSMO-Reviews <TDOT.TrafficOps.TSMO-Reviews@tn.gov>; TDOT ADA <TDOT.ADA@tn.gov>; Lori Fiorentino <Lori.Fiorentino@tn.gov>; Troy J. Ebbert <Troy.J.Ebbert@tn.gov>; Christie Brown <Christie.Brown@tn.gov>; John Barrett <John.Barrett@tn.gov>; Michael W. Palmer <Michael.W.Palmer@tn.gov>; Andrew Padgett <Andrew.Padgett@tn.gov>; TDOT R1.Traffic <TDOT.R1.Traffic@tn.gov>
Cc: Brian Egan <Brian.Egan@tn.gov>; Susannah Kniazewycz <Susannah.Kniazewycz@tn.gov>; Tammy Sellers <Tammy.Sellers@tn.gov>; Matt Meservy <Matt.Meservy@tn.gov>; James D. Kelley <James.D.Kelley@tn.gov>; Sharon Schutz <Sharon.Schutz@tn.gov>; Jeff Hoge <Jeff.Hoge@tn.gov>; Amy Rauch <Amy.Rauch@tn.gov>; Antonia Hayes <Antonia.Hayes@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Loren McWright <Loren.McWright@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>; Steve Allen <Steve.Allen@tn.gov>; Terry Gladden <Terry.Gladden@tn.gov>; Ted Kniazewycz <Ted.Kniazewycz@tn.gov>; Wesley Peck <Wesley.Peck@tn.gov>; Lee J. Smith <Lee.J.Smith@tn.gov>; Steve Borden <Steve.Borden@tn.gov>; Amanda Snowden <Amanda.Snowden@tn.gov>; Dexter Justis <Dexter.Justis@tn.gov>; Sheena A. Foster <Sheena.A.Foster@tn.gov>; Jay Norris <Jay.Norris@tn.gov>; Jamie Fitzpatrick <Jamie.Fitzpatrick@tn.gov>
Subject: Call for Comments (OSD1) - Cocke and Washington County Bridges (PINs 124254.00, 124272.00, 124279.00, and 132623.00)

All,

As a part of the Project Delivery Network (PDN) Stage OSD1 Early Coordination process, please see the attached PDFs to access the site visit packet for early comments. The purpose of receiving comments is to have initial input compiled from the different functional areas prior to the site visit to identify areas of interests. The proposed improvements are subject to change based on feedback we receive. We will compile all the comments we receive and discuss at the site visit. Below is the project information as well as a Google Maps link to the project location:

| | | | | |
|-----------|-------|---------------------------|---------------------------|---|
| 124254.00 | Cocke | Chemwood Dr (0A055) | Bridge over Sinking Creek | https://www.google.com/maps/@33.2070674,322m/data=!3m1!1e3 |
| 124272.00 | Cocke | Caney Creek Rd (0A407) | Bridge over Cosby Creek | https://www.google.com/maps/@33.2398405,342m/data=!3m1!1e3 |
| 124279.00 | Cocke | Ball Park Rd | Bridge over Cosby Creek | https://www.google.com/maps/@33.2462273,450m/data=!3m1!1e3 |

| | | | | |
|-----------|------------|--------|---|---|
| 132623.00 | Washington | SR-353 | (Bailey Bridge Road), Bridge over Nolichucky River, LM 0.45 | https://www.google.com/maps/place/82.5905506,39.99m/data=!3m1!1e3 |
|-----------|------------|--------|---|---|

We request that each division identified within the PDN process provide their comments or confirmation of no comments by **COB Friday, April 7**. The site visit will be held on Wednesday, April 19, 2023 beginning at **9AM Eastern Time at the Washington County Project**. Attached is a calendar invite for the site visit as well if you choose to attend this site visit. Please feel free to reach out if you have any questions.



Amy Rauch, PE | C.E. Manager 1
 Strategic Transportation Investments Division
 James K. Polk Building, 10th Floor
 505 Deaderick St., Nashville, TN 37243
 p. 615-741-0969 c. 615-733-9008
Amy.Rauch@tn.gov
tn.gov/tdot
tn.gov/tdot/strategic-transportation-investments

Ty Tucker

From: Emily Burgess
Sent: Monday, November 13, 2023 9:04 AM
To: Ty Tucker
Subject: FW: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

Please file.



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

From: TDOT.TrafficOps TSMO-Reviews <TDOT.TrafficOps.TSMO-Reviews@tn.gov>
Sent: Thursday, November 9, 2023 9:26 AM
To: Emily Burgess <Emily.Burgess@tn.gov>
Subject: RE: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

No comments.



Michelle Nickerson, P.E., PTOE | Civil Engineering Manager 1
Traffic Operations Division/ Traffic Engineering Office
James K. Polk Bldg. 18th Floor
505 Deaderick St. Nashville, TN 37243
p. 615-741-0894
michelle.nickerson@tn.gov
tn.gov/tdot

From: Emily Burgess <Emily.Burgess@tn.gov>
Sent: Tuesday, November 7, 2023 1:55 PM
To: K.Brandon Chance <K.Brandon.Chance@tn.gov>; Lisa Dunn <Lisa.Dunn@tn.gov>; TDOT MultimodalPlanning <TDOT.MultimodalPlanning@tn.gov>; Daniel Pallme <Daniel.Pallme@tn.gov>; Stacy Morrison <Stacy.Morrison@tn.gov>; Brian Hurst <Brian.Hurst@tn.gov>; Jay Lanius <Jay.Lanius@tn.gov>; Wesley Peck <Wesley.Peck@tn.gov>; TDOT.TrafficOps TSMO-Reviews <TDOT.TrafficOps.TSMO-Reviews@tn.gov>; TDOT ADA <TDOT.ADA@tn.gov>; Lori Fiorentino <Lori.Fiorentino@tn.gov>; Troy J. Ebbert <Troy.J.Ebbert@tn.gov>; Christie Brown <Christie.Brown@tn.gov>; Andrew Padgett <Andrew.Padgett@tn.gov>; TDOT R1.Traffic <TDOT.R1.Traffic@tn.gov>; Andrew Barlow <Andrew.Barlow@tn.gov>; Adam Price <Adam.Price@tn.gov>; Kathleen McLaughlin <Kathleen.McLaughlin@tn.gov>
Cc: Brian Egan <Brian.Egan@tn.gov>; Jamie Fitzpatrick <Jamie.Fitzpatrick@tn.gov>; Susannah Kniazewycz <Susannah.Kniazewycz@tn.gov>; Tammy Sellers <Tammy.Sellers@tn.gov>; Matt Meservy <Matt.Meservy@tn.gov>; James D. Kelley <James.D.Kelley@tn.gov>; Sharon Schutz <Sharon.Schutz@tn.gov>; Jeff Hoge <Jeff.Hoge@tn.gov>; Amy

Rauch <Amy.Rauch@tn.gov>; Antonia Hayes <Antonia.Hayes@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Loren McWright <Loren.McWright@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>; Steve Allen <Steve.Allen@tn.gov>; Terry Gladden <Terry.Gladden@tn.gov>; Ted Kniazewycz <Ted.Kniazewycz@tn.gov>; Lee J. Smith <Lee.J.Smith@tn.gov>; Mickey Hamilton <Mickey.Hamilton@tn.gov>; Steve Borden <Steve.Borden@tn.gov>; Amanda Snowden <Amanda.Snowden@tn.gov>; Dexter Justis <Dexter.Justis@tn.gov>; Sheena A. Foster <Sheena.A.Foster@tn.gov>; Ty Tucker <Ty.Tucker@tn.gov>

Subject: Draft Report Review (OSD2) - PIN 132623.00 Washington County SR-353

All,

As a part of the Project Delivery Network (PDN) Stage OSD2 Draft Concept Report Review, please see attached pdf to access the draft report for your review. We would like all stage zero information provided back in addition to any comments on the report. Below is the project information as well as a Google Maps link to the project location:

- PIN 132623.00
- Washington County
- SR 353 Bridge over Nolichucky River
- Project Location: <https://maps.app.goo.gl/4AoW2xDo83T3xQhBA>
- Draft Report: Attached

We request that each division identified within the PDN process provide their comments or confirmation of no comments by **COB November 21st**.

Please feel free to reach out if you have any questions or issues accessing this report.

Thanks,



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>



Emily Burgess, P.E. | Transportation Project Specialist, Senior
Strategic Transportation Investments Division
James. K. Polk Building, 10th Floor
505 Deaderick Street, Nashville, TN 37243
p. 615-253-4490
emily.burgess@tn.gov
tn.gov/tdot
<https://www.tn.gov/tdot/strategic-transportation-investments.html>

7.0 Additional Comments

Project: New Bridge over Nolichucky River
Comment Resolution Form
County: Washington
PIN 132623.00

| Comment Stage | Division | Commenter | Date Received | Comment | Comment Addressed? | Additional Notes |
|------------------------------------|---------------------|------------|---------------|---|--------------------|--|
| Early Coordination (OSD1) | Project Development | Jay Morgan | 4/6/2023 | According to ETRIMS and ETRIMS image viewer, the existing speed limit is 45 mph. | ✓ | Updated report to reflect, 35 mph speed came from 2013 Google Earth imagery |
| Early Coordination Comments (OSD1) | Project Development | Jay Morgan | 4/6/2023 | It looks like this sign fell down. I did find it on the 2021 image viewer in ETRIMS. There was both a 12T and 21T weight limit | ✓ | Updated report to reflect |
| Early Coordination Comments (OSD1) | Project Development | Jay Morgan | 4/6/2023 | This is correct according to RD11-TS-2, but shouldn't we at least design it to the posted speed? However, if we go above 40 mph, then we no longer can use the curved parapet on S-CPW-1 making it harder to tie in the side roads. | ✓ | Updated report to reflect, 50 mph design speed with posted 45 mph. To use 50 mph design speed. |
| Early Coordination Comments (OSD1) | Environmental | Mike Cook | 4/10/2023 | This project is in Washington County which is in attainment for all regulated criteria pollutants. Therefore, conformity does not apply to this project. | ✓ | Noted in report |
| Early Coordination Comments (OSD1) | Environmental | Mike Cook | 4/10/2023 | This project qualifies as a categorical exclusion under 23 CFR 771.1 | ✓ | Noted in report |
| Early Coordination Comments (OSD1) | Environmental | Mike Cook | 4/10/2023 | The new bridge will be located southeast of the existing structure. However, the relocation will not halve the distance between the center of the near travel lane and an adjacent noise-sensitive land use. Therefore, the project is Type III in accordance with the FHWA noise regulation in 23 CFR 772 and TDOT's noise policy and a noise study is not needed. | ✓ | Noted in report |
| Early Coordination Comments (OSD1) | Environmental | Mike Cook | 4/10/2023 | There is one perennial stream within project limits. There are several cliff swallow nests on existing bridge. There are 10 endangered/threatened species within 4 miles of project. | ✓ | Noted in report |

| Comment Stage | Division | Commenter | Date Received | Comment | Comment Addressed? | Additional Notes |
|------------------------------------|---------------|-------------------|---------------|---|--------------------|---|
| Early Coordination Comments (OSD1) | Environmental | Kyle Kirschenmann | 4/10/2023 | No known hazardous materials sites impact this bridge replacement as shown in the TIR. An Asbestos Containing Material (ACM) survey was completed on Bridge No. 90S23860001 SR-353 over Nolichucky River LM 0.45 (90-SR353-00.45). The bridge has asbestos in 116 deck drains at 6% chrysotile and 4% crocidolite, and 2000 square feet of bearing pads at 20% chrysotile. Please see the report for further details and photographs. The State of Tennessee asbestos accreditation requirements (TDEC Rules Chapter 1200-01-20) mandates that ACM abatement work be performed by an accredited firm (contractor) using accredited abatement workers and supervisors. Abatement of this material shall be accomplished per SP202ACM Special Provision Regarding Removal of Asbestos-Containing Materials. ACM abatement should be completed prior to any demolition activities if possible. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Sections 107.08.D and 202.03). | ✓ | Noted in report |
| Early Coordination Comments (OSD1) | Multimodal | Will Rogers III | 3/30/2023 | At this 35 mph speed on the bridge, 6' shoulders as written will accommodate cyclists. It will not accommodate pedestrians. This is not a state bike route, but cyclist volume is high along this bridge. On both sides, 5' sidewalks with curb and gutter are requested. | ✓ | Sidewalks add 28% to cost estimate so will not be provided. |
| Early Coordination Comments (OSD1) | Environmental | Rachel Head | 4/11/2023 | It is not indicated whether ROW acquisition or permanent easements will be required on this project. The addition of ROW and/or permanent acquisitions could alter NEPA's concerns. Currently, this project is showing state-only funding in PPRM. Therefore, Section 4(f) is not applicable. Based on a visual inspection of the project location through Google Earth and Google Maps, it does not appear that any know Section 4(f)resources are adjacent to the project site. A desktop search of LWCF-funded projects in Washington County shows no projects close to the project location. . A desktop search of FEMA floodplains in the area confirmed that the bridge project spans a 100-year floodplain (Zone A). Please see the attached National Flood Hazard Layer FIRM map for confirmation. | ✓ | Noted in report |

| Comment Stage | Division | Commenter | Date Received | Comment | Comment Addressed? | Additional Notes |
|------------------------------------|--|-----------------------------|---------------|---|--------------------|--|
| Early Coordination Comments (OSD1) | Long Range Planning | Troy Ebbert | 3/24/2023 | The Washington county project at Baileys Bridge has a TWRA canoe launch near the bridge. I believe it is on the south west quadrant | ✓ | Noted in report |
| Site Visit Coordination (OSD2) | Environmental | Brittney Hensley | 4/19/2023 | Nolichucky is used for rafting, find out who to contact for water recreation | ✓ | Noted rafting in report, coordination will be required |
| Draft Report Review (OSD2) | Construction | Jamie Fitzpatrick | 11/17/2023 | HQ Construction has no comments at this time | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Materials & Tests Division/Geotechnical Division | Ann Walters | 11/13/2023 | There is no risk for Acid Producing Material in the area. My biggest comment would be regarding the new foundations adjacent to old ones. If the new piers can be spaced so they do not impact old foundations it will make construction much easier. | ✓ | New piers are not in the location of existing |
| Draft Report Review (OSD2) | Environment & Planning Bureau | Lisa Dunn | 11/7/2023 | I have no comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Structures | Ted Kniazewycz | 11/8/2023 | Is the ADT too high to keep the alignment and do a single lane with a signal? There seems to be a lot of roadway work plus the bridge ends up skewed across the river. | ✓ | Put bridge back on existing alignment to reduce scope and existing bridge will no longer be able to remain |
| Draft Report Review (OSD2) | Traffic Ops | Michelle Nickerson | 11/9/2023 | No comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Long Range Planning | Troy Ebbert | 11/9/2023 | Long-range Planning cannot locate any plans for this area that will affect the project. I am familiar with the area and have shared a few details(not the entire project) with TWRA and the State Park in the area referring them to you for comments. The old roadbed we would normally remove could be utilized as a road to a new river access potentially if TWRA is interested. | ✓ | Put bridge back on existing alignment to reduce scope and existing bridge will no longer be able to remain |
| Draft Report Review (OSD2) | David Crockett Birthplace State Park, TWRA | Joe Nowotarski, Tommy Woods | 11/10/2023 | Tennessee State Parks and David Crockett Birthplace State Park is definitely interested in this opportunity. It is in our management plan to increase public access to the Nolichucky River and an access point at Bailey Bridge would be crucially important. Bailey Bridge is ~10 miles upriver from the park. | ✓ | Put bridge back on existing alignment to reduce scope and existing bridge will no longer be able to remain |
| Draft Report Review (OSD2) | TWRA | Jam Habera | 11/9/2023 | TWRA is very much interested in a new access point on the Nolichucky River through TDOT's Bailey Bridge replacement. It would provide an excellent starting point for a float trip to the Davy Crockett Birthplace State Park access about 8.7 miles downstream. | ✓ | Put bridge back on existing alignment to reduce scope and existing bridge will no longer be able to remain |

| Comment Stage | Division | Commenter | Date Received | Comment | Comment Addressed? | Additional Notes |
|----------------------------|-------------------------------|--------------------|---------------|--|--------------------|--|
| Draft Report Review (OSD2) | Structures | C. David Lewis | 11/22/2023 | Proposed travel lanes are planned to be 11ft. Typical lane widths for new generation bridges are 12ft. Please verify if proposed lanes should be kept 11ft. | ✓ | Based on Table II on RD11-TS-2, 11 ft lanes are proposed for ADT from 1500-2000. The table for minimum clear width roadway widths and design loadings for new and reconstructed bridges states the minimum clear roadway width of bridges is traveled way + 8 ft. Will retain 11 ft lanes. |
| Draft Report Review (OSD2) | Structures | C. David Lewis | 11/22/2023 | Planned or assumed superstructure beam type is 33" (height) prestressed concrete box beams for 4 span bridge. Planned span lengths are about 95ft long with possibly 75 degree pier skew. This beam size (height) is structurally not feasible for 95-100 ft long spans. Minimum of 39" may handle such long spans. Or 5 span bridge may be structurally fine with 33" box beams. | ✓ | Made box beams 39", did not affect the amount of grade to be raised |
| Draft Report Review (OSD2) | Structures | C. David Lewis | 11/22/2023 | Utility conflict at proposed beginning bridge location. See picture below: | ✓ | Accounted for this in the cost estimate |
| Draft Report Review (OSD2) | Structures | C. David Lewis | 11/22/2023 | Existing begin of bridge – Abutment footings are on very steep slope. Looking at plans, it looks like planned proposed abutment shall be parallel to existing abutment. I would suggest to bring proposed abutment (beginning of bridge) further back and have at least 4ft to 6 ft berm and have 2:1 slope rip-rap. This may increase the planned bridge length by at least 10ft to 15 ft. See picture below: | ✓ | Moved beginnng of bridge to where it is offset from existing and was able to make slope 2:1. Did not have to increase bridge length. |
| Draft Report Review (OSD2) | Washington County | Richard Thompson | 11/20/2023 | No comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Environment & Planning Bureau | Lisa Dunn | 11/29/2023 | I have no comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Structures | Ted Kniazewycz | 11/29/2023 | No comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Traffic Ops | Bryan Bartnik | 12/7/2023 | No comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Traffic Ops | Michelle Nickerson | 12/8/2023 | No comments | ✓ | Nothing to note |
| Draft Report Review (OSD2) | Multimodal | Masonya Osei | 12/12/2023 | No comments | ✓ | Nothing to note |