Concept Report Form

The Concept Report Form develops an initial project vision, basis of design and report (e.g., the Concept Report) to transition into the subsequent design stages (Stages 1 through 4 in the Project Delivery Network [PDN]). This form summarizes all project components using information to complete the Concept Report.

			General I	Proj	ect Informa	tion				
Project Name	Shellmound	Rd (L.R. 02	l 61) - Bridge	over	Interstate 24 Ea	stbound				
PIN	130902.00									
Route	Route NHS (Y/N)		Fund	Functional Class			City		County	
Information	L.R. 02161	No	Rural	Mino	r Collector				Mario	on
Project Information	Begin Lo Mile	g End Mi	- 441	OT¹	Design Hour Vol. (DHV) ¹	Truck % ¹	Design Speed (MPH)	Posted Speed (MPH)	Base Year	Design Year
	1.29	1.4	0 1,93	30	232	2.00	40	30	2026	2046
Project Description & Standard Drawings Used	A field review was held for the above-mentioned project on August 3, 2021. The proposed structure is a 154' long, single span BT-72 Concrete Bulb-T Beam bridge with an out-to-out width of 33' 3". The typical section consists of 2-11' wide lanes each with a 5' wide shoulder. The proposed finished grade of the bridge will need to be raised approximately 4' and will provide a minimum clearance of seventeen 17' under the bridge. A 7.8 mile detour will be established while the proposed bridge is completed.									
Important Project History or Related Projects	The replacement of the I-24 WB Bridge over Shellmound Road (Pin# 130900.00) located 0.25 miles north of the proposed Shellmound RD Bridge over I-24 EB replacement will need to be considered when scheduling construction. The existing bridge is a 3 span concrete deck girder bridge crossing over I-24 EB at L.M. 22.78. The existing structure has an out-to-out width of 34' 6". The overall structure length is 139' 6". The current load limit for this structure is 20 tons. Marion County Highway Department is planning to resurface Shellmound Rd in 2023.								Project Details	
Project Purpose/Need	The need to replace this bridge is due to the present condition of the existing bridge: - Built in 1965. - Sufficiency rating is 54.2 (FAIR) – July 21, 2020 - Typical section does not meet current TDOT standards.								Proj	
Major Environmental Considerations	There are n	o major env	ironmental c	consic	derations.					

Multi-Modal Considerations	- Five (5) feet Paved Shoulder Width to accommodate bicycle traffic - Forty-two (42) inch bridge rail TDOT Multimodal Project Scoping Manual, Roadway Design Guidelines, MM-TS-1, MM-BPR-1					
Major Project Risks	Utilities: Distribution lines, communications cable					
Concent	Total Current Project Cost	Construction Year Estimate	> 10			
Concept Estimate and	\$ 3,210,000	\$ 4,100,000	Preliminary Estimates			
Timeline	Proposed Construction Year	Estimated Construction Duration	relin			
Illiellie	2027	TBD	P			

¹ Traffic numbers reflect identified design year

<u>Approv</u>	<u>vals</u>
Executed for approval of this Concept Report	
Steve Allen (Nov 18, 2022 05:19 CST)	Nov 18, 2022
STID Director	Date
The following individuals to execute if a bridge concept report:	
APPROVED By Ted A. Kniazewycz at 6:08 pm, Nov 19, 2022	11/19/2022
Structures Director	Date
Alch	12/12/2022
Regional Project Development Director	Date
Me	Feb 7, 2023
Bureau Chief of Engineering	Date
RESTON J ELLIOTT Digitally signed by PRESTON J ELLIOTT Date: 2022.12.12 12:48:07 -06'00'	12/12/2022
Bureau Chief of Environment and Planning	Date

Action Checklist							
0SD1 Initiate Concept Report and Request Funding							
Complete	NA		Date Completed				
	✓	Request and Finalize Safety Data					
✓		Request Project Number, PIN, and Task Profile Numbers	10/02/2020				
	✓	Coordinate with Long Range Planning					
✓		Request and Finalize Traffic Data	04/26/2021				
	✓	Request Preliminary Survey Data					
✓		Initiate Division Reviews	11/29/2021				
✓		Schedule Site Review (with appropriate Divisions)	07/09/2021				
0EN1 Con	duct	Environmental Desktop Review					
Complete	NA		Date Completed				
✓		Confirm Environmental Desktop Review is Complete	01/06/2022				
0MM1 Co	nduc	t Multimodal Review					
Complete	NA		Date Completed				
✓		Confirm Multimodal Review is Complete	09/27/2022				
✓		Review Multimodal Considerations & Recommendations	09/27/2022				
0TO1 Con	duct	Initial Traffic Ops/TSMO Review (include HQ Traffic Ops and Regional Traffic Office)					
Complete	NA		Date Completed				
✓		Confirm Transportation Systems Management & Operations (TSMO) Alignment & Operations Review is Complete	09/27/2022				
	✓	Request Concept Report Review					
0ST1 Dev	elop	Structures Recommendations					
Complete	NA		Date Completed				
✓		Confirm Recommended Structure Type for Concept Report is Complete	03/31/2022				
✓		Confirm Hydraulic Recommendations for Concept Report is Complete	04/06/2021				
OSY1 Prov	vide I	Preliminary Survey Data					
Complete	NA		Date Completed				
	✓	Confirm Control Ground Survey Set					
	✓	Review Preliminary Survey Data					
	✓	Determine Time to Complete the Aerial Survey					
0GT1 Conduct Preliminary Geotechnical Assessment							
Complete	NA		Date Completed				
	✓	Confirm Geotechnical Division Review is Complete					
0RD1 Pro	vide	Roadway Desktop Review	<u> </u>				
Complete	NA		Date Completed				
	✓	Confirm Roadway Division Review is Complete					

Action Checklist						
0SD2 Dev	elop	Draft Concept Report				
Complete	NA		Date Completed			
	✓	Conduct Intersection and Interchange Evaluation (IIE)				
	✓	Complete Conceptual Signal Warrants				
✓		Develop Draft Conceptual Layouts/Crash Figures for Site Visit	07/06/2021			
	✓	Compile Initial Divisional Reviews for Site Visit				
✓		Prepare & Send Site Visit Packet	07/09/2021			
✓		Lead Site Visit	08/03/2021			
	✓	Initiate Interstate Access Requests (IAR) Concept Coordination with FHWA (if applicable)				
✓		Develop, Compile, and Distribute the Draft Concept Report	11/03/2021			
0TO2 Dev	elop	TSMO Scope Items (include HQ Traffic Ops and Regional Traffic Office)				
Complete	NA		Date Completed			
	✓	Confirm Signal Warrants Analysis is Complete				
	✓	Confirm Lighting Warrants Analysis is Complete				
	✓	Review and Confirm TSMO & ITS Scope and Budget				
0RW1 Cor	nplet	te Preliminary Right-of-Way Estimates				
Complete	NA		Date Completed			
✓		Review and Confirm Preliminary Right-of-Way Cost Estimates	11/03/2021			
0UT1 Con	plet	e Utility Preliminary Estimates				
Complete	NA		Date Completed			
✓		Review and Confirm Preliminary Utility Estimate	11/03/2021			
	✓	Review and Confirm Preliminary Railroad Cost Estimate				
0SD3 Fina	lize (Concept Report				
Complete	NA		Date Completed			
	✓	Compile and Review Initial Risk Assessment				
✓		Finalize Conceptual Layouts	09/27/2022			
✓		Develop Environmental Technical Study Area (ETSA)	09/27/2022			
✓		Address Comments and Finalize Concept Report	09/29/2022			
	✓	Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable)				
	✓	Develop Roadway Safety Audit (RSA) No Plans Document				
✓		Submit the final Concept Report for Review and Signatures (as needed; see 0SD3 for additional information)	09/29/2022			
	✓	Finalize Document and Upload All Needed Electronic Files				
	✓	Notify the Project Management Director or Assigned Project Manager to Set Up Project (1PM1)				

NA Justification

- Conduct Intersection and Interchange Evaluation (IIE) No interchange within the limits of the project
- Complete Conceptual Signal Warrants Signal warrants not needed for the low AADT
- Initiate Interstate Access Requests (IAR) Concept Coordination with FHWA (if applicable) Not applicable
- Confirm Signal Warrants Analysis is Complete AADT too low for signal warrant
- Review and Confirm TSMO & ITS Scope and Budget No ITS within project limits
- Review and Confirm Preliminary Railroad Cost Estimate No railway within project limits
- Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable) Not applicable

PIN: 130902.00

- Develop Roadway Safety Audit (RSA) No Plans Document - RSA outside the scope of this BTIR


Concept Report		
Table of Contents/Attachments	Included	NA
One-Page Summary (with project location map)	√ √	IVA
Conceptual Layout(s) and Cross Section	✓	
Environmental Technical Study Area (ETSA) Layout	✓	
Concept Cost Estimate (Construction Year Estimate)	✓	
TSMO & ITS Scope and Budget ¹		√
ROW Form 44-A ¹		1
Crash Packet ¹		✓
Crash Prediction Analysis ¹		✓
Site Visit Attendee List	✓	
Environmental Desktop Review Form ¹	✓	
Multimodal Considerations & Recommendations ¹	✓	
Existing Structure Summary ¹	✓	
Email or memo containing Structure Type Recommendations ¹		✓
Email or memo containing Hydraulic Recommendations ¹		✓
Hydraulic Data		✓
Intersection and Interchange Evaluation (IIE) Analysis and Summary Form		✓
Traffic Analysis Summary/Tables	✓	
Forecasted Traffic Sheets ¹	✓	
Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output) ¹		✓
Signal Warrant ¹		✓
Lighting Warrant ¹		✓
Initial Risk Assessment using the Risk Assessment Form		✓
Final Interstate Access Request (IAR) Document and Memo with Letter from STID Director		✓
Road Safety Audit (RSA) No Plans ¹		✓


NA Justification


- TSMO & ITS Scope and Budget* No ITS at site
- Crash Packet* -Crash packets are not typically provided for Bridge replacements
- Intersection and Interchange Evaluation (IIE) Analysis and Summary Form No intersection or interchange
- Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output)* AADT too low to model


- Signal Warrant* No intersection to signal warrant
- Road Safety Audit (RSA) No Plans* RSA outside the scope of this BTIR


^{*} External document to STID















CROSS-SECTION DETAIL

MARION COUNTY - SHELLMOUND ROAD (02161) BRIDGE OVER I-24 EB @ L.M. 1.36 BRIDGE ID: 58I00240039



BRIDGE SECTIONS MARION COUNTY - SHELLMOUND ROAD (02161) BRIDGE OVER I-24 EB @ L.M. 1.36 BRIDGE ID: 58I00240039

BRIDGE TRANSPORTATION INVESTMENT REPORT (TIR) LR 02161 (SHELLMOUND RD)

LM 1.36

LOCATION								
Bridge #:	58100240039	Feature Crossed:	I-24 EB					
Road Name:	Shellmound Rd	Log mile:	1.36					
Route ID:	02161	System:	State Highway Agency					
City:		Functional Class:	Rural Minor Collector					
County:	Marion							
PIN:	130902.00							

	ROADWAY		
	Existing	Proposed (Preliminary Design Estimate)	
Design Standard		RD11-TS-2	
Route Characteristics			
AADT:	1,750	1,930	
AADT Year:	2026	2046	
Terrain:	Rolling	Rolling	
No. Lanes:	2	2	
Speed(Posted):	30	30	
Speed (Design):		40	
Approach Character.			
Lane Width (ft):	10	11	
Shoulder Width (ft):	2	5	
ROW Width (ft):	60	60	
ROW Tracts Affected		0	
ROW Required (acre)		0	
Cross Section Width (ft):	20/24/60	22/30/60	
Northern Approach Length (ft)		230'	
Southern Approach Length (ft):		310'	
Alignment:	Centerline	Maintain Centerline	
Grade:	N/A	Raise Approximately 4.3'	
Surface Material:	Asphalt Concrete	Asphalt Concrete	
App. Lower Than Structure	NO	NO	
Utilities (list)	transmission and communications utili	tes alongside road will need to be relocated	
Comments		I-24 EB use RD11-TS-5A	

	STRUCTURE	
	Existing	Proposed (Preliminary Design Estimate)
Bridge Characteristics		
Year Built	1965	
Load Limit	16 tons	
Sufficiency Rating	54.2 (FAIR)	
Skew	58	58
Structure Type	Concete Tee Beam	Concrete Prestressed Bulb-T Beam
Structures in Channel	NO	NO
Length (ft)	139' 6"	154'
No. Spans (App./Main)	3 main	1 main
Width (curb to curb) (ft)	28'	30'
Width (o to o) (ft)	34' 6"	31' 3"
Sidewalks on Structure	NO	NO
Superstructure Depth (in)	61" / 85"	124"
Girder Depth (in)	24" / 48"	72"
Finish Grade-Low Girder (in)	31" / 55"	82"
Bridge Rail Type	Concrete parapet	Concrete Wall
Bridge Rail Height (ft)	30"	42"
Indication Overtopping	NO	
Local Scour	NO	
Obstructions	NO	
Other Structures	Use BT	-72 for single span
Comments	Minimum Clearance of ex	kisting located at 24" beam thickness

BRIDGE TRANSPORTATION INVESTMENT REPORT (TIR) LR 02161 (SHELLMOUND RD)

	LM 1.36					
MAINTENANCE OF TRAFFIC						
Method of Maintaining Traffic	close road					
Description	Close Bridge and Detour 7.8 miles on TVA Road, U.S. 64 and U.S. 41					
Comments	TVA Road will need to be striped and signed for detour.					

COST ESTIMATE SUMMARY

LR 02161 Route:

Termini: Shellmound Rd, Bridge over I-24 Eastbound

Scope of Work:

Project Type of Work: **Bridge Replacement**

Concept

County: Marion Length: 0.23 Miles Date: October 4, 2022 Estimate Type:



DESCRIPTION	LOCAL	STATE	FEDERAL	TOTAL					
DESCRIPTION	0%	0%	0%						
Construction Items									
Removal Items	\$0	\$0	\$0	\$45,100					
Asphalt Paving	\$0	\$0	\$0	\$389,000					
Concrete Pavement	\$0	\$0	\$0	\$0					
Drainage	\$0	\$0	\$0	\$15,100					
Appurtenances	\$0	\$0	\$0	\$0					
Structures	\$0	\$0	\$0	\$1,010,000					
Fencing	\$0	\$0	\$0	\$0					
Signalization & Lighting	\$0	\$0	\$0	\$0					
Railroad Crossing	\$0	\$0	\$0	\$0					
Earthwork	\$0	\$0	\$0	\$194,000					
Clearing and Grubbing	\$0	\$0	\$0	\$0					
Seeding & Sodding	\$0	\$0	\$0	\$2,700					
Rip-Rap or Slope Protection	\$0	\$0	\$0	\$31,900					
Guardrail	\$0	\$0	\$0	\$38,400					
Signing	\$0	\$0	\$0	\$1,700					
Pavement Markings	\$0	\$0	\$0	\$21,900					
Maintenance of Traffic	\$0	\$0	\$0	\$75,500					
Mobilization 5%	\$0	\$0	\$0	\$91,300					
Other Items and Annual Inflation 10%	\$0	\$0	\$0	\$192,000					
Const. Contingency (Structures Not Included) 30%	\$0	\$0	\$0	\$330,000					
Const. Eng. & Inspec. 10%	\$0	\$0	\$0	\$244,000					
Construction Estimate	\$0	\$0	\$0	\$2,680,000					
Interchanges & Unique Intersections									
Roundabouts	\$0	\$0	\$0	\$0					
Interchanges	\$0	\$0	\$0	\$0					
Right-of-Way & Utilties	LOCAL	STATE	FEDERAL	TOTAL					
	0%	0%	0%						
Right-of-Way	\$0	\$0	\$0	\$0					
Utilities	\$0	\$0	\$0	\$260,000					
Preliminary Engineering	LOCAL 0%	STATE 0%	FEDERAL 0%	TOTAL					
Prelim. Eng. 10.0%	\$0	\$0	\$0	\$268,000					
Total Project Cost (2022)	\$ -	\$ -	\$ -	\$ 3,210,000					

PAY ITEM SUMMARY

TDOT PAY ITEM	TDOT DESCRIPTION	UNIT	TOOL QUANTITIES	ADDITIONAL QUANTITIES	TOOL QUANTITIES + ADDITIONAL QUANTITIES	Statewide UNIT COST	TOTAL COST < Unit Cost Trends with Quantities
Pavment Removal 202-03.01	REMOVAL OF ASPHALT PAVEMENT	SY	3919		3919	\$ 11.50	\$ 45,068.17
					PAVEMENT REMO	OVAL TOTAL (ROUNDED)	\$ 45,100
Asphalt Roads							
303-01 307-(01, 02, 03).01	MINERAL AGGREGATE, TYPE A BASE, GRADING D ASPHALT CONCRETE MIX (All Grades) (BPMB-HM) GRADING A	TON TON	2770 1419		2770 1419	\$ 33.59 \$ 96.50	\$ 93,062.03 \$ 136,976.49
307-01.(20 & 21 & 22)	AGGREGATE (BPMB-HM) GRADING A-S MIX	TON	414		414	\$ 86.50	\$ 35,795.14
307-(01 & 02 & 03).08 402-01	ASPHALT CONCRETE MIX (ALL GRADES) (BPMB-HM) GRADING B-M2 BITUMINOUS MATERIAL FOR PRIME COAT (PC)	TON	492 6		492 6		\$ 67,763.87 \$ 4,871.47
402-02 403-01	AGGREGATE FOR COVER MATERIAL (PC) BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	22 4		22 4		\$ 1,525.92 \$ 2,863.32
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	TON	17		17	\$ 147.40	\$ 2,509.89
411-(01 & 02 & 03).10	ACS MIX(ALL GRADES) GRADING D	TON	298		298 PA\	\$ 147.76 VING TOTAL (ROUNDED)	\$ 43,987.41 \$ 389,400
Concrete Roads				CONCRETI		/AYS TOTAL (ROUNDED)	\$ -
Drainage							
607-05.02 611-07.01	24" CONCRETE PIPE CULVERT (CLASS III) CLASS A CONCRETE (PIPE ENDWALLS)	LF CY	66 3		66 3	\$ 100.62 \$ 1,425.66	\$ 6,661.31 \$ 4,131.57
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	LB	275		275	\$ 3.12	\$ 858.85
710-02	Aggregate Underdrains (with pipe)	LF	475		475 DRAIN	\$ 7.10 IAGE TOTAL (ROUNDED)	\$ 3,372.55 \$ 15,100
Appurtenances				ROADWAY AND PA	VEMENT APPURTENAN	NCES TOTAL (ROUNDED)	\$ -
Earthwork & Mineral							
105-01 203-01	CONSTRUCTION STAKES, LINES AND GRADES ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	LS CY	1 8015		1 8015	\$ 31,120.89 \$ 15.45	\$ 31,120.89 \$ 123,829.74
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	TON	378		378	\$ 32.33	\$ 12,225.97
203-03	BORROW EXCAVATION (UNCLASSIFIED)	CY	1800		1800 EARTHWORK & MINE	\$ 14.91 ERAL TOTAL (ROUNDED)	\$ 26,845.32 \$ 194,100
Characterist .							
Structures N/A	Removal of Bridge	SF	4468		4468	\$ 20.00	\$ 89,355.00
N/A	New Bridge (Concrete Girder):	SF	5121		5121 STRUCTI	\$ 180.00 JRES TOTAL (ROUNDED)	\$ 921,690.00 \$ 1,011,100
Interchanges and Unique Intersections Lighting & Signalization						ONS TOTAL (ROUNDED)	\$ -
Guardrail 705-01.01	GUARDRAIL AT BRIDGE ENDS	LF	100	u	GHTING & SIGNALIZAT	FION TOTAL (ROUNDED) \$ 66.52	\$ 6,651.84
705-06.01	W Beam GR (Type 2) Mash TL3	LF	143	1132	1275	\$ 20.07	\$ 25,589.25
705-04.05 705-06.20	GUARDRAIL TERMINAL (TYPE-IN-LINE) Tangent Energy Absorbing Term Mash TL-3	EA EA	5	3 -4	3		\$ 1,771.11 \$ 2,626.00
706-06.03	RADIUS RAIL	LF		75	75	\$ 21.47	\$ 1,610.25
706-10.26	ROUNDED END ELEMENT	EA	_	3		\$ 42.68 RAIL TOTAL (ROUNDED)	\$ 128.04 \$ 38,400
Seeding and Sodding							
801-01		UNIT	45		45		\$ 1,239.07
801-01.07 801-02		UNIT	34 34		34 34		\$ 760.56 \$ 603.40
Maintenace of Traffic	Traffic Control	LS	1		SODE	DING TOTAL (ROUNDED)	\$ 2,700
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	LF	61		61	\$ 30.18	\$ 1,832.53
					VIAINTENANCE OF TRA	AFFIC TOTAL (ROUNDED)	\$ 75,500
Signs Not Listed	Signs (Construction)	LS	1		1 SIGN	\$ - NING TOTAL (ROUNDED)	\$ 1,700 \$ 1,700
Pavement Markings 716-13.07	Spray Thermo P.M. (40 mil 6")	LM		17.7	17.6838	\$ 1,237.50	\$ 21,883.70
/10-13.0/	Spray Thermo P.W. (40 Mil 6")	LIVI		1/./		ings total (rounded)	\$ 21,883.70
Fencing					FEN	CE TOTAL (ROUNDED)	\$ -
Rip-Rap 709-05.05	Machined Rip-Rap (Class A-3)	TON	800		800	\$ 39.85	\$ 31,880.00
Clearing and Grubing	Macrimed riphrap (class 8-3)	TON	800	RIP-		FION TOTAL (ROUNDED)	\$ 31,900.00
Railroad At-Grade Crossing				RAILROAD		BING TOTAL (ROUNDED) TION TOTAL (ROUNDED)	
Utilties							
N/A N/A	Overhead Distribution Underground Communication	LM LM	0.23 0.23		0.23 0.23	\$ 750,000 \$ 380,000	\$ 172,500 \$ 87,400
.4/.	Shaeiground Communication		0.23			ES TOTAL (ROUNDED)	\$ 259,900.00
Right-of-Way							
N/A	Right-of-Way	LS	1		1 RIGHT-OF-W		\$ - \$ -

BRIDGE TRANSPORTATION INVESTMENT REPORT (TIR) LR 02161 (SHELLMOUND RD)

LM 1.36

	DATE:	8/8/2021			
Name	Organization	Phone	Email		
Michael Cloud	TDOT - STID	615-532-7696	michael.cloud@tn.gov		
Michael Gilbert	TDOT - STID	615-741-0772	michael.gilbert@tn.gov		
David Duncan	TDOT - STID	615-532-6131	david.duncan@tn.gov		
Alan Wolfe	R2 - Traffic	423-510-1139	Alan.Wolfe@tn.gov		
Chester Sutherland	R2 - ETO	423-510-1229	Chester.Sutherland@tn.gov		
Marykate Collins	R2 - Traffic	423-510-1139	marykate.collins@tn.gov		
Ann Casseus	R2- Survey	423-510-1233	Ann.Casseus@tn.gov		
Jackson Collette	R2- Traffic	423-510-1139	Jackson.Collette@tn.gov		
Tami Johnson-Praino	R2 - Survey	423-510-1233	Tami.Johnson-Praino@tn.gov		



Northern Approach looking South



Western Edge of Bridge



Eastern Edge of Bridge



Southern Approach looking North



On bridge looking South



Southern Approach intersection with Piercy Road



Northern approach of bridge looking North



Drainage feature on Shellmound Rd



EB I-24 Looking East Under bridge



EB I-24 Looking West Under Bridge



EB I-24 Looking North Under Bridge



EB I-24 Looking South Under Bridge

СН	ECK LIST OF DETERMINANTS FOR LOCATION STUDY						
	acilities or ESE categories are located within the project area or k opposite the item. Where more than one alternate is to be cor tion in the blank.						
1. Agricultural land usage							
. Airport (existing or proposed)							
3. Commercial area, shopping center							
Floodplains							
5. Forested land							
6. Historical, cultural, or natural landmark							
7. Industrial park, fact	ory						
8. Institutional usages	•						
a. School or other educational institution							
	comment of the control of the contro						
c. Hospital or oth							
d. Public building, e.g., fire station							
e. Defense installation							
9. Recreation usages							
a. Park or recreational area							
b. Game preserve or wildlife area							
10. Residential establishment							
11. Urban area, town, o	city, or community						
12. Waterway, lake, po	nd, river, stream, spring						
Permit required:	Coast Guard						
·	Section 404						
	TVA Section 26a review						
	NPDES						
	Aquatic Resource Alteration						
13. Other		✓					
14. Location coordinated with local officials							
15. Railroad crossings							
16. Hazardous materials site							

Michael Cloud

From: David A. Duncan

Sent: Tuesday, March 15, 2022 9:59 AM

To: Michael Cloud

Subject: FW: Draft Bridge TIR - 130902.00 - Shellmound Road, Bridge over I-24 Eastbound Attachments: 130902.00 - Marion Co Shellmound Rd BTIR over I-24 EB - draft (12-3-21).pdf

From: Linda Tidwell <Linda.Tidwell@tn.gov>
Sent: Thursday, January 6, 2022 2:44 PM
To: David A. Duncan <David.A.Duncan@tn.gov>

Cc: Kimberly Vasut-Shelby <Kimberly.Vasut-Shelby@tn.gov>; Sharon Sanders <Sharon.Sanders@tn.gov>

Subject: FW: Draft Bridge TIR - 130902.00 - Shellmound Road, Bridge over I-24 Eastbound

David,

Thank you for the opportunity to comment on the draft Bridge TIR for the Shellmound Road Bridge over I-24 Eastbound.

The project is located in a rural/agricultural area and there are no obvious Section 4(f) resources in the project area. The bridge sufficiency rating is 54.2. Please include a purpose and need statement for replacing the bridge. Also, please include a statement as to whether the proposed project is expected to be constructed within the existing ROW. If ROW is needed, please include an estimated amount of ROW needed.

Thanks, Linda



Linda Tidwell | TDOT Environmental Studies Specialist Environmental Division/ NEPA Programs Office James K. Polk Building, 9th Floor 505 Deaderick Street, Nashville, TN 37243 P. 615-253-2860 Linda.Tidwell@tn.gov tn.gov/tdot

tri.gov/tuot

NEPA Office (tn.gov)

From: Kimberly Vasut-Shelby < Kimberly.Vasut-Shelby@tn.gov

Sent: Thursday, December 30, 2021 9:58 AM **To:** Linda Tidwell < Linda. Tidwell@tn.gov > **Cc:** Sharon Sanders < Sharon. Sanders@tn.gov >

Subject: Project Assignment: Draft Bridge TIR - 130902.00 - Shellmound Road, Bridge over I-24 Eastbound

Linda,

I have assigned the following project to you. Please provide NEPA comments for this draft.

Michael Cloud

From: Veda Nguyen

Sent: Tuesday, September 27, 2022 3:01 PM **To:** David A. Duncan; Daniel McDonell

Cc: Steve Allen; Jim Waters; Daniel Pallme; Michael Cloud; Michael Gilbert

Subject: RE: 130902.00 - Marion Shellmound Road over I-24 EB

Follow Up Flag: Follow up Flag Status: Flagged

Hi David,

Based on the information provided in the BTIR and TDOT standards and guidelines:

- Bicyclists can be accommodated with a shared lane
 - On low speed (Posted Speed <=35 mph) and low volume (ADT < 2000) rural roads, MM-TS-1 Table 2 indicates that a shared lane with vehicles is an acceptable bike accommodation.
- Pedestrians can be accommodated with a 5 ft paved shoulder
 - On rural collector roads where only an occasional pedestrian is expected, TDOT Design Guidelines, Chapter 3, Section 3-205.00 indicates that the shoulder is an acceptable pedestrian accommodation. TDOT Design Guidelines, Chapter 3, Section 3-801.00, Table 3-5 recommends a minimum paved shoulder width of 5ft (4ft + 1ft) to accommodate pedestrians along the bridge. The additional 1 ft is a required offset to the bridge railing (vertical element).

Please let me know if you have any follow-up questions.

Thanks,



Veda L. Nguyen, P.E. | Civil Engineering Manager II Multimodal Planning Office James K. Polk Bldg, 12th Floor 505 Deaderick St., Nashville, TN 37243 Office No. 615-532-0421 Veda.Nguyen@tn.gov

From: David A. Duncan < David.A. Duncan@tn.gov> Sent: Tuesday, September 27, 2022 8:58 AM

To: Veda Nguyen < Veda.Nguyen@tn.gov>; Daniel McDonell < Daniel.McDonell@tn.gov>

Cc: Steve Allen <Steve.Allen@tn.gov>; Jim Waters <Jim.Waters@tn.gov>; Daniel Pallme <Daniel.Pallme@tn.gov>;

Michael Cloud <Michael.Cloud@tn.gov>; Michael Gilbert <Michael.Gilbert@tn.gov>

Subject: 130902.00 - Marion Shellmound Road over I-24 EB

Veda/Daniel,

I don't think we ever got comments from your office for the attached bridge TIR, and it was going through the review process prior to the IIJA discussions began earlier this year. We are currently showing 4' shoulders across the bridge, but I think the Multimodal guidelines call for 5' shoulders when a vertical wall is present. Do you think we need to

accommodate pedestrians on this bridge? Or we okay with just providing the width on the shoulders for bikes? Let us know you thoughts about the multimodal accommodations for this project.

Thanks, Dave



David Duncan, PE | Civil Engineering Manager 1
Strategic Transportation Investments Division / Project Investigation
James K. Polk Building, 10th Floor
505 Deaderick St., Nashville, TN 37243
p. 615-532-6131
David.A.Duncan@tn.gov
tn.gov/tdot

https://www.tn.gov/tdot/strategic-transportation-investments.html

NATIONAL BRIDGE INVENTORY TENNESSEE INVENTORY AND APPRAISAL REPORT



COUNTY: MARION

ROUTE: 02161

BRIDGE ID NUMBER: 58100240039

BRIDGE OWNER: **STATE OF TENNESSEE**

FIPS CODE: 00000

ROAD NAME: **SHELLMOUND RD.**

CROSSING: SHELLMOUND RD. / I-24 EB

LOCATION: 3.5 MI S OF SR28

COUNTY SEQUENCE: 1 LOG MILE: 1.36

SPECIAL CASE: 0

SUFFICIENCY RATING: 54.2

IDENTIFICATION	CLASSIFICATION —				
(16a,b) LATITUDE: N 35.04068 DEGREES	(112) MEETS NBIS BRIDGE LENGTH: YES				
(17a,b) LONGITUDE: W 85.60353 DEGREES	(104) NATIONAL HIGHWAY SYSTEM: NOT A NHS ROUTE				
(98a) BORDER BRIDGE STATE CODE: N/A	(26) FUNCTIONAL CLASS: RURAL MINOR COLLECTOR				
(98b) PERCENT SHARE: N/A	(101) PARALLEL BRIDGE: NO PARALLEL BRIDGE				
(99) BORDER BRIDGE NUMBER: NOT APPLICABLE	(102) TRAFFIC DIR: 2-WAY TRAFFIC				
	(103) TEMPORARY BRIDGE: NOT APPLICABLE				
BRIDGE TYPE AND MATERIAL	(110) NATIONAL TRUCK ROUTE: NOT ON TRUCK NETWORK				
(43a) MAIN SPAN MATERIAL: CONCRETE CONTINUOUS	(37) HISTORICAL CLASS: HISTORICAL SIGNIFICANCE HAS				
(44a) APPR SPAN MATERIAL: NOT APPLICABLE	NOT BEEN DETERMINED				
(45) NUMBER OF MAIN SPANS: 3	———— CONDITION RATINGS				
(46) NUMBER OF APPROACH SPANS: 0	(58) DECK: 7				
(107) TYPE OF DECK: CONCRETE CAST-IN-PLACE	(59) SUPERSTRUCTURE: 5				
(108) TYPE OF WEARING SURFACE AND DECK PROTECTION:	(60) SUBSTRUCTURE: 7				
A) TYPE OF SURFACE: ASPHALT	(61) STREAM CHANNEL AND CHANNEL PROTECTION: N				
B) TYPE MEMBRANE: NONE	(62) CULVERT CONDITION (IF APPLICABLE): N				
C) TYPE PROTECTION: NONE	— DESIGN LOAD AND WEIGHT POSTING —				
	(31) DESIGN LOADING: HS-20-44 +MOD				
AGE AND SERVICE	WEIGHT POSTING (2 AXLE VEHICLES): ALL LEGAL LOADS				
(27) YEAR THE BRIDGE WAS BUILT: 1965	WEIGHT POSTING (3 OR MORE AXLES): ALL LEGAL LOADS				
(106) YEAR THE BRIDGE WAS REHABILITATED: N/A	(70) BRIDGE POSTING CODE: 5				
(42a) SERVICE ON BRIDGE: HIGHWAY	(41) WT POSTING STATUS: OPEN				
(42b) UNDER BRIDGE: HIGHWAY	APPRAISAL —				
(28a) NUMBER OF LANES CARRIED BY BRIDGE: 2	-				
(28b) NUMBER OF LANES UNDER THE BRIDGE: 2	(67) STRUCTURAL EVALUATION: 5 (68) DECK GEOMETRY: 5				
GEOMETRIC DATA	(69) UNDERCLEARANCE RATING: 3				
(48) MAXIMUM SPAN LENGTH: 61.0 FT	(71) WATERWAY ADEQUACY:				
(49) TOTAL BRIDGE LENGTH: 140.1 FT	(72) APPROACH ROADWAY ALIGNMENT: 6				
(50a) LEFT SIDEWALK WIDTH: 0.0 FT	(36) TRAFFIC SAFETY FEATURES: 0000				
(50b) RIGHT SIDEWALK WIDTH: 0.0 FT	(113) SCOUR CONDITION RATING:				
(51) BRIDGE CURB TO CURB WIDTH: 27.9 FT					
(52) BRIDGE OUT TO OUT WIDTH: 34.4 FT	RECOMMENDED IMPROVEMENTS				
(32) APPROACH ROADWAY (W/ SHLDS) WIDTH: 27.9 FT	(75) TYPE OF WORK: BRIDGE DECK REPAIR				
(33) BRIDGE MEDIAN: NO MEDIAN	(76) LENGTH OF BRIDGE IMPROVEMENT: 140.1 FT				
(34) BRIDGE SKEW: 32 DEGREES	(94) BRIDGE IMPROVEMENT COST: \$152,000.00				
(35) BRIDGE FLARE: NO FLARE	(95) ROADWAY IMPROVEMENT COST: \$16,000.00				
(520) MIN VERTICAL CLEARANCE OVER RD: NO RESTRICTION	(96) TOTAL PROJECT COST: \$229,000.00				
(47) MIN HORIZONTAL CLEARANCE ON ROADWAY: 27.9 FT	(97) YEAR OF IMPROVEMENT COST ESTIMATE: 2019				
(54a) VERT UNDERCLR: HIGHWAY BENEATH BRIDGE	INSPECTION DATES				
(54b) MIN VERTICAL UNDERCLEARANCE: 17.52 FT	(90) DATE OF LAST REGULAR INSPECTION: 7/24/2018				
(55a) HORZ UNDERCLR: HIGHWAY BENEATH BRIDGE	(91) REGULAR INSPECTION FREQUENCY (MONTHS): 24				
(55b) MIN HORZ UNDERCLR ON RIGHT: 11.15 FT	(93b) DATE OF LAST UNDERWATER INSP (MO/YR): N/A				
(56) MIN HORZ UNDERCLR ON LEFT: NOT APPLICABLE	(92b) UNDERWATER INSP FREQUENCY (MONTHS): N				
NAVIGATION DATA	(93c) DATE OF SPECIAL INSPECTION (MO/YR): N/A				
(38) NAV CONTROL: NOT APPLICABLE	(92c) SPECIAL INSP FREQUENCY (MONTHS): N				
(39) NAVIGATION VERTICAL CLEARANCE: N/A	PRODUCED PURSUANT TO				
	I NODUCED EUROUANT IU				

N/A

N/A

PUBLICATION DATE 19-Mar-20

(116) LIFT BRIDGE VERT CLEARANCE:


(40) NAVIGATION HORZ CLEARANCE:

PRODUCED PURSUANT TO
PUBLIC RECORDS REQUEST
This document is covered by 23 USC §409
and its production pursuant to a public
document records request does not
waive the provisions of §409

TENNESSEE DEPARTMENT OF TRANSPORTATION STRATEGIC TRANSPORTATION INVESTMENTS DIVISION

PROJECT NO.: 58100-0187-44						ROUTE:	SHELLMOUND ROAD				
COUNTY:	Y: MARION				CITY:						
PROJECT	PIN NUM	IBER: 130	902.00			_					
PROJECT DESCRIPTION: BRIDGE OVER I-24 @ L.M.				I. 1.36.							
DIVISIO	N REQ	UESTING	<u>:</u>			DATIENTEN	T DEGL	CNI	Г	¬	
MAINTE	NANCE			7			PAVEMENT DESIGN STRUCTURES				
MAINTEI S.T.I.D.	NANCE		L	_ 7				MIAN DI	EGIGN F	╡	
		MENT & A	DM [<u>ا</u> ا		SURVEY &			_	╡	
PUBLIC T				-		OTHER	SIGNAL	DESIGN	`	╡	
		& AEKO. ROGRAMME			DUCTION					_	
		ROGRAMMI ING DATE:	ED FOR CO	JNSII	RUCTIO	N: <u>2026</u>					
FROJECTI		ING DATE.	-								
TRAFFI	C ASSI	GNMENT	<u>:</u>								
							DESIGN DESIGN				
D. 65.							ROADWAY AVERAGE				
BASE Y	1	ļ		IGN Y		 		UCKS	DAILY LOADS		
AADT	YEAR	AADT	DHV	%	YEAR	DIR.DIST.	DHV	AADT	FLEX	RIGID	
1,750	2026	1,930	232	12	2046	65-35	2	3			
REQUESTED BY: NAME MICHAEL CLOUD				DATE	DATE 4/26/21						
-		DIVISION S.T.I.D.									
ADDRESS 1000 J. K. POLK BUIL			DING	TG .							
			NASHV	/ILLE	R TN 372	243					
REVIEWED BY:		DATE									
TRANSPORTATION MANAGER 1				_							
SUITE 1000, JAMES K. POLK BUILDING											
ADDROVED DV TONY ADMICTRONIC TO A TOTAL TO THE CONTROL OF THE CONT					14						
APPROVE	APPROVED BY: TONY ARMSTRONG / ony Armstrong DATE 4/26/2021						<u> </u>				
	TRANSPORTATION MANAGER 2 / SUITE 1000, JAMES K. POLK BUILDING										
		501115 1000,	27 MATERS IX. I	OLK.	POILDIM	J					
COMMI	ENTS:										

THIS TRAFFIC IS BASED ON A 2019 CYCLE COUNT. THE DESIGN YEAR TRAFFIC IS BASED ON GROWTH RATE FROM THE ADAM COMPUTER PROGRAM.



Marion County

Shellmound Road

Bridge over I-24 @ L.M. 1.36

Michael Cloud

From: David A. Duncan

Sent: Monday, September 26, 2022 1:26 PM

To: Michael Cloud

Subject: FW: FOLLOW-UP on Request for Letter of Approval - 130902.00 - MarionCo Shellmound Rd BTIR -

bridge over I-24 EB - detour approval request

Follow Up Flag: Follow up Flag Status: Flagged

Please add this to the report.

From: Marion County Highway Department <marion.hwy.dept@gmail.com>

Sent: Monday, September 26, 2022 1:25 PM **To:** David A. Duncan < David.A. Duncan@tn.gov>

Subject: [EXTERNAL] RE: FOLLOW-UP on Request for Letter of Approval - 130902.00 - MarionCo Shellmound Rd BTIR -

bridge over I-24 EB - detour approval request

*** This is an EXTERNAL email. Please exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email - STS-Security. ***

Mr. Hawk agrees the detour will be sufficient.

Paula Richards

Marion County Highway Department Administrative Office 513 East Valley Rd Jasper, TN 37347 Phone: 423-942-2581

WARNING:

CONFIDENTIALITY NOTICE - The information enclosed with this transmission are the private, confidential property of the sender, and the material is privileged communication intended solely for the individual indicated. If you are not the intended recipient, you are notified that any review, disclosure, copying, distribution, or the taking of any other action relevant to the contents of this transmission are strictly prohibited. If you have received this transmission in error, please notify me immediately at (423) 942-2581.

From: David A. Duncan

Sent: Monday, September 26, 2022 1:18 PM

To: marion.hwy.dept@gmail.com

Cc: Michael Cloud; Michael Gilbert; Jim Waters; Steve Allen

Subject: FW: FOLLOW-UP on Request for Letter of Approval - 130902.00 - MarionCo Shellmound Rd BTIR - bridge over I-

24 EB - detour approval request

Mr. Hawk,

I'm following up on Mr. Cloud's request below. We need confirmation from the County Roadway Department that the proposed detour is sufficient before we can finish up the report. Please let us know if you have any questions. Thanks.



David Duncan, PE | Civil Engineering Manager 1

Strategic Transportation Investments Division / Project Investigation James K. Polk Building, 10th Floor 505 Deaderick St., Nashville, TN 37243

p. 615-532-6131

David.A.Duncan@tn.gov

tn.gov/tdot

https://www.tn.gov/tdot/strategic-transportation-investments.html

From: Michael Cloud < Michael. Cloud@tn.gov> Sent: Tuesday, September 13, 2022 10:54 AM

To: Marion.HWY.DEPT@gmail.com

Cc: David A. Duncan < David.A.Duncan@tn.gov>; Michael Gilbert < Michael.Gilbert@tn.gov>; Jim Waters

<Jim.Waters@tn.gov>; Steve Allen <Steve.Allen@tn.gov>

Subject: FOLLOW-UP on Request for Letter of Approval - 130902.00 - Marion Co Shellmound Rd BTIR - bridge over I-24

EB - detour approval request

Hello Mr. Hawk,

This is a courtesy follow-up email regarding the previous request for Marion County Approval of the detour for the proposed Shellmound Rd Bridge replacement. I have included a map of the 7.8 mile detour that we plan to relocate traffic onto during project construction. Please let us know if you agree with this detour route by sending a response to this email.

Thanks,

Mike Cloud



Michael Cloud, PE | Transportation Project Specialist - Senior Strategic Transportation Investments Division James K. Polk Building, 10th Floor 505 Deaderick St., Nashville, TN 37243 p. 615-532-7696 c. 615-414-5040

tn.gov/tdot

https://www.tn.gov/tdot/strategic-transportation-investments.html

From: Michael Cloud

Sent: Thursday, September 1, 2022 7:42 AM

To: marion.hwy.dept@gmail.com

Cc: David A. Duncan < David.A. Duncan@tn.gov >; Michael Gilbert < Michael.Gilbert@tn.gov >; Steve Allen

<<u>Steve.Allen@tn.gov</u>>; Jim Waters <<u>Jim.Waters@tn.gov</u>>


Subject: 130902.00 - Marion Co Shellmound Rd BTIR - bridge over I-24 EB - detour approval request

Mr. Hawk,

Yesterday, we had a conversation over the phone about detours for the attached proposed BTIR project. What is shown in the attached report is 1-lane phase construct with a temporary signal, but what I am currently proposing will need a temporary roadway closure and reroute traffic onto the detour found below.

Do you think Shellmound Rd and TVA Rd can handle the detour traffic for this project if we restripe and install signs? We may need to have the bridge crossing closed and use the detour for over a year. Do you foresee any issues with the proposed detour route?

Please respond with an email confirming if the county is agreeable to the proposed detour route, or if you have any other ideas to consider.



Thanks, Mike Cloud



Michael Cloud, PE | Transportation Project Specialist – Senior Strategic Transportation Investments Division James K. Polk Building, 10th Floor 505 Deaderick St., Nashville, TN 37243 p. 615-532-7696 c. 615-414-5040 tn.gov/tdot

 $\underline{https://www.tn.gov/tdot/strategic\text{-}transportation\text{-}investments.} \underline{https://www.tn.gov/tdot/strategic\text{-}transportation\text{-}investments.} \underline{https://www.tn.gov/tdot/strategic\text{-}transportation\text{-$