

## Concept Report Form

The Concept Report Form develops an initial project vision, basis of design and report (e.g., the Concept Report) to transition into the subsequent design stages (Stages 1 through 4 in the Project Delivery Network [PDN]). This form summarizes all project components using information to complete the Concept Report.

### General Project Information

<b>Project Name</b>	Bridge over Lost Creek									
<b>PIN</b>	134879.00									
<b>Route Information</b>	<b>Route</b>	<b>NHS (Y/N)</b>	<b>Functional Class</b>			<b>City</b>		<b>County</b>		
	SR-180	No	Rural Major Collector			Nutbush		Haywood		
<b>Project Information</b>	<b>Begin Log Mile</b>	<b>End Log Mile</b>	<b>AADT<sup>1</sup></b>	<b>Design Hour Vol. (DHV)<sup>1</sup></b>	<b>Truck %<sup>1</sup></b>	<b>Design Speed (MPH)</b>	<b>Posted Speed (MPH)</b>	<b>Base Year</b>	<b>Design Year</b>	
	4.75		1,180	142	3.00	50	45	2029	2049	
<b>Project Description &amp; Standard Drawings Used</b>	<p>The proposed bridge is to be a 100' single span bridge. The typical section for the approach and bridge will be 2-10' foot travel lanes with 4' shoulders. The out-to-out width based on the above recommendations will be 29'3". The proposed grade and vertical clearance will be raised 1'. A detour is recommended. The state route detour is 42 minutes (32.1 miles) the local route detour is 12 minutes (7.4 miles). Superstructure depth is 67.51" = 54" (beam) + 10" (deck) + 3.51" (width (in inches) x0.02/2).</p> <p>RD11-TS-2</p>									
<b>Important Project History or Related Projects</b>	<p>The existing structure is a 5 span timber bridge, 95' long with an out-to-out width of 25'. The existing structure has 2-9' travel lanes with minimal to no shoulders. The listed weight limit on the inspection report is 40 tons 8/22/2023 The discharges for the drainage basin (StreamStats Version 4.19.4) for drainage area of 5.33 square miles: Q10 is 1860 cfs, Q50 is 2550 cfs, and Q100 is 2830 cfs.</p> <p>This project is not expected to utilize federal funding.</p>									
<b>Project Purpose/Need</b>	<p>The need to replace this bridge is due to the present condition of the existing bridge:</p> <ul style="list-style-type: none"> <li>-Built in 1961</li> <li>-Timber bridges are being phased out and is near the end of it's service life</li> <li>-Current typical section does not meet TDOT standards</li> <li>-The bridge is in POOR condition</li> </ul>									
<b>Major Environmental Considerations</b>	<p>Archaeology: A survey will be required.          Historic Preservation: A survey will be required.          Ecology: Water resources likely within project area.          NEPA: If the project remains state-funded, a TEER will be produced unless there is a federal nexus.</p>									

Project Details

<p><b>Multi-Modal Considerations</b></p>	<p>This project is in a rural area with a proposed 2-lane bridge width of less than 44 ft where the cost of dedicated multimodal accommodations is excessively disproportionate to the need and probable use. Excessively disproportionate is defined as exceeding 20 percent of the cost of the project.</p>	
<p><b>Major Project Risks</b></p>	<p>Approx. 0.94 acres of ROW to be acquired under the detour option and 3.86 acres for the realignment option. Power, Telecom, and Gas Utilities are present. This bridge replacement should be coordinated with the replacements at L.M. 4.57.</p> <p>This document is covered by 23 USC § 407 and its production pursuant to fulfilling public planning requirements does not waive the provisions of § 407.</p>	

<sup>1</sup> Traffic numbers reflect identified design year

**Approvals**

*Executed for approval of this Concept Report*

David Duncan  
 David Duncan (Nov 25, 2024 14:12 CST)  
 Engineering Concepts and Statewide Programs Director

11/25/2024  
 Date

*The following individuals to execute if a bridge concept report:*

Jed A. Krnigewicz  
 Structures Director

11/25/2024  
 Date

BLAZ  
 Regional Project Management Director

11/26/2024  
 Date

## Action Checklist

OSD1 Initiate Concept Report and Request Funding		
Complete	NA	Date Completed
✓		Request and Finalize Safety Data
✓		Request Project Number, PIN, and Task Profile Numbers
	✓	Coordinate with Long Range Planning
✓		Request and Finalize Traffic Data
	✓	Request Preliminary Survey Data
	✓	Initiate Division Reviews
	✓	Schedule Site Review (with appropriate Divisions)
0EN1 Conduct Environmental Desktop Review		
Complete	NA	Date Completed
✓		Confirm Environmental Desktop Review is Complete
0MM1 Conduct Multimodal Review		
Complete	NA	Date Completed
	✓	Confirm Multimodal Review is Complete
	✓	Review Multimodal Considerations & Recommendations
0TO1 Conduct Initial Traffic Ops/TSMO Review <i>(include HQ Traffic Ops and Regional Traffic Office)</i>		
Complete	NA	Date Completed
	✓	Confirm Transportation Systems Management & Operations (TSMO) Alignment & Operations Review is Complete
	✓	Request Concept Report Review
0ST1 Develop Structures Recommendations		
Complete	NA	Date Completed
✓		Confirm Recommended Structure Type for Concept Report is Complete
✓		Confirm Hydraulic Recommendations for Concept Report is Complete
0SY1 Provide Preliminary Survey Data		
Complete	NA	Date Completed
	✓	Confirm Control Ground Survey Set
	✓	Review Preliminary Survey Data
	✓	Determine Time to Complete the Aerial Survey
0GT1 Conduct Preliminary Geotechnical Assessment		
Complete	NA	Date Completed
	✓	Confirm Geotechnical Division Review is Complete
0RD1 Provide Roadway Desktop Review		
Complete	NA	Date Completed
		Confirm Roadway Division Review is Complete

## Action Checklist

OSD2 Develop Draft Concept Report			
Complete	NA		Date Completed
	✓	Conduct Intersection and Interchange Evaluation (IIE)	
	✓	Complete Conceptual Signal Warrants	
	✓	Develop Draft Conceptual Layouts/Crash Figures for Site Visit	
	✓	Compile Initial Divisional Reviews for Site Visit	
	✓	Prepare & Send Site Visit Packet	
	✓	Lead Site Visit	
	✓	Initiate Interstate Access Requests (IAR) Concept Coordination with FHWA (if applicable)	
✓		Develop, Compile, and Distribute the Draft Concept Report	10/02/2024
OTO2 Develop TSMO Scope Items <i>(include HQ Traffic Ops and Regional Traffic Office)</i>			
Complete	NA		Date Completed
	✓	Confirm Signal Warrants Analysis is Complete	
	✓	Confirm Lighting Warrants Analysis is Complete	
	✓	Review and Confirm TSMO & ITS Scope and Budget	
ORW1 Complete Preliminary Right-of-Way Estimates			
Complete	NA		Date Completed
	✓	Review and Confirm Preliminary Right-of-Way Cost Estimates	
OUT1 Complete Utility Preliminary Estimates			
Complete	NA		Date Completed
✓		Review and Confirm Preliminary Utility Estimate	10/17/2024
	✓	Review and Confirm Preliminary Railroad Cost Estimate	
OSD3 Finalize Concept Report			
Complete	NA		Date Completed
	✓	Compile and Review Initial Risk Assessment	
✓		Finalize Conceptual Layouts	11/21/2024
✓		Develop Environmental Technical Study Area (ETSA)	10/02/2024
✓		Address Comments and Finalize Concept Report	11/21/2024
	✓	Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable)	
	✓	Develop Roadway Safety Audit (RSA) No Plans Document	
✓		Submit the final Concept Report for Review and Signatures (as needed; see OSD3 for additional information)	11/21/2024
✓		Finalize Document and Upload All Needed Electronic Files	12/2/2024
✓		Notify the Project Management Director or Assigned Project Manager to Set Up Project (1PM1)	12/2/2024

## NA Justification

Coordinate with Long Range Planning-Long Range Planning coordination not needed for STID BCR document  
Request Preliminary Survey Data- survey data not needed for STID BCR document  
Schedule a site visit-site visit not required  
0MM1 Conduct Multimodal Review- multimodal coordination not required  
0SY1 Provide Preliminary Survey Data- survey data not needed for STID BCR document  
0GT1 Conduct Preliminary Geotechnical Assessment- geotechnical data not received for STID BCR document  
0SD2 Develop Draft Concept Report-no site visit was held for this bridge and no interchange or signal warrants were required  
0TO2 Develop TSMO Scope Items-no signals or lighting needed within project limits  
0RW1 Complete Preliminary Right-of-Way Estimates-ROW estimate calculated in cost estimate  
0UT1 Complete Utility Preliminary Estimates-utility cost calculated in cost estimate  
Compile and Review Initial Risk Assessment-Risk Assessment not needed for STID BCR document  
Address Comments and Finalize Interstate Access Requests (IAR) Document and Memo (if applicable)-no interstate within project limits  
Develop Roadway Safety Audit (RSA) No Plans Document- no plans document not needed for STID BCR document




**Concept Report  
Table of Contents/Attachments**

	Included	NA
One-Page Summary (with project location map)	✓	
Conceptual Layout(s) and Cross Section	✓	
Environmental Technical Study Area (ETSA) Layout	✓	
Concept Cost Estimate (Construction Year Estimate)	✓	
TSMO & ITS Scope and Budget <sup>1</sup>		✓
ROW Form 44-A <sup>1</sup>		✓
Crash Packet <sup>1</sup>	✓	
Crash Prediction Analysis <sup>1</sup>		✓
Site Visit Attendee List		✓
Environmental Desktop Review Form <sup>1</sup>		
Multimodal Considerations & Recommendations <sup>1</sup>		✓
Existing Structure Summary <sup>1</sup>	✓	
Email or memo containing Structure Type Recommendations <sup>1</sup>	✓	
Email or memo containing Hydraulic Recommendations <sup>1</sup>	✓	
Hydraulic Data	✓	
Intersection and Interchange Evaluation (IIE) Analysis and Summary Form		✓
Traffic Analysis Summary/Tables	✓	
Forecasted Traffic Sheets <sup>1</sup>	✓	
Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output) <sup>1</sup>		✓
Signal Warrant <sup>1</sup>		✓
Lighting Warrant <sup>1</sup>		✓
Initial Risk Assessment using the Risk Assessment Form		✓
Final Interstate Access Request (IAR) Document and Memo with Letter from STID Director		✓
Road Safety Audit (RSA) No Plans <sup>1</sup>		✓

**NA Justification**

TSMO & ITS Scope and Budget-no ITS within project limits; ROW Form 44-A-form not needed for STID BCR document; Crash Prediction Analysis- 2 crashes occurred within the project limits, crash prediction analysis not needed; Site Visit Attendee List-no site visit was held; Multimodal Considerations & Recommendation-no multimodal coordination; Intersection and Interchange Evaluation (IIE) Analysis and Summary Form- AADT is too low for IIE Analysis Traffic Modeling (e.g., Synchro, VISSIM, Highway Capacity Software (HCS) Output)- AADT too low to model Signal Warrant-no signals warranted within project limits; Lighting Warrant-no lighting warranted within project limits Initial Risk Assessment using the Risk Assessment Form-Risk Assessment not needed for STID BCR document Final IAR Document and Memo with Letter from STID Director-no interstate access within project limits Road Safety Audit (RSA) No Plans-RSA no plans document not needed for STID BTIR document


<sup>1</sup> External document to STID




Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community

**AREA MAP**  
**SR-180 BRIDGE [38S80510009]**  
**BRIDGE OVER LOST CREEK**  
**L.M. 4.75**  
**HAYWOOD COUNTY**





SR-180 BRIDGE [38S80510009]  
BRIDGE OVER LOST CREEK  
L.M. 4.75





Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community




LOCATION MAP  
SR-180 BRIDGE [38S80510009]  
BRIDGE OVER LOST CREEK  
L.M. 4.75  
HAYWOOD COUNTY







**SR-180 BRIDGE [38S80510009]  
BRIDGE OVER LOST CREEK  
L.M. 4.75**



Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community



**TOPOGRAPHIC MAP**  
**SR-180 BRIDGE [38S80510009]**  
**BRIDGE OVER LOST CREEK**  
**L.M. 4.75**  
**HAYWOOD COUNTY**



TYPE	YEAR	COUNTY	FIGURE NO.
BCR	2024	HAYWOOD	1


I:\13\2024 2:37:34 PM X:\Projects\Haywood\SR-180 (Forked Deer Rd)\Bridge over Overflow, LM 4.57 (TMA)\Project Files\Microstation\ConceptualPlans (DCN & PDF)\SR 180 Bridge over Overflow, L.M. 4.57.dgn



PIN 134878.00  
BRIDGE# 38S80510007  
70' BRIDGE LENGTH  
SINGLE SPAN USING 36" BOX BEAM  
2- 10' LANES W/ 4' SHOULDERS  
RAISE GRADE 1.5'

PIN 134879.00  
BRIDGE# 38S80510009  
100' BRIDGE LENGTH  
SINGLE SPAN USING TYPE IV I BEAM OR BT-54  
2-10' LANES W/ 4' SHOULDERS  
RAISE GRADE 1'

INCLUDE LIMITS OF RIPRAP  
IN CHANNEL IN PROPOSED ROW




## R4 TIMBER BRIDGE PROGRAM

STATE ROUTE 180  
BRIDGE OVER OVERFLOW, L.M. 4.57  
BRIDGE OVER LOST CREEK, L.M. 4.75  
HAYWOOD COUNTY

**CAUTION!**  
PRELIMINARY  
PLANS  
SUBJECT TO  
CHANGE

TYPE	YEAR	COUNTY	FIGURE NO.
BCR	2024	HAYWOOD	2

I:\13\2024 215144 PM  
 X:\Projects\Haywood\SR-180 (Forked Deer Rd)\Bridge over Lost Creek, LM 4.75 (TMA)\Project Files\Microstation\Conceptual Plans (DGN & PDF)\SR 180 Bridge over Lost Creek and Overflow, L.M. 4.57 and 4.75.dgn




## R4 TIMBER BRIDGE PROGRAM

STATE ROUTE 180  
 BRIDGE OVER OVERFLOW, L.M. 4.57  
 BRIDGE OVER LOST CREEK, L.M. 4.75  
 HAYWOOD COUNTY

**CAUTION!**  
 PRELIMINARY  
 PLANS  
 SUBJECT TO  
 CHANGE

TYPE	YEAR	COUNTY	FIGURE NO.
ETSA	2024	HAYWOOD	2a

\*Note: ETSA boundary combines Figure 1 & 2.




**ENVIRONMENTAL TECHNICAL STUDY AREA**  
 STATE ROUTE 180  
 BRIDGE OVER OVERFLOW, L.M. 4.57  
 BRIDGE OVER LOST CREEK, L.M. 4.75  
 HAYWOOD COUNTY

**CAUTION!**  
PRELIMINARY  
PLANS  
SUBJECT TO  
CHANGE

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION S.T.I.D.	
FIGURE 2a	
S.R. 180	
L.M. 4.57	
L.M. 4.75	

**PROPOSED COMPLETED**



**CROSS-SECTION DETAIL**

**REGION 4 TIMBER BRIDGE PROGRAM  
TRANSPORTATION MODERNIZATION ACT (TMA)**

**CAUTION!  
PRELIMINARY  
PLANS  
SUBJECT TO  
CHANGE**

# DETOUR MAP - STATE ROUTE

**Search along the route** | Gas | EV charging | Hotels

42 min | 11 hr | 2 hr 55

- 4576-4752 Forked Deer Rd, Gates, TN 381
- Brownsville, TN, Tennessee
- Ripley, Tennessee 38063
- Haywood County School District, Tennes
- Haywood County School District, Tennes

+ Add destination

Options

Send directions to your phone | Copy link

via TN-180 N | 42 min | 42 min without traffic | 32.1 miles

Details

Explore Haywood County School District

Layers

Map data ©2024 United States Terms Privacy Send Product Feedback 1 mi

# DETOUR MAP - LOCAL ROUTE

**Transportation Modes:** 12 min (Car), 2 hr 36 (Public Transit), 39 min (Bike), 39 min (Walk), 39 min (Plane)

**Destinations:**  
4576-4752 Forked Deer Rd, Gates, TN 38037  
Forked Deer, Tennessee 38037  
Haywood County School District, Tennessee  
Haywood County School District, Tennessee

**Options:**  
Send directions to your phone | Copy link

**Route Summary:**  
via TN-180 N | 12 min | 12 min without traffic | 7.4 miles

**Explore Haywood County School District:**  
Restaurants | Hotels | Gas stations | Parking Lots | More

**Map Labels:** Search along the route, Gas, EV charging, Hotels, Forked Deer Community Park, Forked Deer, Sundown Express, Woodville, Woodville Baptist Church Cemetery, Haywood County School District, 4576-4752 Forked Deer Road, Haywood County School District, Maranatha Baptist Church, Curve Woodville Rd, TN-180 N, TN-180 E

**Map Data:** ©2024 United States | Terms | Privacy | Send Product Feedback | 2000 ft

# Haywood Co SR180 - Bridge over Overflow

Created on April 4, 2024

Created by JOSHUA CLOUD

Data extents: March 28, 2021 to March 28, 2024



## Applied Filters

County = Haywood Shape: Polygon



Total Crashes	2	Fatal Crashes	0
---------------	---	---------------	---

Summary	Crash	
Total Crashes	2	100.00%
+ 5 more	0	0%

Type of Crash	Crash	
(B) Suspected Minor Injury	1	50.00%
(O) Property-Damage Only	1	50.00%
+ 3 more	0	0%

Date of Crash (Year)	Crash	
2023	1	50.00%
2021	1	50.00%
+ 9 more	0	0%

Manner of First Collision	Crash	
No Collision W/ Vehicle	2	100.00%
+ 9 more	0	0%



First Harmful Event		Crash
Ditch	1	50.00%
Earth Embankment	1	50.00%
+ 63 more	0	0%

Crash Location		Crash
Along Roadway	2	100.00%
+ 6 more	0	0%

Light Conditions		Crash
Dark-Not Lighted	1	50.00%
Daylight	1	50.00%
+ 6 more	0	0%

Weather Conditions		Crash
Clear	2	100.00%
+ 11 more	0	0%



Latitude:35.75331, Longitude:-89.39081

Region 04, 38 - Haywood County

Team Leader: Jason Ellison

Inspectors: Tonjuanita James, Stuart Wood, Nathan Bedford, Shayne Hayes, Ty Patrick



Span 1



Span 2



Spall steel slab F span 2



Typical span 1 slab B




Span #5 PCCS "E" spall to steel



Span #5 PCCS "B" spall to steel



Span #5 PCCS "A" spall to steel



Bottom deck span #3




Right elevation



Span #4 PCCS "B" spall to steel



Bottom deck span #4



Span #3 PCCS "B" spall to steel






Approach 1 weight limit sign



Approach 2 weight limit sign



Approach 2 right embankment washing



Right side downstream



Left side upstream



Approach 2 asphalt



Approach 1 asphalt



Bent 4 pile f crack 1/4" wide



Bent 4 pile C decayed



Abutment 2



Rear side bent 1



Front side bent 1



Abutment 1



Approach 2 weight limit sign



Opposite direction of route




End of span 4 right side curb spalled





Span 3 view across top deck



Span 2 top deck spalled



Approach 1 weight limit sign



Direction of route




View across deck span 1



Left elevation



Bent 3 pile D splintered area



Bent 3 pile C decayed to a 1.5" shell




Bent 3 pile A decayed area



Bent 2 pile B decayed to a 1" shell

# Haywood Co SR180 - Bridge over Lost Creek (LM 4.75)

Region ID: TN  
 Workspace ID: TN20240409154010670000  
 Clicked Point (Latitude, Longitude): 35.75334, -89.39060  
 Time: 2024-04-09 10:40:33 -0500



[+ Collapse All](#)

## > Basin Characteristics

Parameter Code	Parameter Description	Value	Unit
CONTDA	Area that contributes flow to a point on a stream	5.33	square miles
DRNAREA	Area that drains to a point on a stream	5.33	square miles

## > Peak-Flow Statistics

### Peak-Flow Statistics Parameters [DAOnly Area 4]

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
CONTDA	Contributing Drainage Area	5.33	square miles	0.76	2308

### Peak-Flow Statistics Flow Report [DAOnly Area 4]

PIL: Lower 90% Prediction Interval, PIU: Upper 90% Prediction Interval, ASEp: Average Standard Error of Prediction, SE: Standard Error (other -- see report)

Statistic	Value	Unit	PIL	PIU	SE	ASEp	Equiv. Yrs.
50-percent AEP flood	1050	ft <sup>3</sup> /s	560	1970	38.7	38.7	1.8
20-percent AEP flood	1540	ft <sup>3</sup> /s	839	2830	37.2	37.2	2.4
10-percent AEP flood	1860	ft <sup>3</sup> /s	1000	3450	38	38	3.1
4-percent AEP flood	2260	ft <sup>3</sup> /s	1180	4330	40.1	40.1	3.8
2-percent AEP flood	2550	ft <sup>3</sup> /s	1290	5050	42.2	42.2	4.2
1-percent AEP flood	2830	ft <sup>3</sup> /s	1380	5810	44.7	44.7	4.4
0.2-percent AEP flood	3490	ft <sup>3</sup> /s	1550	7860	51.1	51.1	4.7

*Peak-Flow Statistics Citations*

**Law, G.S., and Tasker G.D., 2003, Flood-Frequency Prediction Methods for Unregulated Streams of Tennessee, 2000: U.S. Geological Survey Water-Resources Investigations Report 03-4176, 79p. (<http://pubs.usgs.gov/wri/wri034176/>)**

➤ **Maximum Probable Flood Statistics**

**Maximum Probable Flood Statistics Parameters [Crippen Bue Region 3]**

<b>Parameter Code</b>	<b>Parameter Name</b>	<b>Value</b>	<b>Units</b>	<b>Min Limit</b>	<b>Max Limit</b>
DRNAREA	Drainage Area	5.33	square miles	0.1	10000

**Maximum Probable Flood Statistics Flow Report [Crippen Bue Region 3]**

<b>Statistic</b>	<b>Value</b>	<b>Unit</b>
Maximum Flood Crippen Bue Regional	16600	ft <sup>3</sup> /s

*Maximum Probable Flood Statistics Citations*

**Crippen, J.R. and Bue, Conrad D. 1977, Maximum Floodflows in the Conterminous United States, Geological Survey Water-Supply Paper 1887, 52p. (<https://pubs.usgs.gov/wsp/1887/report.pdf>)**

USGS Data Disclaimer: Unless otherwise stated, all data, metadata and related materials are considered to satisfy the quality standards relative to the purpose for which the data were collected. Although these data and associated metadata have been reviewed for accuracy and completeness and approved for release by the U.S. Geological Survey (USGS), no warranty expressed or implied is made regarding the display or utility of the data for other purposes, nor on all computer systems, nor shall the act of distribution constitute any such warranty.

USGS Software Disclaimer: This software has been approved for release by the U.S. Geological Survey (USGS). Although the software has been subjected to rigorous review, the USGS reserves the right to update the software as needed pursuant to further analysis and review. No warranty, expressed or implied, is made by the USGS or the U.S. Government as to the functionality of the software and related material nor shall the fact of release constitute any such warranty. Furthermore, the software is released on condition that neither the USGS nor the U.S. Government shall be held liable for any damages resulting from its authorized or unauthorized use.

USGS Product Names Disclaimer: Any use of trade, firm, or product names is for descriptive purposes only and does not imply endorsement by the U.S. Government.

Application Version: 4.19.4  
StreamStats Services Version: 1.2.22  
NSS Services Version: 2.2.1

**TENNESSEE DEPARTMENT OF TRANSPORTATION  
STRATEGIC TRANSPORTATION INVESTMENTS DIVISION**

PROJECT NO.: 38S180-S1-006 ROUTE: S.R. 180  
 COUNTY: HAYWOOD CITY: \_\_\_\_\_  
 PROJECT PIN NUMBER: 134879.00  
 PROJECT DESCRIPTION: BRIDGE OVER LOST CREEK @ L.M. 4.75  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**DIVISION REQUESTING:**

MAINTENANCE  PAVEMENT DESIGN   
 S.T.I.D.  STRUCTURES   
 PROG. DEVELOPMENT & ADM.  SURVEY & ROADWAY DESIGN   
 PUBLIC TRANS. & AERO.  TRAFFIC SIGNAL DESIGN   
 OTHER \_\_\_\_\_   
 YEAR PROJECT PROGRAMMED FOR CONSTRUCTION: 2029  
 PROJECTED LETTING DATE: 2029

**TRAFFIC ASSIGNMENT:**

BASE YEAR		DESIGN YEAR					DESIGN ROADWAY % TRUCKS		DESIGN AVERAGE DAILY LOADS	
AADT	YEAR	AADT	DHV	%	YEAR	DIR.DIST.	DHV	AADT	FLEX	RIGID
820	2029	1,180	142	12	2049	65-35	3	4		

REQUESTED BY: NAME CALEB SMITH DATE 2/15/24  
 DIVISION S.T.I.D.  
 ADDRESS 1000 J. K. POLK BUILDING  
NASHVILLE TN 37243

REVIEWED BY: RANDY BOGUSKIE Randy Boguskie DATE 2/22/2024  
 TRANSPORTATION MANAGER 1  
 SUITE 1000, JAMES K. POLK BUILDING

APPROVED BY: TONY ARMSTRONG Tony Armstrong DATE 2/22/2024  
 TRANSPORTATION MANAGER 2  
 SUITE 1000, JAMES K. POLK BUILDING

**COMMENTS:**

FURNISH THE 2029-2049 TRAFFIC DATA.

THIS TRAFFIC IS BASED ON A 2023 CYCLE COUNT. THE DESIGN YEAR TRAFFIC IS BASED ON GROWTH RATE FROM THE TN-TIMES LINEAR REGRESSION TOOL.

**DHV'S ARE NOT REQUIRED FOR SIDE ROADS LESS THAN 1000 AADT.**

**NOTE:** FOR BRIDGE REPLACEMENT PROJECTS, ADLs ARE NOT REQUIRED FOR ADTs OF 1000 OR LESS AND PERCENTAGE OF TRUCKS OF 7% OR LESS.

SEE ATTACHMENTS FOR TURNING MOVEMENTS AND/OR OTHER DETAILS.

(REV. 6/9/21)





# Environmental Division

## 0SD2 Environmental Desktop Review Form

### Part 1 – Project Information

<b>PIN</b>	134879.00
<b>Project Number (if available)</b>	
<b>County</b>	Haywood
<b>Route</b>	SR180
<b>Termini</b>	Bridge over Lost Creek (TMA)
<b>Type of Document</b>	
<b>Date ENV DIV Comments are Due</b>	10/17/24 by noon

**Part 2: Provide information identifying known Environmental Resources within the proposed project area using the attached information. If no known resources are identified, each study area should note that none were identified.**

### Air & Noise

#### AIR QUALITY

##### ***Transportation Conformity***

This project is in Haywood County which is in attainment for all regulated criteria pollutants. Therefore, conformity does not apply to this project.

##### ***Mobile Source Air Toxics (MSATs)***

This project qualifies as a categorical exclusion under 23 CFR 771.117 and, therefore, does not require an evaluation of MSATs per FHWA's "Interim Guidance Update on Air Toxic Analysis in NEPA Documents" dated January 2023.

#### NOISE

This project is Type III in accordance with the FHWA noise regulation in 23 CFR 772 and TDOT's noise policy; therefore, a noise study is not needed.

## **Cultural Resources**

Archaeology: No resources within a 1 mile radius. A survey will be required.

Historic Preservation – There are no previously surveyed resources within 0.25 miles of the proposed project. However, the bridge itself is over 50 years old. A survey will be required.

## **Ecology**

Water resources likely within project area.

## **HazMat**

No known hazardous materials sites affect the area around this bridge replacement. No additional hazardous material studies are recommended at this time. The asbestos bridge survey has been completed and the following project commitments have been submitted in PPRM. In the event hazardous materials or wastes are encountered within the right-of-way, notification shall be made per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Section 107.08.C. Disposition of hazardous materials or wastes shall be subject to all applicable Federal, State, and local regulations, including the applicable sections of the Federal Resource Conservation and Recovery Act, as amended; the Comprehensive Environmental Response, Compensation, and Liability Act, as amended; and the Tennessee Hazardous Waste Management Act of 1983, as amended. Databases reviewed include Google Earth imagery, EPA National Priorities List, EPA EnviroMapper (Envirofacts), TDEC Registered Underground Storage Tanks Public Data Viewer and Data and Reports, TDEC Division of Water Resources Public Data Viewer and Oil and Gas Wells database, TDEC Division of Remediation Sites Public Data Viewer, TDOT Integrated Bridge Information System, and others, as necessary.

EDHZ001. An Asbestos Containing Material (ACM) survey was completed on Bridge No. 38S80510009 SR-180 over Lost Creek LM 4.75 (38-SR180-04.75). The bridge has asbestos in the pad material between the curb and guard rail supports; approximately 50 square feet at 60% chrysotile. Please see the report for further details and photographs.

EDHZ002. The State of Tennessee asbestos accreditation requirements (TDEC Rules Chapter 1200-01-20) mandates that ACM abatement work be performed by an accredited firm (contractor) using accredited abatement workers and supervisors. Abatement of this material shall be accomplished per SP202ACM Special Provision Regarding Removal of Asbestos-Containing Materials. ACM abatement should be completed prior to any demolition activities if possible. Prior to the demolition or rehabilitation of any structure (bridge or building), the contractor is required to submit the National Emission Standards for Hazardous Air Pollutants standard 10-day notice of demolition to the TDEC Division of Air Pollution Control (per TDOT Standard Specifications for Road and Bridge Construction (January 1, 2021) Sections 107.08.D and 202.03).

## **NEPA**

If the project remains state-funded, a TEER will be produced unless there is a federal nexus.

Based on a preliminary review, there are No Section 6(f) properties within the project area.

Based on the 2022 ACS data, there are no EJ populations.

Consider combining the ETSA boundaries from Figure 1a and Figure 2a. A single ETSA should be reasonably conservative to minimize the risk of a Reevaluation.