| TYPE | YEAR | PROJECT NO. | SHEET NO. |
|---|---|---|---|
| CONST. | 2017 | HSIP-106(33) | 22A |

ALL SIGNS SHOWN WITH DESIGNATIONS ARE TO BE FABRICATED AS DETAILED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (CURRENT EDITION)

SEE STD. DWG. NO. T-S-19

| SIGN NO | LEGEND | | SHEET NO | SIZE | | | | COPY | | | | SHIELD | ARROW | SIGN FACE | | | STEEL DESIGN (BREAK-AWAY) | | | | | MINIMUM VERTICAL CLEARANCE | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | LENGTH | HEIGHT | RADIUS | BORDER WIDTH | CAPITAL | LOWER CASE | NUMERAL | SERIES | | | COPY | BACKGROUND | MATERIAL | SUPPORT TYPE | SUPPORT LENGTH | FOOTING | CONC. CU. YD. | REIN STEEL LBS. | | |
| 17 | | W1-8L | 21 | 18" | 24" | | | | | | | | | BLACK | YELLOW (FLOR.) | 0.080" SHEET ALUM. | U1 | h1=11'-0" | | | | 5'-0" | |
| 23 | | | | | | | | | | | | | | | | | | | | | | | |
| 25 | | | | | | | | | | | | | | | | | | | | | | | SLIP BASE REQUIRED ITEM NO. 713-11.21. SEE STD. DWG. T-S-23A. |
| 16 | | W1-8R | 21 | 18" | 24" | | | | | | | | | BLACK | YELLOW (FLOR.) | 0.080" SHEET ALUM. | USE ANGLE BRACKET | | | | | | MOUNTED ON BACK OF SIGN #17 |
| 22 | | | | | | | | | | | | | | | | | | | | | | | MOUNTED ON BACK OF SIGN #23 |
| 24 | | | | | | | | | | | | | | | | | | | | | | | MOUNTED ON BACK OF SIGN #25 |
| 19 | | OM3-L | 21 | 12" | 36" | | | | | | | | | BLACK | YELLOW (REF.) | 0.100" SHEET ALUM. | U3 | h1=10'-9" | | | | 4'-0" | |
| 20 | | | | | | | | | | | | | | | | | | h1=10'-9" | | | | | |
| 18 | | OM3-R | 21 | 12" | 36" | | | | | | | | | BLACK | YELLOW (REF.) | 0.100" SHEET ALUM. | U3 | h1=10'-9" | | | | 4'-0" | |
| 21 | | | | | | | | | | | | | | | | | | h1=10'-9" | | | | | |
| 26 |  | W3-3 | 21 | 36" | 36" | | | | | | | | | BLACK RED (REF.) GREEN (REF.) | YELLOW (FLOR.) | 0.100" SHEET ALUM. | P6 | h1=14'-3" | | | | 5'-0" | SOLAR FLASHING WARNING BEACON (AMBER) SLIP BASE REQUIRED ITEM NO. 713-11.21. SEE STD. DWG. T-S-23A. 2" YELLOW RETROREFLECTIVE STRIP MOUNTED ON THE POST FACING EASTBOUND TRAFFIC ON CRITZ LANE. |

U-POST SUBSTITUTION TABLE

| BID ITEM 713-11.01 | SUBSTITUTION ALLOWED |
|---|---|
| 2#/FT. U1 | 2#/FT. MU1 OR 2#/FT. R1 |
| 2.5#/FT. U3 | 2.5#/FT. MU3 OR 3#/FT. R2* |
| 3#/FT. U6 | |
| 4#/FT. U7 | NO SUBSTITUTES |

* PAID AT A RATE OF 2.5#/FT.

SEALED BY




STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

# SIGN SCHEDULE

9/19/2017 5:49:32 AM
T:\TDOT\Williamson_SRI06_Critz\022A.sht