| TYPE | YEAR | PROJECT NO. | SHEET NO. |
|---|---|---|---|
| CONST. | 2017 | HSIP-106(33) | 2A4 |
| | | | |
| | | | |
| | | | |

## ESTIMATED UTILITY QUANTITIES

| ITEM NO. | DESCRIPTION | UNIT | 94014-3235-94 QUANTITY |
|---|---|---|---|
| 775-60.01 | 18IN BALL AND SOCKET DIP RESTRAINED | L.F. | 126 |
| 775-60.02 | 12IN BALL AND SOCKET DIP RESTRAINED | L.F. | 108 |
| 795-01.03 | 6IN DIP RESTRAINED JOINT WATER LINE | L.F. | 140 |
| 795-01.08 | 10IN DIP SLIP JOINT WATER LINE | L.F. | 20 |
| 795-01.10 | 12IN DIP SLIP JOINT WATER LINE | L.F. | 1300 |
| 795-01.15 | 18IN DIP RESTRAINED JOINT WATER LINE | L.F. | 150 |
| 795-01.16 | 18IN DIP SLIP JOINT WATER LINE | L.F. | 300 |
| 795-03.02 | 2IN PVC WATER LINE | L.F. | 20 |
| 795-03.05 | 6IN PVC WATER LINE | L.F. | 570 |
| 795-05.14 | HDD 3IN HDPE CASING PIPE - UNCON | L.F. | 750 |
| 795-05.63 | BORE/JACK 12IN STEEL CASING PIPE-UNCON. | L.F. | 140 |
| 795-05.69 | BORE/JACK 30IN STEEL CASING PIPE-UNCON. | L.F. | 140 |
| 795-06.02 | CONNECT TO 3IN WATER LINE | EACH | 1 |
| 795-07.03 | 6IN X 6IN TAPPING SLEEVE AND VALVE | EACH | 2 |
| 795-07.10 | 10IN X 10IN TAPPING SLEEVE AND VALVE | EACH | 1 |
| 795-08.01 | 2IN GATE VALVE ASSEMBLY | EACH | 1 |
| 795-08.02 | 3IN GATE VALVE ASSEMBLY | EACH | 1 |
| 795-08.04 | 6IN GATE VALVE ASSEMBLY | EACH | 7 |
| 795-08.09 | 12IN GATE VALVE ASSEMBLY | EACH | 3 |
| 795-08.16 | 18IN GATE VALVE ASSEMBLY | EACH | 3 |
| 795-09.01 | 3/4IN WATER SERVICE METER ASSEMBLY | EACH | 10 |
| 795-09.62 | 1IN PEXA SERVICE PIPE | L.F. | 800 |
| 795-11.01 | BLOW-OFF ASSEMBLY | EACH | 2 |
| 795-11.02 | FIRE HYDRANT ASSEMBLY | EACH | 5 |
| 795-13.01 | DI FITTINGS | LBS | 1500 |
| 795-14.02 | CLASS B CONCRETE | C.Y. | 30 |
| 795-14.08 | RESTORE ASPHALT | S.Y. | 15 |
| 795-14.10 | RESTORE GRAVEL | S.Y. | 15 |
| | | | |

**NOTE: SEE SHEET U1-1 FOR INDEX OF UTILITY SHEETS**

SEALED BY




09/21/2017

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

# ESTIMATED UTILITIES QUANTITIES

9/20/2017 9:10:46 AM
T:\TDOT\Williamson_SR106_Critz\002A4.sht