| TYPE | YEAR | PROJECT NO. | SHEET NO. |
|---|---|---|---|
| CONST. | 2017 | HSIP-106(33) | 20A |
| | | | |
| | | | |
| | | | |

## TRAFFIC CONTROL QUANTITIES

| ITEM NO. | DESCRIPTION | UNIT | QUANTITY | SIGN SIZE S.F. | ITEM NO. 712-06 (S.F.) | SIZE | M.U.T.C.D. NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|
| 705-08.51 | PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3 | EACH | 5 | | | | | |
| 712-01 | TRAFFIC CONTROL | LS | 1 | | | | | |
| 712-02.02 | INTERCONNECTED PORTABLE BARRIER RAIL | L.F. | 1770 | | | | | |
| 712-04.01 | FLEXIBLE DRUMS (CHANNELIZING) | EACH | 167 | | | | | |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 1 | 16 | 16 | 48" X 48" | W1-4 | REVERSE CURVE LT |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 1 | 16 | 16 | 48" X 48" | W1-4 | REVERSE CURVE RT |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 2 | 6.25 | 12.5 | 30" X 30" | W13-1P | ADVISORY SPEED 40 M.P.H. (PLAQUE) |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 2 | 3 | 6 | 24" X 18" | W16-2P | SUPPLEMENTAL DISTANCE 500 FT (PLAQUE) |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 4 | 16 | 64 | 48" X 48" | W20-1 | ROAD WORK AHEAD |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 4 | 4.5 | 18 | 36" X 18" | G20-2 | END ROAD WORK |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 2 | 16 | 32 | 48" X 48" | W20-1 | ROAD WORK 1500 FT |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 2 | 16 | 32 | 48" X 48" | W20-1 | ROAD WORK 1000 FT |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 2 | 16 | 32 | 48" X 48" | W20-4 | ONE LANE ROAD 1000 FT |
| 712-06 | SIGNS (CONSTRUCTION) | S.F. | 4 | 16 | 64 | 48" X 48" | W20-7 | FLAGGER SYMBOL |
| 716-05.01 | PAINTED PAVEMENT MARKING (4" LINE) | L.M. | 3 | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| **TOTAL** | | | | | **293** | | | |

SEALED BY




STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

# TRAFFIC CONTROL TABULATED QUANTITIES

9/21/2017 11:52:16 AM
T:\TDOT\Williamson_SRI06_Critz\020A.sht