

THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY:

Daniel McGaha Digitally signed by Daniel McGaha Date: 2025.09.24 08:13:55-05'00'

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. THE SIGNATURE MUST BE VERIFIED ON THE ELECTRONIC DOCUMENTS.

HDR ENGINEERING, INC. 120 BRENTWOOD COMMONS WAY SUITE 525 BRENTWOOD, TN 37027 DANIEL K. MCGAHA, P.E. 108037

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE OF TENN. CODE ANN. §62-2-306.

SHEET NAME	SHEET NO.
SIGNATURE SHEET	ROADWAY-SIGN
TITLE SHEET	1
ROADWAY INDEX, STANDARD ROADWAY DRAWINGS AND	
STANDARD TRAFFIC DESIGN DRAWINGS	1A
ESTIMATED ROADWAY QUANTITIES	2
TYPICAL SECTIONS AND PAVEMENT SCHEDULE	2B
GENERAL NOTES	2C
SPECIAL NOTES	2D
ENVIRONMENTAL NOTES	2E, 2E1
TABULATED QUANTITIES	2F
UTILITY NOTES AND UTILITY OWNERS	3
PAVEMENT EDGE DROP-OFF NOTES FOR TRAFFIC CONTROL	T1

YEAR	PROJECT NO.	SHEET NO.
2025	NH-55(34)	ROADWAY-SIGN 1

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SIGNATURE SHEET PROJECT TO BE LET WITH: MOORE CO. SR 55 PIN 135033-00


STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING

MOORE COUNTY


STATE ROUTE 55 FROM SR-50 (MAIN STREET) TO NEAR RIDDLE ROAD

RESURFACE & SAFETY MILL, 411D AND PAVEMENT MARKINGS

STATE HIGHWAY NO. 55 F.A.H.S. NO. N/A



	TENN.	YEAR	SHEET NO.
	I EININ.	2025	1
FED	. AID PROJ. NO.	NH-55(34)
STA	ATE PROJ. NO.	64S055-F8	-003
STA	ATE PROJ. NO.	64S055-M3	3-003



64SR0550007 64SR0550009 64SR0550011

EXCLUSIO	NS
STATION TO STATION	LENGTH (FT.)
2.57 - 3.22	0.65
-	•
-	
TOTAL=	0.65

64S055-F8-003 END PROJECT NO. NH-55(34) RESURFACE & SAFETY

NEAR RIDDLE ROAD (L.M. 5.59)

BRIDGE DECK REPAIR PROJECT NO. 64S055-M3-003

SR-55 @ L.M 3.88 & 4.26

64S055-F8-003 BEGIN PROJECT NO. NH-55(34) RESURFACE & SAFETY

SR-50 (MAIN STREET) (L.M. 0.00)

SPECIAL NOTES

PROPOSALS MAY BE REJECTED BY THE COMMISSIONER IF ANY OF THE UNIT PRICES CONTAINED THEREIN ARE OBVIOUSLY UNBALANCED, EITHER EXCESSIVE OR BELOW THE REASONABLE COST ANALYSIS VALUE.

THIS PROJECT TO BE CONSTRUCTED UNDER THE STANDARD SPECIFICATIONS OF THE TENNESSEE DEPARTMENT OF TRANSPORTATION DATED JANUARY 1, 2021 AND ADDITIONAL SPECIFICATIONS AND SPECIAL PROVISIONS CONTAINED IN THE PLANS AND IN THE PROPOSAL CONTRACT.

TDOT PROJECT MANAGER: KONNER SPRADLIN, P.E.

DESIGN FIRM: HDR ENGINEERING, INC.

DESIGNER: DANIEL K. MCGAHA, P.E.

98034-4299-04 (DESIGN) PIN NO. 135034.00

CHECKED BY DAVID HORNE, P.E.

PROJECT LENGTH TOTAL LANE MILES RESURFACED

SCALE: 1"= 1 MILE

4.94 MILES 10.45 MILES

TIMS FORD LAKE

SEALED BY

TRAFFIC COUNTER & WEATHER STATIONS

STATION LOCATION	LOG MIL
TC STATION 30	0.052
TC STATION 10	3.075
TC STATION 12	4.120

TRAFFIC DATA	
ADT (2025)	8914
POSTED SPEED LM 0.00 - 0.55	45 MPH
POSTED SPEED LM 0.55 - 1.73	30 MPH
POSTED SPEED LM 1.73 - 2.33	45 MPH
POSTED SPEED LM 2.33 - 5.59	55 MPH

ROADWAY INDEX

NUMBERING OF SHEETS.

SHEET NAME	SHEET NO.
SIGNATURE SHEETS	ROADWAY-SIGN
TITLE SHEET	1
ROADWAY INDEX, STANDARD ROADWAY DRAWINGS, AND	
STANDARD TRAFFIC DESIGN DRAWINGS	1A
ESTIMATED ROADWAY QUANTITIES	2
TYPICAL SECTIONS AND PAVEMENT SCHEDULE	2B
GENERAL NOTES	2C
SPECIAL NOTES	2D
ENVIRONMENTAL NOTES	2E, 2E1
TABULATED QUANTITIES	2F
PAVEMENT MARKING IMPROVEMENTS	2G, 2G1 – 2G3
UTILITY NOTES, AND UTILITY OWNERS	3
PAVEMENT EDGE DROP-OFF NOTES FOR TRAFFIC CONTROL	T1
BRIDGE REPAIR PLANS	B-1

NOTE: THE ALPHABETICAL LETTERS "I", "O" & "Q" ARE NOT USED IN THE

NO PROJECT COMMITMENT SHEETS ARE INCLUDED IN THIS SET OF PLANS

NO UTILITY SHEETS ARE INCLUDED IN THIS SET OF PLANS

STANDARD ROADWAY DRAWINGS

DWG.	REV.	DESCRIPTION
10-100.00 S AND LEGE		D ROADWAY TITLE SHEET, ABBREVIATIONS,
RD-A-1	02-20-20	STANDARD ABBREVIATIONS A THROUGH L
RD-A-2		STANDARD ABBREVIATIONS M THROUGH Z
RD-L-1	02-20-20	STANDARD LEGEND

STANDARD LEGEND

RD-L-1A

STANDARD TRAFFIC DESIGN DRAWINGS

DWG.	REV.	DESCRIPTION
10-201.00	SIGNALS	
T-SG-2	06-27-16	LOOP LEAD-INS, CONDUIT AND PULL BOXES
T-SG-3	07-11-17	STANDARD NOTES AND DETAILS OF INDUCTIVE LOOPS
40.004.00	DE01011	
10-204.00	DESIGN -	TRAFFIC CONTROL
T-M-1	01-24-25	DETAILS OF PAVEMENT MARKINGS FOR CONVENTIONAL ROADS AND MARKING ABBREVIATIONS
T-M-3	01-24-25	MARKING STANDARDS FOR TRAFFIC ISLANDS, PAVED SHOULDERS AND MEDIANS FOR CONVENTIONAL ROADS
T-M-4	01-24-25	STANDARD INTERSECTION PAVEMENT MARKINGS
T-M-4A2		STANDARD RRFB COMMERCIAL AND STREET ENTRANCES
T-M-16	01-24-25	RUMBLE STRIPE INSTALLATION LAYOUT
T-M-16A	01-24-25	RUMBLE STRIPE DETAILS FOR EDGE OF PAVEMENT AND CENTERLINE
T-WZ-10	03-26-25	ADVANCE ROAD WORK SIGNING ON HIGHWAYS AND FREEWAYS
T-WZ-FAB1	03-26-25	FLASHING YELLOW ARROW BOARD

TYPE	YEAR	PROJECT NO.	SHEET NO.	
RESURF	2025	NH-55(34)	1A	
				1

SEALED BY

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

ROADWAY INDEX, STANDARD ROADWAY DRAWINGS AND STANDARD TRAFFIC DESIGN DRAWINGS

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY 64SR055-F8-003
(1)	208-01.05	BROOMING & DEGRASSING SHOULDERS	L.M.	9.9
(2)	303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	TON	1269
(3)	307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	TON	3124
(4)	307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	TON	1500
(5)	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	81
(6)	411-02.10	ACS MIX(PG70-22) GRADING D	TON	7014
(2)	411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	L.M.	6.9
(7)	415-01.01	COLD PLANING BITUMINOUS PAVEMENT	TON	9466
(8)	712-01	TRAFFIC CONTROL	LS	0.5
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	50
(9)	712-06	SIGNS (CONSTRUCTION)	S.F.	1105
8. 8	712-08.03	ARROW BOARD (TYPE C)	EACH	2
	713-16.01	CHANGEABLE MESSAGE SIGN UNIT	EACH	1
	716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	EACH	516
	716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	EACH	48
(10)	716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	EACH	564
(11)(12)(14)	716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	S.Y.	127
1)(12)(13)(14)	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	383
(11)(12)(14)	716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH	11
(11)(12)(14)	716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	L.F.	474
(11)(12)	716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	L.F.	163
(11)(12)(14)	716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	S.F.	96
(15)	716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	L.M.	35.4
(16)	716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	L.F.	1918
(16)	716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	EACH	2
(17)	716-09.83	CONTRAST PAVEMENT MARKING 6"	L.F.	1782
(18)	716-09.84	CONTRAST PAVEMENT MARKING 8"	L.F.	100
(19)	716-09.97	CONTRAST PAVEMENT SHADOW MARKING 6"	L.F.	72
(11)	716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	L.M.	17.2
(11)	716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	L.F.	700
- X	717-01	MOBILIZATION	LS	0.5
(20)	730-14.02	SAW SLOT	L.F.	568
(20)	730-14.03	LOOP WIRE	L.F.	1336

NO DIRT OR DEBRIS WILL BE LEFT ON SHOULDERS INCLUDING UNDER AND AROUND GUARDRAIL.
SHOULDERS SHOULD BE CLIPPED AS DIRECTED BY THE ENGINEER TO ALLOW FOR PROPER
DRAINAGE. THIS WORK TO BE PERFORMED BEFORE ALL OTHER OPERATIONS. THE CONTRACTOR
IS RESPONSIBLE FOR ENSURING COLD PLANING AND ASPHALT DEBRIS DOES NOT ENTER THE DRAINS
AND WILL BE RESPONSIBLE FOR CLEAN OUTS. WORK SHALL BE PERFORMED AT L.M. 0.00 - L.M 2.57
AND L.M. 3.22 - L.M. 3.59, INCLUDING CURB & GUTTER SECTION. SEE SHEET 2C, PAVEMENT MARKINGS,
FINAL PAVEMENT MARKING, NOTE 6 FOR MORE INFORMATION.

FOOTNOTES

TO BE USED AS DIRECTED BY THE ENGINEER

(1)

TO BE USED AS DIRECTED BY THE ENGINEER FOR SPOT LEVELING AREAS TO CORRECT ANY SCABBING EXPOSED AFTER MILLING OPERATION, USING 65 PSY THROUGHOUT.

ITEM TO BE USED FOR SPOR REPAIR, AND B-M2 MAY INCREASE/DECREASE AS DIRECTED BY THE ENGINEER. LOCATIONS TO BE DETERMINED BASED ON FIELD CONDITIONS, SEE SHEET 2B FOR VARIOUS LOCATIONS.

INCLUDES 2 TONS EXTRA WIDTH PAVING, DRIVEWAYS, COUNTY ROADS, FIELD ENTRANCES, BUSINESS ENTRANCES.

INCLUDES 404 TONS EXTRA WIDTH PAVING, DRIVEWAYS, COUNTY ROADS, FIELD ENTRANCES, BUSINESS ENTRANCES.

INCLUDES 357 TONS EXTRA WIDTH PAVING, DRIVEWAYS, COUNTY ROADS, FIELD ENTRANCES, BUSINESS ENTRANCES. THE CONTRACTOR SHALL MILL INTO SIDE ROADS TO A MINIMUM, A PAVER WIDTH, OR AS DIRECTED BY ENGINEER. INCLUDES 1393 TONS FOR SPOT REPAIR AREAS.

THE CONTRACTOR SHALL COMPLY WITH SECTION 712 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION REGARDING TEMPORARY TRAFFIC CONTROL AND THE CURRENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR IS RESPONSIBLE FOR THE STAKING OF CONSTRUCTION SIGNS. IN THE EVENT THAT A CONSTRUCTION AND/OR REGULATORY SIGN IS TEMPORARILY DESIGNATED NOT IN USE DURING THE CONSTRUCTION PHASE OF A PROJECT, THE CONTRACTOR SHALL CHOOSE A SIGN COVERING APPROVED BY THE ENGINEER. TEMPORARY SIGN COVERINGS SHALL NOT BE PAID FOR DIRECTLY BUT SHALL BE INCLUDED IN THE PRICE BID FOR ITEM NO.

712-06 SIGNS (CONSTRUCTION). SEE TRAFFIC CONTROL SIGN TABULATION (RESURFACING), SHEET 2F. THE CONTRACTOR SHALL REMOVE EXISTING SPM BY A METHOD THAT DOES NOT DAMAGE THE EXISTING ASPHALT. IF DAMAGE OCCURS DURING REMOVAL THE CONTRACTOR SHALL MAKE REPAIRS AT THEIR OWN EXPENSE BEFORE PAVING.

(11) ITEM TO BE USED FOR FINAL PAVEMENT MARKING ONLY.

(12) THE CONTRACTOR MAY ELECT TO SUBSTITUTE PREFORMED PLASTIC FOR THERMOPLASTIC. PREFORMED PLASTIC SHALL BE PAID FOR AT THE SAME UNIT PRICE AS BID FOR THERMOPLASTIC.

(13) ALL STOP BARS ON SIDE ROADS WILL BE RETRACED AS DIRECTED BY THE ENGINEER.

14) SEE PAVEMENT MARKING SHEETS 2G, 2G1 - 2G3. USE AS DIRECTED BY THE ENGINEER.

(15) ITEM TO BE USED FOR TEMPORARY PAVEMENT MARKING ONLY.

(16) ITEM TO BE USED FOR ALL CONCRETE SURFACES.

(17) FOR PERMANENT EDGE LINE ON CONCRETE SURFACES.

(18) FOR PERMANENT TURN LANE LINE MARKING ON CONCRETE SURFACES.

(19) FOR PERMANENT LANE LINE MARKING ON CONCRETE SURFACES. ITEM COST INCLUDES 36 LF WHITE MARKING AND 36 LF BLACK MARKING.

(20) TO BE USED FOR TRAFFIC SIGNALS AT SR-55 @ MECHANIC ST. INTERSECTION, LOCATED AT L.M. 1.51.

TYPE YEAR PROJECT NO.

RESURF 2025 NH-55(34) 2

SEALED BY

SEALED BY

AGRICULTURE

AGRICULTURE

NO. 108037


OF TENNISHING


OVA 1/2025


STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION


ESTIMATED ROADWAY QUANTITIES

THERE ARE NO GUARDRAIL ADJUSTMENTS WITHIN PROJECT LIMITS









SPOT LEVELING DETAIL
THE CONTRACTOR IS TO ENSURE A FLUSH TRANSITION WITH EXISTING PAVEMENT VARIES 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
EXISTING BASE VARIABLE
PROPOSED SPOT LEVELING AS DIRECTED BY THE ENGINEER (NOT TO SCALE)

SHEE NO

YEAR

2025

RESURF

PROJECT NO.

NH-55(34)

SEALED BY

NOT TO SCALE

STATE OF TENNESSEE

DEPARTMENT OF TRANSPORTATION

TYPICAL


SECTIONS AND

PAVEMENT

SCHEDULE

9/24/2025

ADDITIONAL COLD PLANING FOR SPOT REPAIR (AS DIRECTED BY THE ENGINEER)							
LOCATION	LENGTH	WIDTH	DEPTH	REPLACEMENT MIX (BM2, D, ETC.)	COMMENTS		
L.M. 1.16 TO 1.85 LT & RT	3650 LF	23.0"	2"	BM2			
L.M. 3.22 TO 3.30 RT	422 LF	11.5"	2"	BM2			
L.M. 3.88 BRIDGE END LT & RT	1000 LF	33.0"	2"	BM2			





GRADING

- (1) ANY AREA THAT IS DISTURBED OUTSIDE LIMITS OF CONSTRUCTION DURING THE LIFE OF THIS PROJECT SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
- (3) THE CONTRACTOR SHALL NOT DISPOSE OF ANY MATERIAL EITHER ON OR OFF STATE-OWNED R.O.W. IN A REGULATORY FLOOD WAY AS DEFINED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) WITHOUT APPROVAL BY FEMA. ALL MATERIAL SHALL BE DISPOSED OF IN UPLAND (NON-WETLAND) AREAS AND ABOVE ORDINARY HIGH WATER OF ANY ADJACENT WATERCOURSE. THIS DOES NOT ELIMINATE THE NEED TO OBTAIN ANY OTHER LICENSES OR PERMITS THAT MAY BE REQUIRED BY ANY OTHER FEDERAL. STATE OR LOCAL AGENCY.

MISCELLANEOUS

- (2) THE CONTRACTOR SHALL BE REQUIRED TO REMOVE AND RESET MAILBOXES AND POSTS WHERE AND AS DIRECTED BY THE ENGINEER. COST TO BE INCLUDED IN PRICE BID FOR OTHER CONSTRUCTION ITEMS.
- (3) NOTHING IN THE GENERAL NOTES OR SPECIAL PROVISIONS SHALL RELIEVE THE CONTRACTOR FROM HIS RESPONSIBILITIES TOWARD THE SAFETY AND CONVENIENCE OF THE GENERAL PUBLIC AND THE RESIDENTS ALONG THE PROPOSED CONSTRUCTION AREA.

PAVEMENT MARKINGS

TEMPORARY PAVEMENT MARKINGS ON INTERMEDIATE LAYERS

(2) TEMPORARY PAVEMENT LINE MARKINGS ON INTERMEDIATE LAYERS OF PAVEMENT SHALL BE REFLECTIVE TAPE OR REFLECTORIZED PAINT INSTALLED TO PERMANENT STANDARDS AT THE END OF EACH DAY'S WORK. SHORT, UNMARKED SECTIONS SHALL NOT BE ALLOWED. THESE MARKINGS WILL BE MEASURED AND PAID FOR UNDER ITEM NO. 716-05.20, PAINTED PAVEMENT MARKING (6" LINE), L.M.

FINAL PAVEMENT MARKING

- (6) THE CONTRACTOR WILL BE REQUIRED TO PERFORM THE FOLLOWING WORK:
 - a. BROOMING & DE-GRASSING SHOULDERS SHALL INCLUDE CLIPPING OF MATERIAL INTERFERING WITH PROPER DRAINAGE OF ROADWAY (INCLUDING PAVED AND GRAVEL SHOULDERS), AS DIRECTED BY THE ENGINEER.
 - b. ALL MATERIAL FROM CLIPPING, BROOMING AND DE-GRASSING SHOULDERS SHALL BE PICKED UP, REMOVED AND PROPERLY DISPOSED AS DIRECTED BY THE ENGINEER.
 - c. ALL COSTS ASSOCIATED WITH PICKING UP, REMOVAL AND PROPER DISPOSAL SHALL BE PAID FOR UNDER ITEM NO. 208-01.05.
 - d. REMOVE ALL GARBAGE AND CONSTRUCTION DEBRIS FROM PROJECT. THE COST FOR THIS WILL BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF CONSTRUCTION.
- (8) PERMANENT PAVEMENT LINE MARKINGS SHALL BE 6" ENHANCED FLATLINE THERMOPLASTIC INSTALLED TO PERMANENT STANDARDS AT THE END OF EACH DAY'S WORK. SHORT UNMARKED SECTIONS SHALL NOT BE ALLOWED. PAVEMENT MARKINGS WILL BE MEASURED AND PAID FOR UNDER ITEM NO. 716-12.02, ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE), L.M. THE CONTRACTOR SHALL HAVE THE OPTION OF USING REFLECTORIZED PAINT INSTALLED TO PERMANENT STANDARDS AT THE END OF EACH DAY'S WORK AND THEN INSTALLING THE PERMANENT MARKINGS AFTER THE PAVING OPERATION IS COMPLETED. THE TEMPORARY MARKINGS FOR THE FINAL SURFACE WILL NOT BE MEASURED AND PAID FOR DIRECTLY, BUT THE COSTS ARE TO BE INCLUDED IN THE PRICE BID FOR THE PERMANENT MARKINGS.
- (9) PERMANENT PAVEMENT LINE MARKINGS SHALL BE 8" ENHANCED FLATLINE THERMOPLASTIC INSTALLED TO PERMANENT STANDARDS AT THE END OF EACH DAY'S WORK. SHORT UNMARKED SECTIONS SHALL NOT BE ALLOWED. PAVEMENT MARKINGS WILL BE MEASURED AND PAID FOR UNDER ITEM NO. 716-12.03, ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE), L.F. THE CONTRACTOR SHALL HAVE THE OPTION OF USING REFLECTORIZED PAINT INSTALLED TO PERMANENT STANDARDS AT THE END OF EACH DAY'S WORK AND THEN INSTALLING THE PERMANENT MARKINGS AFTER THE PAVING OPERATION IS COMPLETED. THE TEMPORARY MARKINGS FOR THE FINAL SURFACE WILL NOT BE MEASURED AND PAID FOR DIRECTLY, BUT THE COSTS ARE TO BE INCLUDED IN THE PRICE BID FOR THE PERMANENT MARKINGS.

SNOWPLOWABLE REFLECTIVE PAVEMENT MARKERS

(19) REMOVE EXISTING SNOWPLOWABLE MARKERS PRIOR TO PAVING AND/OR COLD PLANING. REMOVE ALL ADHESIVES PRIOR TO PAVING. PATCH ANY HOLES OR DIVOTS RESULTING FROM THE REMOVAL OF A MARKER IN A MANNER WHICH ENSURES A UNIFORM PAVED SURFACE. PATCH WORK SHALL BE INCLUDED WITH COST OF OTHER ITEMS OF CONSTRUCTION.

PAVEMENT

PAVING

(2) THE CONTRACTOR SHALL BE REQUIRED TO COLD PLANE AND PAVE IN THE DIRECTION OF TRAFFIC.

RESURFACING

- (4) WHERE DIRECTED BY THE TDOT ENGINEER, THE CONTRACTOR SHALL BE REQUIRED TO SHAPE PUBLIC SIDE ROADS, BUSINESS ENTRANCES, AND PRIVATE DRIVES, AS WELL AS CLEANING OF EXISTING DRAINS BEFORE PLACING MATERIALS. ALL COSTS ARE TO BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF CONSTRUCTION.
- (5) ALL PUBLIC SIDE ROADS SHALL BE PAVED ONE PAVER WIDTH THROUGH THE INTERSECTION AS A MINIMUM. A SATISFACTORY TRANSITION FROM THE NEW PAVEMENT TO THE EXISTING GRADE OF THE INTERSECTING PUBLIC ROAD OR BUSINESS ENTRANCE SHALL BE PROVIDED. SHOULD THE PAVEMENT OF THE INTERSECTING PUBLIC ROAD BE DISTRESSED, THE RESURFACING WIDTH MAY BE INCREASED TO THE NORMAL RIGHT OF WAY LINE.
- (6) PRIVATE DRIVEWAYS, FIELD ENTRANCES, AND BUSINESS ENTRANCES WILL BE RESURFACED A PAVER WIDTH (LANE WIDTH) AS A MINIMUM. A PAVEMENT TAPER TO TRANSITION THE NEW PAVEMENT SHALL BE REQUIRED, IT SHALL BE BASED ON AN ADDITIONAL ONE FOOT OF WIDTH PER ONE INCH DEPTH OF PAVEMENT. IF THE SHOULDER IS NARROW ENOUGH THAT THE SUM OF THE SHOULDER AND THE TRANSITION ARE LESS THAN A PAVER WIDTH, THE TRANSITION SHALL OCCUR WITHIN THE PAVER WIDTH. IF THE SUM OF THE SHOULDER AND THE TRANSITION IS GREATER THAN A PAVER WIDTH (LANE WIDTH), THE TRANSITION SHALL OCCUR OUTSIDE OF THE PAVER WIDTH.
- ON CURB AND GUTTER SECTIONS, PUBLIC ROAD INTERSECTIONS SHALL BE RESURFACED TO THE END OF RADIUS. A SATISFACTORY TRANSITION FROM THE NEW PAVEMENT TO THE EXISTING GRADE OF THE INTERSECTING PUBLIC ROAD SHALL BE PROVIDED.
- 8) ON URBAN TYPICAL SECTIONS, (CURB AND GUTTER), RESIDENTIAL DRIVEWAYS AND BUSINESS ENTRANCES SHALL HAVE A MINIMUM WIDTH OF MATERIAL NOT LESS THAN ONE FOOT USED IN THE TRANSITION TO FEATHER THE PAVEMENT EDGE.
- (9) IN ALL CASES, THE LENGTH OF THE PAVEMENT TRANSITION, THE THICKNESS AND WIDTH OF THE RESURFACING AND ANY ADDITIONAL PAVEMENT MATERIALS SHALL BE AS DIRECTED BY THE TDOT ENGINEER.

SIGNING

(12) ALL SIGNS WHICH INTERFERE WITH CONSTRUCTION WILL BE RELOCATED OUTSIDE LIMITS OF CONSTRUCTION BY THE CONTRACTOR. UPON COMPLETION OF CONSTRUCTION, THE CONTRACTOR WILL RESTORE THE SIGNS TO ORIGINAL LOCATION. THE CONTRACTOR SHALL CHECK WITH THE REGIONAL TRAFFIC ENGINEER PRIOR TO MOVING ANY PERMANENT SIGNS.

SIGNALIZATION

- (11) THE PROJECT ENGINEER SHALL NOTIFY THE LOCAL GOVERNMENTAL AGENCY RESPONSIBLE FOR TRAFFIC CONTROL MAINTENANCE AT LEAST ONE DAY IN ADVANCE OF THE COLD PLANING ACTIVITY AT SIGNALIZED INTERSECTIONS WHERE DETECTOR LOOPS ARE ON THE PAVEMENT. THE MAINTAINING AGENCY WILL THEN BE RESPONSIBLE FOR DISCONNECTING THE LOOP DETECTORS AND MAKING ANY NECESSARY TIMING ADJUSTMENTS IN THE SIGNAL CONTROLLER PRIOR TO THE CONSTRUCTION.
- (12) THE PROJECT ENGINEER SHALL BE RESPONSIBLE FOR SUPPLYING THE CONTRACTOR WITH AS BUILT SIGNAL PLANS AT THE PRE-CONSTRUCTION CONFERENCE. THESE PLANS WILL PROVIDE THE CONTRACTOR WITH THE DESIRED LOCATION FOR DETECTOR LOOP REPLACEMENT.
- (14) LOOP REPLACEMENT SHALL BE IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS.

CONSTRUCTION WORK ZONE & TRAFFIC CONTROL

- (1) ADVANCED WARNING SIGNS SHALL NOT BE DISPLAYED MORE THAN FORTY-EIGHT (48) HOURS BEFORE PHYSICAL CONSTRUCTION BEGINS. SIGNS MAY BE ERECTED UP TO ONE WEEK BEFORE NEEDED, IF THE SIGN FACE IS FULLY COVERED.
- (2) IF THE CONTRACTOR MOVES OFF THE PROJECT, HE SHALL COVER OR REMOVE ALL UNNEEDED SIGNS AS DIRECTED BY THE ENGINEER. COSTS OF REMOVAL, COVERING, AND REINSTALLING SIGNS SHALL NOT BE MEASURED AND PAID FOR SEPARATELY, BUT ALL COSTS SHALL BE INCLUDED IN THE ORIGINAL UNIT PRICE BID FOR ITEM NO. 712-06, SIGNS (CONSTRUCTION) PER SQUARE FOOT.
- 3) A LONG TERM BUT SPORADIC USE WARNING SIGN, SUCH AS A FLAGGER SIGN, MAY REMAIN IN PLACE WHEN NOT REQUIRED PROVIDED THE SIGN FACE IS FULLY COVERED.
- (4) TRAFFIC CONTROL DEVICES SHALL NOT BE DISPLAYED OR ERECTED UNLESS RELATED CONDITIONS ARE PRESENT NECESSITATING WARNING.
- USE OF BARRICADES, PORTABLE BARRIER RAILS, AND DRUMS SHALL BE LIMITED TO THE IMMEDIATE AREAS OF CONSTRUCTION WHERE A HAZARD IS PRESENT. THESE DEVICES SHALL NOT BE STORED ALONG THE ROADWAY WITHIN THIRTY (30) FEET OF THE EDGE OF THE TRAVELED WAY BEFORE OR AFTER USE UNLESS PROTECTED BY GUARDRAIL, BRIDGE RAIL, AND/OR BARRIERS INSTALLED FOR OTHER PURPOSES FOR ROADWAYS WITH CURRENT ADT'S LESS THAN 1500 AND DESIGN SPEED OF LESS THAN 60 MPH. THIS DISTANCE SHALL INCREASE TO FORTY-FIVE (45) FEET FOR ROADWAYS WITH CURRENT ADT'S OF 1500 OR GREATER AND DESIGN SPEED OF 60 MPH OR GREATER OR ON THE OUTSIDE OF A HORIZONTAL CURVE. THESE DEVICES SHALL BE REMOVED FROM THE CONSTRUCTION WORK ZONE WHEN THE ENGINEER DETERMINES THEY ARE NO LONGER NEEDED. WHERE THERE IS INSUFFICIENT RIGHT-OF-WAY TO PROVIDE FOR THIS REQUIRED SETBACK, THE CONTRACTOR SHALL DETERMINE THE ALTERNATE LOCATIONS AND REQUEST THE ENGINEER'S APPROVAL TO USE THEM.
- THE CONTRACTOR SHALL NOT BE PERMITTED TO PARK ANY VEHICLES OR CONSTRUCTION EQUIPMENT DURING PERIODS OF INACTIVITY, WITHIN THIRTY (30) FEET OF THE EDGE OF PAVEMENT WHEN THE LANE IS OPEN TO TRAFFIC UNLESS PROTECTED BY GUARDRAIL, BRIDGE RAIL, AND/OR BARRIERS INSTALLED FOR OTHER PURPOSES FOR ROADWAYS WITH CURRENT ADT'S LESS THAN 1500 AND DESIGN SPEED OF LESS THAN 60 MPH. THIS DISTANCE SHALL BE INCREASED TO FORTY-FIVE (45) FEET FOR ROADWAYS WITH CURRENT ADT'S OF 1500 OR GREATER AND DESIGN SPEED OF 60 MPH OR GREATER OR ON THE OUTSIDE OF A HORIZONTAL CURVE. PRIVATELY OWNED VEHICLES SHALL NOT BE ALLOWED TO PARK WITHIN THIRTY (30) FEET OF AN OPEN TRAFFIC LANE AT ANY TIME UNLESS PROTECTED AS DESCRIBED ABOVE FOR ROADWAYS WITH CURRENT ADT'S LESS THAN 1500 AND DESIGN SPEED OF LESS THAN 60 MPH. THIS DISTANCE SHALL BE INCREASED TO FORTY-FIVE (45) FEET FOR ROADWAYS WITH CURRENT ADT'S OF 1500 OR GREATER AND DESIGN SPEED OF 60 MPH OR GREATER OR ON THE OUTSIDE OF A HORIZONTAL CURVE. WHERE THERE IS INSUFFICIENT RIGHT-OF-WAY TO PROVIDE FOR THIS REQUIRED SETBACK, THE CONTRACTOR SHALL DETERMINE THE ALTERNATE LOCATIONS AND REQUEST THE ENGINEER'S APPROVAL TO USE THEM.
- (7) ALL DETOUR AND CONSTRUCTION SIGNING SHALL BE IN STRICT ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- (9) THE CONTRACTOR SHALL BE RESPONSIBLE FOR STAKING CONSTRUCTION SIGNS. THE COST OF THIS WORK SHALL BE INCLUDED IN ITEM NO. 712-06, SIGNS (CONSTRUCTION), S.F.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2025	NH-55(34)	2C

AGRICULTURE

AGRICULTURE

AGRICULTURE

ON 108037

OF TENNERS

9/24/2025

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SPECIAL NOTES

PAVEMENT

RESURFACING

- (3) SURFACE IS TO BE CROWNED AS DIRECTED BY THE ENGINEER.
- (8) THE BITUMINOUS MATERIAL DESIGNATED TO RESTORE THE COLD PLANING AREA WILL BE PLACED WITHIN 96 HOURS OF THE COMMENCEMENT OF COLD PLANING OPERATIONS. COLD PLANING OPERATIONS WILL BE LIMITED TO AN AREA EQUAL TO THAT WHICH CAN BE COVERED WITH BITUMINOUS MATERIAL WITHIN THE TIME LIMITS SPECIFIED, EVEN IF COLD PLANING OPERATIONS MUST BE SUSPENDED UNTIL PAVING CATCHES UP.

PAVEMENT MARKING

- (1) UNDER THE DIRECTION OF THE ENGINEER, THE CONTRACTOR MAY BE REQUIRED TO APPLY PAINTED MARKINGS IN THE PAVEMENT AREAS NOT SPECIFICALLY DETAILED IN THE PLANS. PAYMENT WILL BE MADE AT THE UNIT PRICE BID FOR ITEM NO. 716-05.20.
- (2) UNDER THE DIRECTION OF THE ENGINEER, THE CONTRACTOR MAY BE REQUIRED TO APPLY PLASTIC MARKINGS IN THE PAVEMENT AREAS NOT SPECIFICALLY DETAILED IN THE PLANS. PAYMENT WILL BE MADE AT THE UNIT PRICE BID FOR ITEM NO. 716-12.02.

SIGNS

(1) IF THE CONTRACTOR ELECTS TO UTILIZE SIGNPOST ANCHORS (STUBS) FOR SIGN ERECTION, THESE SHALL BE REMOVED WHEN THE SIGNS ARE REMOVED TO AVOID FUTURE DAMAGE TO MOWERS OR OTHER MACHINERY.

MISCELLANEOUS

(4) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ANY SIGNS AND MAILBOXES DURING THE OPERATION. ANY SIGNS OR MAILBOXES DAMAGED AS A RESULT OF THE OPERATIONS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE

CONSTRUCTION WORK ZONE & TRAFFIC CONTROL

(1) THE CONTRACTOR SHALL KEEP TWO TRAFFIC LANES, ONE IN EACH DIRECTION, OPEN TO TRAFFIC DURING NON-WORK HOURS OR NON-WORK DAYS.

BRIDGE

(1) THE CONTRACTOR SHOULD TAKE EXTREME CARE WHEN COLD PLANING THE EXISTING ASPHALT OFF BRIDGE DECK, SO AS NOT TO DAMAGE THE EXISTING DECK SEALANT AND/OR EXPANSION JOINT MEMBERS (STEEL PLATES, BARS, AND/OR HEADERS). IF DAMAGE DOES OCCUR, THE CONTRACTOR SHALL BE RESPONSIBLE FOR NECESSARY REPAIRS ON ALL DAMAGED MEMBERS TO THE SATISFACTION OF THE PROJECT ENGINEER AT NO ADDITIONAL COST.

WORK RESTRICTIONS

(1) CONSTRUCTION ACTIVITIES SHALL NOT INTERFERE WITH SCHOOL OR WORK TRAFFIC EITHER AM OR PM OR AS DIRECTED BY THE ENGINEER. NO CONSTRUCTION ACTIVITIES ALLOWED DURING THE JACK DANIEL'S BBQ WORLD CHAMP., THE 2ND WEEK OF OCTOBER.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2025	NH-55(34)	2D

SEALED BY

SEALED BY

AGRICULTURE

AGRICULTURE

NO. 108031

9/24/2025

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SPECIAL NOTES

ENVIRONMENTAL NOTES

ENVIRONMENTAL GENERAL NOTES

NATURAL RESOURCES

- (4) THE OPERATION OF EQUIPMENT IN WATERS OF THE STATE/U.S., INCLUDING WETLANDS AND EPHEMERAL, INTERMITTENT, AND PERENNIAL STREAMS. IS NOT ALLOWED.
- (9) THE CONTRACTOR SHALL TAKE APPROPRIATE STEPS PRIOR TO ANY CONSTRUCTION AND MAINTENANCE ACTIVITIES TO ENSURE THAT ENVIRONMENTAL FEATURES (E.G., STREAMS, WETLANDS, SPRINGS, ETC.) ARE NOT IMPACTED BEYOND PERMITTED LOCATIONS. IF THE CONTRACTOR OR TDOT INSPECTOR IS UNSURE OF THE IDENTITY OF AN ENVIRONMENTAL FEATURE, THE INSPECTOR SHALL CONTACT THE TDOT REGION ENVIRONMENTAL TECH GROUP IMMEDIATELY.

SPECIES

- (11) SHOULD CLIFF SWALLOW OR BARN SWALLOW NESTS, EGGS, OR BIRDS (YOUNG AND ADULTS) BE PRESENT, THE CONTRACTOR SHALL CONTACT THE REGIONAL ECOLOGY OFFICE TO DETERMINE IF SEASONAL RESTRICTIONS WILL BE NECESSARY. GENERALLY, BIRDS, NESTS, AND EGGS MAY NOT BE DISTURBED BETWEEN APRIL 15 AND JULY 31. FROM AUGUST 1 TO APRIL 14, NESTS CAN BE REMOVED OR DESTROYED SO LONG AS BIRDS OR EGGS ARE NOT PRESENT, AND MEASURES IMPLEMENTED TO PREVENT FUTURE NEST BUILDING AT THE SITE (I.E., CLOSING OFF AREA USING NETTING).
- (12) IF THE REMOVAL OF ANY TREES WITH A DIAMETER AT BREAST HEIGHT (DBH) GREATER THAN 3 INCHES IS DEEMED NECESSARY THE TDOT SUPERVISOR SHALL CONTACT THE TDOT ENVIRONMENTAL DIVISION, ECOLOGY SECTION IMMEDIATELY.

PERMITS, PLANS & RECORDS

(15) IF A CHANGE IN PROJECT SCOPE OCCURS DURING CONSTRUCTION, INCLUDING VALUE ENGINEERING, THE TDOT PERMIT SECTION SHALL BE CONTACTED TO DETERMINE WHETHER PERMIT REVISIONS ARE NEEDED. THE ENGINEERING PRODUCTION SUPPORT DIVISION SHALL BE CONTACTED TO DETERMINE IF ANY PLAN REVISIONS ARE NEEDED.

ENVIRONMENTAL

(20) EXCEPT AS OTHERWISE SPECIFIED, THERE ARE NO KNOWN SPECIAL ENVIRONMENTAL FACTORS PRESENT ON THIS PROJECT THAT INDICATE A NEED FOR SEASONAL LIMITATIONS ON THE CLEARING, GRUBBING, EXCAVATION, GRADING, CUTTING OR FILLING OPERATIONS OR ON THE TOTAL AREA OF EXPOSED SOIL.

ENVIRONMENTAL SPECIAL NOTES

ENVIRONMENTAL

(1) STAFF FROM THE TDOT ENVIRONMENTAL DIVISION COMPLIANCE AND FIELD SERVICES OFFICE SHALL BE INVITED TO ALL PRE-CONSTRUCTION MEETINGS.

ECOLOGY

- (2) STAFF FROM THE TDOT ENVIRONMENTAL DIVISION OR A DESIGNEE SHALL ADVISE THE CONTRACTOR DURING THE PRE-CONSTRUCTION MEETING WHEN ENVIRONMENTAL DIVISION PERSONNEL OR A DESIGNATED CONSULTANT WILL NEED TO BE ONSITE FOR WORK BEING DONE WHICH COULD AFFECT WATERS OF THE STATE/U.S. OR SPECIES.
- (3) STAFF FROM THE TDOT ENVIRONMENTAL DIVISION OR A DESIGNEE SHALL ATTEND THE PRE-CONSTRUCTION MEETING FOR ALL PROJECTS WHICH HAVE THREATENED OR ENDANGERED SPECIES OR CRITICAL HABITAT PROXIMAL TO SCHEDULED WORK. THIS WILL PROVIDE THE OPPORTUNITY TO ENSURE THAT PERSONNEL INCLUDING THE CONTRACTOR'S PERSONNEL AND SUBCONTRACTORS ARE MADE AWARE OF THE NECESSARY PRECAUTIONS THAT MUST BE FOLLOWED.
- (4) ALL PROJECTS WITH LEGALLY PROTECTED SPECIES OR CRITICAL HABITAT IDENTIFIED SHALL HAVE MEASURES IN PLACE TO CONTAIN CONCRETE DUST, CEMENT DUST AND ALL OTHER MATERIALS. THESE MATERIALS ARE NOT ALLOWED TO ENTER WATERS OF THE STATE/U.S.

SCOPE OF WORK

(6) THIS PROJECT INCLUDES COLD PLANING AND 411D, STRIPING, TRAFFIC CONTROL AND BROOMING AND DEGRASSING SHOULDERS.

EROSION PREVENTION AND SEDIMENT CONTROL GENERAL NOTES

DISTURBED AREA

(1) IF DISTURBED ACREAGE IS EQUAL TO ONE ACRE OR MORE, PLEASE CONTACT TDOT ENVIRONMENTAL DIVISION, PERMITS SECTION AS SOON AS POSSIBLE BECAUSE AN NPDES PERMIT WILL BE REQUIRED.

SEDIMENT CONTROL


- 6) EPSC MEASURES SHALL BE INSTALLED AND FUNCTIONAL PRIOR TO ANY EARTH MOVING OPERATIONS AND SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD EXCEPT AS SUCH WORK MAY BE NECESSARY TO INSTALL EPSC MEASURES.
- (8) THE CONTRACTOR SHALL ESTABLISH AND MAINTAIN A PROACTIVE METHOD TO PREVENT THE OFFSITE MIGRATION OR DEPOSIT OF SEDIMENT OFF THE PROJECT LIMITS (E.G. R.O.W., EASEMENTS, ETC.), INTO WATERS OF THE STATE/U.S., OR ONTO ROADWAYS USED BY THE GENERAL PUBLIC. IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFFSITE ACCUMULATIONS OF SEDIMENT THAT HAVE NOT REACHED A STREAM MUST BE REMOVED AT A FREQUENCY SUFFICIENT TO MINIMIZE OFFSITE IMPACTS (E.G., FUGITIVE SEDIMENT THAT HAS ESCAPED THE CONSTRUCTION SITE AND HAS COLLECTED IN A STREET MUST BE REMOVED SO THAT IT IS NOT SUBSEQUENTLY WASHED INTO STORM SEWERS AND STREAMS BY THE NEXT RAIN AND/OR SO THAT IT DOES NOT POSE A SAFETY HAZARD TO USERS OF PUBLIC STREETS). ARRANGEMENTS CONCERNING REMOVAL OF SEDIMENT ON ADJOINING PROPERTY MUST BE NEGOTIATED WITH THE ADJOINING PROPERTY OWNER BEFORE REMOVAL OF SEDIMENT.

GOOD HOUSEKEEPING MEASURES & WASTE DISPOSAL

- (29) THE CONTRACTOR SHALL ESTABLISH AND MAINTAIN A PROACTIVE METHOD TO PREVENT LITTER AND CONSTRUCTION WASTES FROM ENTERING WATERS OF THE STATE/U.S. THESE MATERIALS SHALL BE REMOVED FROM STORMWATER EXPOSURE PRIOR TO ANTICIPATED STORM EVENTS OR BEFORE BEING CARRIED OFFSITE BY WIND, OR OTHERWISE PREVENTED FROM BECOMING A POLLUTANT SOURCE FOR STORMWATER DISCHARGES. AFTER USE, MATERIALS USED FOR EPSC SHALL BE REMOVED FROM THE SITE.
- (30) THE CONTRACTOR SHALL TAKE APPROPRIATE STEPS TO ENSURE THAT PETROLEUM PRODUCTS OR OTHER CHEMICAL POLLUTANTS ARE PREVENTED FROM ENTERING WATERS OF THE STATE/U.S. ALL EQUIPMENT REFUELING, SERVICING, AND STAGING AREAS SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL LAWS, RULES, REGULATIONS, AND ORDINANCES, INCLUDING THOSE OF THE NATIONAL FIRE PROTECTION ASSOCIATION. APPROPRIATE CONTAINMENT MEASURES FOR THESE AREAS SHALL BE USED.
- (31) CONTRACTORS SHALL PROVIDE DESIGNATED TRUCK WASHOUT AREAS ON THE SITE. THESE AREAS MUST BE SELF CONTAINED, NOT CONNECTED TO ANY STORMWATER OUTLET OF THE SITE, AND PROPERLY SIGNED. WASH DOWN OR WASTE DISCHARGE OF CONCRETE TRUCKS SHALL NOT BE PERMITTED ONSITE UNLESS PROPER SETTLEMENT AREAS HAVE BEEN PROVIDED IN ACCORDANCE WITH BOTH STATE AND FEDERAL REGULATIONS.
- (32) WHEEL WASH WATER SHALL BE COLLECTED AND ALLOWED TO SETTLE OUT SUSPENDED SOLIDS PRIOR TO DISCHARGE. WHEEL WASH WATER SHALL NOT BE DISCHARGED DIRECTLY INTO ANY STORMWATER SYSTEM OR STORMWATER TREATMENT SYSTEM.
- (33) IF PORTABLE SANITARY FACILITIES ARE PROVIDED ON CONSTRUCTION SITES, SANITARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS IN A TIMELY MANNER BY A LICENSED WASTE MANAGEMENT CONTRACTOR OR AS REQUIRED BY ANY REGULATIONS. THE CONTRACTOR SHALL OBTAIN ANY AND ALL NECESSARY PERMITS TO DISPOSE OF SANITARY WASTE.

- 34) ONLY CONSTRUCTION PRODUCTS NEEDED SHALL BE STORED ONSITE BY THE CONTRACTOR. THE CONTRACTOR SHALL STORE ALL MATERIALS UNDER COVER AND IN APPROPRIATE CONTAINERS. PRODUCTS MUST BE STORED IN ORIGINAL CONTAINERS AND LABELED. MATERIAL MIXING SHALL BE CONDUCTED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. THE CONTRACTOR'S RESPONSIBLE PARTY SHALL INSPECT MATERIALS STORAGE AREAS REGULARLY TO ENSURE PROPER USE AND DISPOSAL.
- (35) WHEN POSSIBLE, ALL PRODUCTS SHALL BE USED COMPLETELY BEFORE PROPERLY DISPOSING OF THE CONTAINER OFFSITE. THE MANUFACTURER'S DIRECTIONS FOR DISPOSAL OF MATERIALS AND CONTAINERS SHALL BE FOLLOWED.
- (36) ALL PAINT CONTAINERS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT SHALL BE DISPOSED OF ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS AND APPLICABLE STATE AND LOCAL REGULATIONS.
- (37) ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN A MANNER WHICH IS COMPLIANT WITH LOCAL OR STATE REGULATIONS. SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES, AND THE INDIVIDUAL DESIGNATED AS THE CONTRACTOR'S RESPONSIBLE PARTY SHALL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED. THE CONTRACTOR SHALL OBTAIN ANY AND ALL NECESSARY PERMITS TO DISPOSE OF HAZARDOUS MATERIAL.
- (38) OPEN BURNING IS PROHIBITED UNLESS IT IS SPECIFICALLY ALLOWED BY LAW. IF ALLOWED, NATURAL VEGETATION, TREES, AND UNTREATED LUMBER SHALL BE THE ONLY MATERIALS THAT CAN BE OPEN BURNED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL APPLICABLE STATE AND LOCAL PERMITS PRIOR TO ANY BURNING.
- (39) DISPOSAL OF ONSITE VEGETATION AND TREES BY CHIPPING THEM INTO MULCH IS PREFERABLE TO OPEN BURNING. THIS MULCH MAY BE USED AS AN ONSITE SOIL STABILIZATION MEASURE WHERE APPROPRIATE.
- (40) WASTE MATERIAL (EARTH, ROCK, ASPHALT, CONCRETE, ETC.) NOT REQUIRED FOR THE CONSTRUCTION OF THE PROJECT WILL BE DISPOSED OF BY THE CONTRACTOR. IMPACTS TO WATERS OF THE STATE/U.S. SHALL BE AVOIDED IF POSSIBLE. IF UNAVOIDABLE, THE CONTRACTOR WILL OBTAIN ANY AND ALL NECESSARY PERMITS INCLUDING, BUT NOT LIMITED TO NPDES, AQUATIC RESOURCES ALTERATION PERMIT(S), CORPS OF ENGINEERS SECTION 404 PERMITS, AND TVA SECTION 26A PERMITS TO DISPOSE OF WASTE MATERIALS.

TYPE	YEAR	PROJECT NO.	NO.
RESURF	2025	NH-55(34)	2E



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ENVIRONMENTAL NOTES


ENVIRONMENTAL NOTES (CONT.)

EROSION PREVENTION AND SEDIMENT CONTROL GENERAL NOTES

SPILL PREVENTION, MANAGEMENT & NOTIFICATION

- (44) ALL ONSITE VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE AND SPILLS.
- (45) FOR ALL HAZARDOUS MATERIALS STORED ONSITE, THE MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEAN UP SHALL BE CLEARLY POSTED. SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES AND THE LOCATIONS OF THE INFORMATION AND CLEANUP SUPPLIES.
- (46) APPROPRIATE CLEANUP MATERIALS AND EQUIPMENT SHALL BE MAINTAINED BY THE CONTRACTOR IN THE MATERIALS STORAGE AREA ONSITE AND UNDER COVER. SPILL RESPONSE EQUIPMENT SHALL BE INSPECTED AND MAINTAINED BY THE CONTRACTOR AS NECESSARY TO REPLACE ANY MATERIALS USED IN SPILL RESPONSE ACTIVITIES.
- (47) ALL SPILLS SHALL BE CLEANED IMMEDIATELY AFTER DISCOVERY AND THE MATERIALS DISPOSED OF PROPERLY. THE SPILL AREA SHALL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.
- (48) THE CONTRACTOR'S RESPONSIBLE PARTY SHALL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT THE SITE SUPERINTENDENT HAS HAD APPROPRIATE TRAINING FOR HAZARDOUS MATERIALS HANDLING, SPILL MANAGEMENT, AND CLEANUP.
- (49) IF AN OIL SHEEN IS OBSERVED ON SURFACE WATER (E.G. SETTLING PONDS, DETENTION PONDS, SWALES), ACTION SHALL BE TAKEN IMMEDIATELY TO REMOVE THE MATERIAL CAUSING THE SHEEN. THE CONTRACTOR SHALL USE APPROPRIATE MATERIALS TO CONTAIN AND ABSORB THE SPILL. THE SOURCE OF THE OIL SHEEN WILL ALSO BE IDENTIFIED AND REMOVED OR REPAIRED AS NECESSARY TO PREVENT FURTHER RELEASES.
- (50) FERTILIZERS SHALL BE APPLIED ONLY IN THE AMOUNTS SPECIFIED. ONCE APPLIED, FERTILIZERS SHALL BE WORKED INTO THE SOIL TO LIMIT THE EXPOSURE TO STORMWATER.
- (51) IF A SPILL OCCURS THE CONTRACTOR'S RESPONSIBLE PARTY SHALL BE RESPONSIBLE FOR COMPLETING THE SPILL REPORTING FORM AND FOR REPORTING THE SPILL TO THE TDOT PROJECT RESPONSIBLE PARTY. ALL SPILLS MUST BE REPORTED TO THE APPROPRIATE AGENCY, AND MEASURES SHALL BE TAKEN IMMEDIATELY TO PREVENT THE POLLUTION OF WATERS OF THE STATE/U.S., INCLUDING GROUNDWATER, SHOULD A SPILL OCCUR.
- (52) WHERE A RELEASE CONTAINING A HAZARDOUS SUBSTANCE IN AN AMOUNT EQUAL TO OR IN EXCESS OF A REPORTABLE QUANTITY ESTABLISHED UNDER EITHER 40 CFR 117 OR 40 CFR 302 OCCURS DURING A 24 HOUR PERIOD, SEE THE LATEST TENNESSEE GENERAL PERMIT NO. TNR100000 STORMWATER DISCHARGES FROM CONSTRUCTION ACTIVITIES SECTION 5.1 FOR REPORTING REQUIREMENTS.
- (53) CONTRACTOR'S BULK FUEL AND PETROLEUM PRODUCTS STORED ONSITE OR ADJACENT TO THE R.O.W. IN ABOVE GROUND STORAGE CONTAINERS WITH A COMBINED CAPACITY OF 1320 GALLONS OR MORE SHALL HAVE SECONDARY CONTAINMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING A SPILL PREVENTION CONTROL AND COUNTERMEASURE (SPCC) PLAN FOR THE BULK STORAGE AND BE SOLELY RESPONSIBLE FOR OBTAINING ANY NECESSARY LOCAL, STATE, AND FEDERAL PERMITS. THE SPCC PLAN AND/OR PERMITS SHALL BE KEPT ONSITE AND A COPY PROVIDED TO THE TDOT PROJECT RESPONSIBLE PARTY PRIOR TO STORING 1320 GALLONS ON SITE.

TYPE	YEAR	PROJECT NO.	SHEET NO.	
RESURF	2025	NH-55(34)	2E1	




STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ENVIRONMENTAL NOTES

IKA	TRAFFIC CONTROL SIGN TABULATION (RESURFACING)								
M.U.T.C.D.			SIZE			TOTAL	ITEM NO.		
SIGN	LEGEND \ DESCRIPTION	IN I	NCH	ES	S.F.	NUMBER	712-06		
NO.		L	X	W		REQUIRED	S.F.		
G20-1	ROAD WORK NEXT 11 MILES	48"	х	24"	8	1	8		
G20-2	END ROAD WORK	48"	х	24"	8	23	184		
W8-11	UNEVEN LANES	48"	х	48"	16	13	208		
W8-15	GROOVED PAVEMENT	48"	X	48"	16	13	208		
W8-15P	MOTORCYCLE PLAQUE	30"	х	24"	5	13	65		
W20-1	ROAD WORK 1 MILE	48"	х	48"	16	1	16		
W20-1	ROAD WORK 1/2 MILE	48"	х	48"	16	1	16		
W20-1	ROAD WORK 1000 FEET	48"	х	48"	16	1	16		
W20-1	ROAD WORK AHEAD	48"	x	48"	16	21	336		
W20-4	ONE LANE ROAD 1000 FT - PORTABLE	48"	х	48"	16	1	16		
W20-7A	FLAGGER SYMBOL - PORTABLE	48"	х	48"	16	1	16		
W21-2	FRESH OIL - PORTABLE	48"	Х	48"	16	1	16		
	JCTION SIGNING IS TO BE A MINIMUM. OTHER Y BE REQUITED DURING DIFFERENT PHASES.	SIGNS	AS D	IRECTE	BY THE	TOTAL	1105		

SIGNALIZATION TABULATION (RESURFACING)					
INTERSECTION	SAW SLOT (L.F.) 730-14.02	LOOP WIRE (L.F.) 730-14.03			
SR-55 @ MECHANIC ST.	568	1336			
TOTALS	568	1336			

	BRIDGE DECK RECOMMENDATIONS (RESURFACING)							
BRIDGE	BRIDGE LOCATION CROSSES BRIDGE BRIDGE BRIDGE							
NUMBER	LOG MILE	OVER/UNDER	LENGTH	RECOMMENDATIONS				
64SR0550001	0.310	EAST FORK MULBERRY CREEK	142' 6"	LEAVE AS IS (RESTRIPE EXISTING MARKINGS ONLY)				
64SR0550003	1.650	EAST FORK MULBERRY CREEK	142' 6"	COLD PLANE 1 1/4" OF THE EXISTING ASPHALT AND REPLACE WITH 1 1/4" OF NEW ASPHALT				
64SR0550005	2.770	GOOD BRANCH	40' 4"	LEAVE AS IS				
64SR0550007	3.880	EAST FORK MULBERRY CREEK	185' 3 9/16"	PROVIDE DECK REPAIR ITEM (BRIDGE SHEETS INCLUDED) (RESTRIPE EXISTING MARKINGS)				
				PROVIDE DECK REPAIR ITEM (BRIDGE SHEETS INCLUDED);				
64SR0550009	4.260	EAST FORK MULBERRY CREEK	180' 0"	REPLACE BRIDGE JOINTS (BRIDGE SHEETS INCLUDED)				
				(RESTRIPE EXISTING MARKINGS)				
64SR0550011	4.520	EAST FORK MULBERRY CREEK	38' 0"	PAVE WITH PLANS MIX/TREATMENT TYPE				



SEALED BY

AGRICULTURE

AGRICULTURE

NO. 108031

9/24/2025

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TABULATED QUANTITIES



STATE ROUTE 55 3.743-4.024 MOORE COUNTY

> REFERENCE STANDARD DRAWING T-M-3, T-M-4

> > FOR REFERENCE ONLY PROVIDED BY TDOT REGION 3 TRAFFIC


FOR REFERENCE ONLY


SEALED BY

STATE OF TENNESSEE **DEPARTMENT OF TRANSPORTATION**

> PAVEMENT MARKING **IMPROVEMENTS**

NOT TO SCALE





STATE ROUTE 55 1.751-1.885 MOORE COUNTY

> FOR REFERENCE ONLY

> > SEALED BY

REFERENCE STANDARD DRAWING T-M-3, T-M-4

FOR REFERENCE ONLY
PROVIDED BY
TDOT REGION 3 TRAFFIC

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING IMPROVEMENTS

NOT TO SCALE

	TYPE	YEAR	PROJECT NO.	SHEET NO.
RE	SURF	2025	NH-55(34)	2G2



STATE ROUTE 55 1.430-1.699 MOORE COUNTY

> REFERENCE STANDARD DRAWING T-M-1, T-M-4, T-M-4A2

> > FOR REFERENCE ONLY PROVIDED BY
> > TDOT REGION 3 TRAFFIC


FOR REFERENCE ONLY

SEALED BY

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

> PAVEMENT MARKING **IMPROVEMENTS**

NOT TO SCALE



STATE ROUTE 55 1.156-1.285 MOORE COUNTY

REFERENCE STANDARD DRAWING T-M-3, T-M-4

FOR REFERENCE ONLY
PROVIDED BY
TDOT REGION 3 TRAFFIC

FOR REFERENCE ONLY

SEALED BY

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING IMPROVEMENTS

NOT TO SCALE

UTILITY NOTES

- (2) UNLESS OTHERWISE NOTED. ALL UTILITY ADJUSTMENTS WILL BE PERFORMED BY THE UTILITY OR ITS REPRESENTATIVE. THE CONTRACTOR AND UTILITY OWNERS WILL BE REQUIRED TO COOPERATE WITH EACH OTHER IN ORDER TO EXPEDITE THE WORK REQUIRED BY THIS CONTRACT. ON CONTRACTS WHERE CONSTRUCTION STAKES, LINES, AND GRADES ARE CONTRACT ITEMS, THE CONTRACTOR WILL BE REQUIRED TO PROVIDE RIGHT-OF-WAY OR SLOPE STAKES, DITCH OR STREAM BED GRADES, OR OTHER ESSENTIAL SURVEY STAKING TO PREVENT CONFLICTS WITH THE HIGHWAY CONSTRUCTION. FREQUENTLY, THIS WILL BE REQUIRED AS THE FIRST ITEM OF WORK AND AT ANY LOCATION ON THE PROJECT DIRECTED BY THE ENGINEER.
- THE CONTRACTOR WILL PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION OF THIS PROJECT. IN THE EVENT THAT SPECIAL EQUIPMENT IS REQUIRED TO WORK OVER AND AROUND THE UTILITIES, THE CONTRACTOR WILL BE REQUIRED TO FURNISH SUCH EQUIPMENT. THE COST OF PROTECTING UTILITIES FROM DAMAGE AND FURNISHING SPECIAL EQUIPMENT WILL BE INCLUDED IN THE PRICE BID FOR OTHER ITEMS OF CONSTRUCTION.
- PRIOR TO SUBMITTING HIS BID. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR CONTACTING OWNERS OF ALL AFFECTED UTILITIES IN ORDER TO DETERMINE THE EXTENT TO WHICH UTILITY RELOCATIONS AND/OR ADJUSTMENTS WILL HAVE UPON THE SCHEDULE OF WORK FOR THE PROJECT. WHILE SOME WORK MAY BE REQUIRED 'AROUND' UTILITY FACILITIES THAT WILL REMAIN IN PLACE, OTHER UTILITY FACILITIES MAY NEED TO BE ADJUSTED CONCURRENTLY WITH THE CONTRACTOR'S OPERATIONS. ADVANCE CLEAR CUTTING MAY BE REQUIRED BY THE ENGINEER AT ANY LOCATION WHERE CLEARING IS CALLED FOR IN THE SPECIFICATIONS AND CLEAR CUTTING IS NECESSARY FOR A UTILITY RELOCATION. ANY ADDITIONAL COST WILL BE INCLUDED IN THE UNIT PRICE BID FOR THE CLEARING ITEM SPECIFIED IN THE PLANS.
- THE CONTRACTOR SHALL NOTIFY EACH INDIVIDUAL UTILITY OWNER OF HIS PLAN OF OPERATION IN THE AREA OF THE UTILITIES. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNERS AND REQUEST THEM TO PROPERLY LOCATE THEIR RESPECTIVE UTILITY ON THE GROUND. THIS NOTIFICATION SHALL BE GIVEN AT LEAST THREE (3) BUSINESS DAYS PRIOR TO COMMENCEMENT OF OPERATIONS AROUND THE UTILITY IN ACCORDANCE WITH TCA 65-31-106. NOTIFICATION BY CALLING THE TENNESSEE ONE CALL SYSTEM, INC AT 1-800-351-1111 WILL BE REQUIRED.

UTILITY OWNERS

TELEPHONE & FIBER:

AT&T

116 SOUTH CANNON AVE. MURFREESBORO, TN 37129 CONTACT: LEE KORNEGAY OFFICE PHONE: 615 848 2082 **CELL PHONE:**

Email: KK4096@ATT.COM

ELECTRIC:

SILICON RANCH CORPORATION

222 2ND AVE. S, SUITE 1900 NASHVILLE, TN 37201 CONTACT: REAGAN FARR OFFICE PHONE: 615 577 4786 **CELL PHONE:**

Email: INFO@SILICONRANCH.COM

WATER & SEWER:

METRO MOORE CO. UTILITY DEPT.

705 FAYETTEVILLE HIGHWAY LYNCHBURG, TN 37352 CONTACT: RONNIE CUNNINGHAM OFFICE PHONE: 931 307 6476

OFFICE PHONE: Email: RCUNNINGHAM.H2OMC@GMAIL.COM

FIBER:

POINT BROADBAND (FORMERLY MONSTER)

1791 O.G. SKINNER DR., SUITE A WEST POINT, GA 31833 CONTACT: ROBIN BROSTER OFFICE PHONE: 205 704 6423 **CELL PHONE:**

Email: ROBIN.BROSTER@POINT-**BROADBAND.COM**

ELECTRIC:

DUCK RIVER ELECTRIC MEM. CORP.

1411 MADISON ST. SHELBYVILLE, TN 37160 CONTACT: SCOTT DAHLSTROM

OFFICE PHONE: 931 680 5840

CELL PHONE:

Email: SDAHLSTROM@DREMC.COM

CABLE:

CHARTER COMMUNICATIONS

415 INDUSTRIAL BLVD. TULLAHOMA, TN 37388 CONTACT: BOBBY BRADLEY OFFICE PHONE: 931 461 4302

Email: BOBBY.BRADLEY@CHARTER.COM

GAS:

ENBRIDGE

CELL PHONE:

565 MARRIOTT DRIVE, SUITE 400 NASHVILLE, TN 37214

CONTACT: KELLY DALY OFFICE PHONE: 701 857 0813

CELL PHONE:

Email: KELLY.DALY@ENBRIDGE.COM

FIBER:

BEN LOMAND CONNECT

311 N. CHANCERY ST., P.O. BOX 670 MCMINNVILLE, TN 37111 CONTACT: RICHARD BOYD

OFFICE PHONE: 931 668 4131

CELL PHONE:

Email: RICHARDBOYD@BENLOMAND,.NET

ELECTRIC:

TENNESSEE VALLEY AUTHORITY

1101 MARKET STREET MR-4G CHATTANOOGA, TN 37402 CONTACT: STEPHEN WILLIAMS OFFICE PHONE:

CELL PHONE: 662 255 6272 Email: SEWILLIAMS@TVA.GOV

CABLE:

COMCAST

660 MAINSTREAM DR. NASHVILLE, TN 37228 CONTACT: KATELYN GROSS OFFICE PHONE:

CELL PHONE: 615 961 2453

Email: KATELYN GROSS@COMCAST.COM Email: NAS-NASHVILLECONSTRUCTIONBETTERMENTS@COMCAST.COM

GAS:

ATMOS ENERGY

810 CRESCENT CENTRE DR., SUITE 600


FRANKLIN, TN 37067

CONTACT: TAYLOR SANDERS OFFICE PHONE: 615 927 1596

CELL PHONE:

Email: TAYLOR.SANDERS@ATMOSENERGY.COM

SHEE NO. YEAR TYPE PROJECT NO. 2025 RESURF NH-55(34)



STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

> UTILITY NOTES UTILITY OWNERS

- DIFFERENCES IN ELEVATION BETWEEN ADJACENT ROADWAY ELEMENTS GREATER THAN 0.75 INCH AND NOT EXCEEDING 1.75 INCHES:
 - a. WARNING SIGNS, UNEVEN LANES (W8-11) AND/OR SHOULDER DROP-OFF WITH PLAQUE (W8-17 AND W8-17P), SHALL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN SIGNS SHALL BE 2.000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. WHERE UNEVEN PAVEMENT IS ENCOUNTERED, SIGNS SHALL BE PLACED ON EACH SIDE OF THE ROADWAY.
 - DIFFERENCES IN ELEVATION BETWEEN ADJACENT TRAFFIC LANES BEING UTILIZED BY TRAFFIC CAUSED BY ADDED PAVEMENT SHALL BE ELIMINATED WITHIN THREE WORKDAYS.
 - c. DIFFERENCES IN ELEVATION BETWEEN ADJACENT TRAFFIC LANES BEING UTILIZED BY TRAFFIC CAUSED BY COLD PLANING SHALL BE ELIMINATED WITHIN THREE WORKDAYS.
 - WHEN THE DIFFERENCE IN ELEVATION IS BETWEEN THE TRAFFIC LANE BEING UTILIZED BY TRAFFIC AND SHOULDER THE DIFFERENCE IN ELEVATION SHALL BE ELIMINATED WITHIN SEVEN WORKDAYS AFTER THE CONDITION IS CREATED.
- 2. DIFFERENCES IN ELEVATION BETWEEN ADJACENT ROADWAY ELEMENTS GREATER THAN 1.75 INCHES AND NOT EXCEEDING 6 INCHES. TRAFFIC IS NOT TO BE ALLOWED TO TRAVERSE THIS DIFFERENCE IN ELEVATION.
 - a. SEPARATION SHALL BE ACCOMPLISHED BY DRUMS, BARRICADES OR OTHER APPROVED DEVICES IN ACCORDANCE WITH THE **FOLLOWING:**
 - (1) WHERE POSTED SPEEDS ARE 50 MPH OR GREATER, SPACING OF THE PROTECTIVE DEVICES SHALL NOT EXCEED 100 FEET.
 - (2) WHERE POSTED SPEEDS ARE LESS THAN 50 MPH, THE MAXIMUM SPACING OF THE PROTECTIVE DEVICES IN FEE SHALL NOT EXCEED TWICE THE POSTED SPEED IN MILES PER HOUR OR 50 FEET. WHICHEVER SPACING IS GREATER
 - IF THE DIFFERENCE IN ELEVATION IS ELIMINATED OR DECREASED TO 2 INCHES OR LESS BY THE END OF EACH WORKDAY, CONES MAY BE USED DURING DAYLIGHT HOURS IN LIEU OF DRUMS, BARRICADES OR OTHER APPROVED PROTECTIVE DEVICES MENTIONED IN PARAGRAPH a, PROVIDED WARNING SIGNS ARE ERECTED. WARNING SIGNS (UNEVEN LANES AND/OR SHOULDER DROP-OFF) SHALL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN SIGNS SHALL BE 2,000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. WHERE UNEVEN PAVEMENT IS ENCOUNTERED, SIGNS SHALL BE PLACED ON EACH SIDE OF THE ROADWAY.
 - c. WHEN THE DIFFERENCE IN ELEVATION IS BETWEEN THE THROUGH TRAFFIC LANE AND THE SHOULDER AND THE ELEVATION DIFFERENCE IS LESS THAN 3 INCHES, THE CONTRACTOR MAY USE WARNING SIGNS AND/OR PROTECTIVE DEVICES AS APPLICABLE AND APPROVED BY THE REGIONAL TRAFFIC ENGINEER. SEE PARAGRAPH a REGARDING USE OF DRUMS, BARRICADES OR OTHER APPROVED PROTECTIVE DEVICES. WARNING SIGNS (UNEVEN LANES AND/OR SHOULDER DROP-OFF) WILL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN SIGNS SHALL BE 2,000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. WHERE UNEVEN PAVEMENT IS ENCOUNTERED, SIGNS SHALL BE PLACED ON EACH SIDE OF THE ROADWAY.

IN THESE SITUATIONS, THE CONTRACTOR SHALL LIMIT HIS OPERATIONS TO ONE WORK ZONE NOT EXCEEDING 2 MILES IN LENGTH UNLESS OTHERWISE NOTED ON THE PLANS OR APPROVED BY THE ENGINEER. ONCE THE CONTRACTOR BEGINS WORK IN A WORK ZONE, A CONTINUOUS OPERATION SHALL BE MAINTAINED UNTIL THE DIFFERENCE IN ELEVATION IS ELIMINATED. SIMULTANEOUS WORK ON SEPARATE ROADWAYS OF DIVIDED HIGHWAYS WILL BE CONSIDERED INDEPENDENTLY IN REGARD TO RESTRICTION OF WORK ZONE ACTIVITY.

- 3. DIFFERENCES IN ELEVATION BETWEEN ADJACENT ROADWAY ELEMENTS GREATER THAN 6 INCHES BUT NOT EXCEEDING 18 INCHES. THE CONTRACTOR, WITH THE ENGINEER'S APPROVAL, MAY UTILIZE ONE OF THE FOLLOWING:
 - a. THE CONTRACTOR SHALL ACCOMPLISH SEPARATION BY DRUMS, BARRICADES OR OTHER APPROVED DEVICES IN ACCORDANCE WITH THE FOLLOWING:
 - (1) WHERE POSTED SPEEDS ARE 50 MPH OR GREATER. SPACING OF THE PROTECTIVE DEVICES SHALL NOT EXCEED 100 FEET.
 - WHERE POSTED SPEEDS ARE LESS THAN 50 MPH, THE MAXIMUM SPACING OF THE PROTECTIVE DEVICES IN FEET SHALL NOT EXCEED TWICE THE POSTED SPEED IN MILES PER HOUR OR 50 FEET. WHICHEVER SPACING IS GREATER.

IN ORDER TO USE THIS METHOD, THE CONTRACTOR MUST REDUCE THE DIFFERENCE IN ELEVATION TO 6 INCHES OR LESS BY THE END OF THE WORKDAY THAT THE CONDITION IS CREATED.

- THE CONTRACTOR SHALL PROVIDE DRUMS, BARRICADES OR OTHER APPROVED SEPARATION DEVICES AS SPECIFIED IN PARAGRAPH a, AND CONSTRUCT A STONE WEDGE WITH A 4:1 SLOPE. OR FLATTER. TO ELIMINATE THE VERTICAL OFFSET IF THE LOWER ELEVATION IS AT OR BELOW SUBGRADE AT THE END OF EACH DAY.
- THE CONTRACTOR SHALL PROVIDE DRUMS, BARRICADES OR OTHER APPROVED SEPARATION DEVICES AS SPECIFIED IN PARAGRAPH a AND IF THE LOWER ELEVATION IS BASE STONE OR ASPHALT PAVEMENT, PLACEMENT OF SUBSEQUENT LAYERS OF PAVEMENT MUST BEGIN THE NEXT WORK DAY AND PROGRESS CONTINUOUSLY UNTIL THE DIFFERENCE IN ELEVATION IS ELIMINATED OR REDUCED TO 6 INCHES OR LESS.
- d. THE CONTRACTOR SHALL PROVIDE SEPARATION BY PORTABLE BARRIER RAIL

FOR PRECEDING CONDITIONS a, b, AND c, THE CONTRACTOR SHALL USE THE SHOULDER DROP-OFF WARNING SIGN WITH PLAQUE (W8-17 AND W8-17P). IT SHALL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN THE SIGNS SHALL BE 2,000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. IN THESE SITUATIONS. THE CONTRACTOR SHALL LIMIT HIS OPERATIONS TO ONE WORK ZONE NOT EXCEEDING 1 MILE IN LENGTH UNLESS OTHERWISE NOTED ON THE PLANS OR APPROVED BY THE ENGINEER ONCE THE CONTRACTOR BEGINS WORK IN A WORK ZONE, A CONTINUOUS OPERATION SHALL BE MAINTAINED UNTIL THE DIFFERENCE IS ELIMINATED. SIMULTANEOUS WORK ON SEPARATE ROADWAYS OF DIVIDED HIGHWAYS WILL BE CONSIDERED INDEPENDENTLY IN REGARD TO RESTRICTION OF WORK ZONE ACTIVITY.

FOR DIFFERENCES IN ELEVATION BETWEEN ADJACENT ROADWAY ELEMENTS GREATER THAN 18 INCHES.

SEPARATION WILL BE PROVIDED BY USE OF PORTABLE BARRIER RAIL

IN THIS SITUATION THE CONTRACTOR SHALL LIMIT HIS OPERATIONS TO ONE WORK ZONE NOT EXCEEDING 1 MILE IN LENGTH UNLESS OTHERWISE NOTED ON THE PLANS OR APPROVED BY THE ENGINEER. ONCE THE CONTRACTOR BEGINS WORK IN A WORK ZONE, A CONTINUOUS OPERATION SHALL BE MAINTAINED UNTIL THE DIFFERENCE IN ELEVATION IS ELIMINATED. SIMULTANEOUS WORK ON SEPARATE ROADWAYS OF DIVIDED HIGHWAYS WILL BE CONSIDERED INDEPENDENTLY IN REGARD TO RESTRICTION OF WORK ZONE ACTIVITY.

В.	IF THE DIFFERENCE IN ELEVATION IS WITHIN 30 FEET OF THE
	NEAREST TRAFFIC LANE BEING USED BY TRAFFIC CAUSED BY
	GRADING, EXCAVATION FOR UTILITIES, DRAINAGE STRUCTURES,
	UNDERCUTTING, ETC.:

- IF THE DIFFERENCE IN ELEVATION IS WITHIN 8 FEET OF THE NEAREST TRAFFIC LANE WITH DIFFERENCE IN ELEVATION GREATER THAN 0.75 INCH AND NOT EXCEEDING 2 INCHES.
 - WARNING SIGNS (UNEVEN LANES AND/OR SHOULDER DROP-OFF) SHALL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN SIGNS SHALL BE 2.000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. WHERE UNEVEN PAVEMENT IS ENCOUNTERED, SIGNS SHALL BE PLACED ON EACH SIDE OF THE ROADWAY.
- IF THE DIFFERENCE IN ELEVATION IS WITHIN 8 FEET OF THE NEAREST TRAFFIC LANE WITH DIFFERENCE IN ELEVATION GREATER THAN 2 **INCHES AND NOT EXCEEDING 6 INCHES:**
 - SEPARATION SHALL BE ACCOMPLISHED BY DRUMS. BARRICADES OR OTHER APPROVED DEVICES IN ACCORDANCE WITH THE FOLLOWING:
 - (1) WHERE POSTED SPEEDS ARE 50 MPH OR GREATER, SPACING OF THE PROTECTIVE DEVICES SHALL NOT EXCEED
 - (2) WHERE POSTED SPEEDS ARE LESS THAN 50 MPH THE MAXIMUM SPACING OF THE PROTECTIVE DEVICES IN FEET SHALL NOT EXCEED TWICE THE POSTED SPEED IN MILES PER HOUR OR 50 FEET. WHICHEVER SPACING IS GREATER.
- IF THE DIFFERENCE IN ELEVATION IS WITHIN 8 FEET OF THE NEAREST TRAFFIC LANE WITH DIFFERENCE IN ELEVATION GREATER THAN 6 INCHES:
 - SEPARATION SHALL BE ACCOMPLISHED BY DRUMS, BARRICADES OR OTHER APPROVED DEVICES IN ACCORDANCE WITH THE FOLLOWING:
 - (1) WHERE POSTED SPEEDS ARE 50 MPH OR GREATER, SPACING OF THE PROTECTIVE DEVICES SHALL NOT EXCEED 100 FEET.
 - WHERE POSTED SPEEDS ARE LESS THAN 50 MPH THE MAXIMUM SPACING OF THE PROTECTIVE DEVICES IN FEET SHALL NOT EXCEED TWICE THE POSTED SPEED IN MILES PER HOUR OR 50 FEET, WHICHEVER SPACING IS GREATER.
 - ELIMINATE VERTICAL OFFSET BY CONSTRUCTING A STONE WEDGE OR GRADING TO A 4:1 SLOPE, OR FLATTER, OR USE PORTABLE BARRIER RAIL.

THE CONTRACTOR SHALL SCHEDULE THE WORK SO AS TO MINIMIZE THE TIME TRAFFIC IS EXPOSED TO AN ELEVATION DIFFERENCE. ONCE THE CONTRACTOR BEGINS AN ACTIVITY THAT CREATES AN ELEVATION DIFFERENCE WITHIN 8 FEET OF A TRAFFIC LANE. THE ACTIVITY SHALL BE PURSUED AS A CONTINUOUS OPERATION UNTIL THE ELEVATION DIFFERENCE IS ELIMINATED.

C. IF THE DIFFERENCE IN ELEVATION IS FARTHER THAN 8 FEET FROM THE NEAREST TRAFFIC LANE BUT NOT MORE THAN 30 FEET FROM THE NEAREST TRAFFIC LANE:

SEPARATION SHALL BE ACCOMPLISHED BY DRUMS, BARRICADES OR OTHER APPROVED DEVICES IN ACCORDANCE WITH THE FOLLOWING:


- 1. WHERE POSTED SPEEDS ARE 50 MPH OR GREATER, SPACING OF THE PROTECTIVE DEVICES SHALL NOT EXCEED 100 FEET.
- 2. WHERE POSTED SPEEDS ARE LESS THAN 50 MPH, THE MAXIMUM SPACING OF THE PROTECTIVE DEVICES IN FEET SHALL NOT EXCEED TWICE THE POSTED SPEED IN MILES PER HOUR OR 50 FEET. WHICHEVER SPACING IS GREATER.

THE CONTRACTOR SHALL SCHEDULE THE WORK SO AS TO MINIMIZE THE TIME TRAFFIC IS EXPOSED TO AN ELEVATION DIFFERENCE. ONCE THE CONTRACTOR BEGINS AN ACTIVITY THAT CREATES AN ELEVATION DIFFERENCE. THE ACTIVITY SHALL BE PURSUED AS A CONTINUOUS OPERATION UNTIL THE ELEVATION DIFFERENCE IS ELIMINATED.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2025	NH-55(34)	T1

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

> PAVEMENT EDGE DROP-OFF NOTES TRAFFIC CONTROL



THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY:

Brian Egli 2025.09.05 11:31:30 -05'00'

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. THE SIGNATURE MUST BE VERIFIED ON THE ELECTRONIC DOCUMENTS.

TENNESSEE DEPARTMENT OF TRANSPORTATION 505 DEADERICK STREET, SUITE 1200 NASHVILLE, TN 37243 BRIAN K. EGLI, P.E. NO. 107196

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE OF TENN. CODE ANN. §62-2-306.

SHEET NAME	SHEET NO.
SIGNATURE SHEETINDEX OF DRAWINGS BRIDGE TABULATION. ESTIMATED QUANTITIES.	
REPAIRS NOTES & DÉTAILSPLAN VIEW REPAIRS LOCATIONSPHASE CONSTRUCTION	B-3 B-4
PLAN VIEW REPAIRS LOCATIONSPHASE CONSTRUCTION EXPANSION JOINT DETAILS	B-6
AT APPROACHES PAVEMENTS ENDS	B-7

YE	AR	PROJECT NO.	SHEET NO.
20)25	64S055-M3-003	STRUCTURE-SIGN 1

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

SIGNATURE SHEET

 PIN NO.:
 135034.00

 DESIGN BY:
 DATE: / /

 DRAWN BY:
 SILESHI ERGICHO
 DATE: 07/25

 SUPERVISED BY:
 KEVIN MARTINKO
 DATE: 07/25

 CHECKED BY:
 DATE: / /

INDEX OF DRAWINGS

SIGNATURE SHEET
INDEX OF DRAWINGS

SIGNATURE SHEET
INDEX OF DRAWINGS


B-1

BRIDGE TABULATION, ESTIMATED QUANTITIES,
REPAIRS NOTES & DETAILS
PHASE CONSTRUCTION
B-4
PLAN VIEW REPAIRS LOCATIONS
B-5
PHASE CONSTRUCTION
B-6
EXPANSION JOINT DETAILS
AT APPROACHES PAVEMENTS ENDS

BAST
B-7

INDEX OF REFERENCE DRAWINGS	<u>DWG.NO</u>
LAYOUT OF THE BRIDGE	M-211-64 M-211-67
SUPERSTRUCTURE	
SUPERSTRUCTURESTANDARD DRAWING REINFORCED CONCRETE	K-86-144
PAVEMENT AT THE BRIDGE ENDS REINFORCED CONCRETE PAVEMENT	STD-1-5
AT THE BRIDGE ENDS	210-1-2

PROJECT NO.		PROJECT NO. YEAR		SHEET NO.
64S055-M3-003		2025	B-1	
			REVISIONS	
NO.	DATE	BY	BRIEF	DESCRIPTION




STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION
INDEX OF DRAWINGS
64-SR55-3.88 & 64-SR55-4.26
OVER EAST FORK
MULBERRY CREEK
MOORE COUNTY
2025

TABULAT	ION OF BRIDGE RE	LATED WORK AND E	STIMATED QL	JANTITIES	
LOCATION OF BRIDGE AND BRIDGE NUMBER	REFERENCE DRAWINGS TO BE PRINTED WITH CONTRACT DRAWINGS	TYPE OF WORK	604-10.50 BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB) S.Y.	604-10.44 EXPANSION JOINT REPAIRS L.F.	604-10.53 CONCRETE REPAIR (PARTIAL DEPTH OF APPROACH PAVEMENT) S.Y.
64-SR55-3.88 OVER EAST FORK MULBERRY CREEK (64SR0550007)	M-211-64 M-211-67 K-86-144	BRIDGE DECK REPAIRS CONCRETE REPAIR	20		15
64-SR55-4.26 OVER EAST FORK MULBERRY CREEK (64SR0550009)	U-29-105 U-29-109 STD-1-5	BRIDGE DECK REPAIRS CONCRETE REPAIR EXPANSION JOINT REPAIRS	5	121	5
	T) T A L	25	121	20

P	PROJECT NO.		YEAR	SHEET NO.	
645	64S055-M3-003		2025	B-2	
			REVISIONS		
NO.	DATE	BY	BRIEF DESCRIPTION		

BRIDGE DECK REPAIR MATERIAL

ALL REPAIRS SHALL USE AN EXTENDED QUICK SET PATCHING MATERIAL FROM THE TDOT QUALIFIED PRODUCTS LIST: 13.004-RAPID SET CEMENTITIUOS PATCHING MATERIALS. PATCHING MATERIAL SHALL BE APPLIED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. MIX MUST MEET 3000 P.S.I. BEFORE OPENING TO TRAFFIC.



SKETCH SHOWING DECK REPAIR

NOTE: PARTIAL DEPTH DECK REPAIR ONLY REMOVE CONCRETE IN ALL DELAMINATED AREAS TO A DEPTH OF 34" BELOW THE TOP BAR OF THE TOP MAT OF REINFORCING STEEL.

NOTE: PARTIAL DEPTH REPAIRS

ALL REINFORCING STEEL IN THE AREAS OF THE DECK REPAIRS SHALL BE COMPLETELY CLEANED.

CLEANING SHALL BE DONE PRIOR TO PLACING NEW CONCRETE. AREAS OF CONCRETE REMOVAL


SHALL BE DESIGNATED BY PERSONNEL FROM THE HEADQUARTERS, BRIDGE INSPECTION AND REPAIR

OFFICE. INSPECTIONS TO DETERMINE AREAS OF DECK REPAIR SHALL BE SCHEDULED WITH THE

BRIDGE REPAIR OFFICE AT LEAST (3) DAYS IN ADVANCE.

THE COST OF CONCRETE, CONCRETE REMOVAL, LABOR, CLEANING REBAR AND ANY MISCELLANEOUS MATERIAL REQUIRED SHALL BE PAID FOR UNDER ITEM NO. 604-10.50 BRIDGE DECK REPAIR (PARTIAL DEPTH OF SLAB), S.Y.

NOTE: ITEM NOS. 604-10.50, BRIDGE DECK REPAIR (PARTIAL DEPTH OF SLAB) SHALL BE BID THIS MAY BE INCREASED, DECREASED OR ELIMINATED AS APPROVED BY THE ENGINEER.




CONCRETE APPROACH PAVEMENT REPAIR DETAILS:

NOTE: REMOVE CONCRETE TO A DEPTH OF 3/4" MINIMUM BELOW EXISTING REINFORCING STEEL OR TO SOUND CONCRETE. CONCRETE REMOVAL SHOULD BE TO A MINIMUM DEPTH OF 4". DEPTH FOR CONCRETE REMOVAL SHOULD NOT BE MORE THAN 6".

NOTE: COST OF SAW CUTTING, CONCRETE REMOVAL, COMPLETELY CLEANING EXPOSED REINFORCING STEEL, LABOR, AND ANY MISCELLANEOUS MATERIALS NECESSARY TO COMPLETE THE REPAIRS AS SHOWN SHALL BE INCLUDED IN ITEM NO. 604-10.53 CONCRETE REPAIR S.Y.

NOTE: ITEM NO.604-10.53, CONCRETE REPAIR (PARTIAL DEPTH OF APPROACH PVMT.)
MAY BE INCREASED, DECREASED OR ELIMINATED AS DIRECTED BY THE ENGINEER.



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

BRIDGE TABULATION,
ESTIMATED QUANTITIES
REPAIRS NOTES
AND DETAILS
64-SR55-3.88 & 64-SR55-4.26
OVER EAST FORK
MULBERRY CREEK
MOORE COUNTY
2025

 PIN NO.:
 135034.00

 DESIGN BY:
 DATE: //

 DRAWN BY:
 SILESHI ERGICHO
 DATE: 07/25

 SUPERVISED BY:
 KEVIN MARTINKO
 DATE: 07/25

 CHECKED BY:
 DATE: //

DENOTES:APPROXIMATE LOCATIONS OF BRIDGE DECK REPAIRS, (PARIAL DEPTH OF SLAB) OR CONCRETE REPAIR (PARTIAL DEPTH OF APPROACH PAVEMENT)

PIN NO.:

DESIGN BY:

DRAWN BY:

CHECKED BY:_

135034.00

SUPERVISED BY: KEVIN MARTINKO

SILESHI ERGICHO

DATE: //

DATE: 07/25

DATE: 07/25

DATE: //

B - 3


PROJECT NO.

SHEET NO.

YEAR

PHASE I CONSTRUCTION

(LOOKING AHEAD ON THE SURVEY)



PHASE II CONSTRUCTION

(LOOKING AHEAD ON THE SURVEY)

SEALED BY

N. K.

OMMERCE

OMMERCE

ON 107196

OF TEN 100 (105)

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PHASE CONSTRUCTION

64-SR55-3.88

OVER EAST FORK

MULBERRY CREEK

MOORE COUNTY

2025

PROJECT NO.

64S055-M3-003

NO. DATE BY

- -

- -

YEAR

REVISIONS

2025

SHEET NO.

B**-**4

BRIEF DESCRIPTION

 PIN NO.:
 135034.00


 DESIGN BY:
 DATE:
 / /

 DRAWN BY:
 SILESHI ERGICHO
 DATE:
 07/25


 SUPERVISED BY:
 KEVIN MARTINKO
 DATE:
 07/25

 CHECKED BY:
 DATE:
 / /

B - 4







STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

PLAN VIEW
REPAIRS LOCATIONS
64-SR55-4.26
OVER EAST FORK
MULBERRY CREEK
MOORE COUNTY
2025

DENOTES:APPROXIMATE EXPANSION JOINT REPAIRS LOCATIONS

DENOTES:APPROXIMATE LOCATIONS OF BRIDGE DECK REPAIRS, (PARIAL DEPTH OF SLAB) OR CONCRETE REPAIR (PARTIAL DEPTH OF APPROACH PAVEMENT)

PIN NO.:

DESIGN BY:

DRAWN BY:

CHECKED BY:

SUPERVISED BY:

135034.00

SILESHI ERGICHO

KEVIN MARTINKO

DATE: //


DATE: 07/25

DATE: 07/25

DATE: / /

PHASE I CONSTRUCTION

(LOOKING AHEAD ON THE SURVEY)




PHASE II CONSTRUCTION


(LOOKING AHEAD ON THE SURVEY)

PIN NO.:	135034.00		
DESIGN BY:		DATE:	11
DRAWN BY:	SILESHI ERGICHO	DATE:	07/2
SUPERVISED BY:	KEVIN MARTINKO	DATE:	07/2
CHECKED BY:		DATE:	//

F	PROJECT	NO.	YEAR	SHEET NO.	
64S055-M3-003		2025	B-6		
	REVISIONS				
NO.	DATE	BY	BRIEF DESCRIPTION		



STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION PHASE CONSTRUCTION
64-SR55-4.26
OVER EAST FORK
MULBERRY CREEK
MOORE COUNTY
2025



EXPANSION JOINT SYSTEM

 PROJECT NO.
 YEAR
 SHEET NO.

 64S055-M3-003
 2025
 B-7

 REVISIONS

 NO.
 DATE
 BY
 BRIEF DESCRIPTION

 - - -

- -

- -

- -

NOTE: THE EXISTING JOINT OPENING SHALL BE CAULKED WITH A BACKER ROD OF SUITABLE DIAMETER, THE ROD SHALL BE PLACED AT A DEPTH TO INSURE THE CORRECT WIDTH/DEPTH RATIO OF THE NEW JOINT SEALANT MATERIAL, BACKER ROD SHALL BE AS PER JOINT MANUFACTURERS RECOMMENDATIONS.

NOTE: FULL DEPTH OF ALL EXISTING JOINTS SHALL SHALL BE RESEALED WITH NEW JOINT SEALER.
THE NEW JOINT SEALER SHALL BE A COLD PUOR TWO PART SILICONE SEALER FROM QPL 5.001.


EXPANSION JOINT REPAIR NOTES:

THE JOINT HEADER SYSTEM SHALL BE FROM QPL 9.002. THE JOINT SEAL SYSTEM CONSISTS OF THE ELASTOMERIC HEADER MATERIAL AND A TWO-PART COLD POUR SILICONE SEALANT. THE CONTRACTOR SHALL ALSO HAVE THE OPTION OF USING A PRECOMPRESSED FOAM WITH SILICONE TOPPED PRODUCT (SIMILAR TO AND INCLUDING BEJS) FROM QPL 7.001 WITH AN APPROPRIATELY SIZED SEAL FOR THE JOINT OPENING, AND AN ELASTOMERIC CONCRETE FROM QPL 9.001. THE SYSTEM SHALL BE INSTALLED UNDER THE DIRECT SUPERVISION OF AN AUTHORIZED TECHNICIAN PROVIDED BY THE SYSTEM MANUFACTURER. THE TECHNICIAN MUST APPROVE ALL ASPECTS OF THE GEOMETRY AND PREPARATION OF THE JOINT LOCATIONS PRIOR TO ANY INSTALLATION OF THE JOINT SYSTEM MATERIALS. PRODUCTS FROM QPL 7.001 "ON A ROLL" AND "COMPRESSION ONLY" WILL NOT BE ALLOWED. THE TOP OF THE QPL 7.001 JOINT FILLER SHALL BE A MINIMUM OF 3/4 OF AN INCH BELOW THE ROADWAY SURFACE UNLESS THE MANUFACTURER REQUIRES A DEEPER DEPTH.

MANUFACTURERS SPECIFICATIONS AND INSTALLATION PROCEDURES SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR REVIEW PRIOR TO THE JOINT REPLACEMENT/REPAIR WORK. THE MANUFACTURER AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE WORKMANSHIP OF THE JOINT INSTALLATION.

PRIOR TO THE INSTALLATION OF THE NEW JOINT, THE EXISTING JOINT OPENING SHALL BE CLEANED OF ALL DIRT, DEBRIS, AND PRIOR CONSTRUCTION MATERIAL, ETC., THE FULL DEPTH OF THE OPENING. THE SURFACES WHERE THE NEW MATERIAL BONDS TO STAY IN PLACE, SHALL BE CLEANED PER MANUFACTURERS RECOMMENDATION, TO REMOVE ANY SUBSTANCES THAT WOULD INHIBIT BONDING.

THE COST FOR REMOVING THE OLD JOINT SYSTEM, INSTALLING THE NEW JOINT SYSTEM, LABOR, AND ANY MISCELLANEOUS MATERIALS NECESSARY TO INSTALL THE NEW EXPANSION JOINT, IS TO BE INCLUDED UNDER ITEM NUMBER 604-10.44, EXPANSION JOINT REPAIRS, L.F.



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT
DETAILS AT APPROACH
PAVEMENT ENDS
64-SR55-4.26
OVER EAST FORK
MULBERRY CREEK
MOORE COUNTY
2025

 PIN NO.:
 135034.00


 DESIGN BY:
 DATE: / /


 DRAWN BY:
 SILESHI ERGICHO
 DATE: 07/25


 SUPERVISED BY:
 KEVIN MARTINKO
 DATE: 07/25

 CHECKED BY:
 DATE: / /

AT PAVEMENT END







TYPICAL CROSS SECTION (LOOKING FORWARD ON SURVEY)

(TYP. BTWN. BEAMS

PH.I ONLY)

2'-71/2" JOINT @ SUPPORT DIAPHRAM

PHASE CONSTRUCTION

'(TYP. BTWN. BEAMS

PH. I ONLY)

☆ DENOTES: BARS A602E (PH. I) OR BARS A603E (PH. II) OR SERIES BARS A604E (PH. II) OR SERIES BARS A605E (PH. I) OR SERIES BARS A606E (PH. I) OR SERIES BARS A607E (PH. II) OR BARS A608E (PH. I) OR BARS A609E (PH. II) ♥ DENOTES: CUT-OFF BARS OMITTED @ MID-SPAN. SEE "PLAN OF MAIN REINFORCEMENT". ♦ DENOTES: BARS A500 (PH.I & II) OR BARS A501 (PH.I OR II) OR

BARS A600E

BARS A502 (PH. I) OR BARS A503 (PH. II)

4′-3"

W BARS A601E

3 SPA.@ 9" = 2'-3"

 $-2 - \frac{1}{2}$ " PLYWOOD SAW CUT LAYERS STAGGERED 1" DEEP - 1 1 P. , 10 P. . REINFORCING STEEL

(TYP. BETWEEN, BEAMS

3′-6"

@ PH.IONLY)

← PRECAST PRESTRESSED CONCRETE

 $(42" \times 36")$ BOX BEAM (TYP.)


2 SPA.@ 8'-3" = 16'-6"

SLAB CONSTRUCTION JOINT DETAIL

DECK CONCRETE POURING SEQUENCE: SLAB CONSTRUCTION JOINTS MAY BE LOCATED AT THE CONTRACTOR'S OPTION SUBJECT TO THE FOLLOWING:

1) NO CONSTRUCTION JOINT MAY BE LOCATED CLOSER THAN 10 FEET OR FURTHER THAN 15 FEET FROM AN INTERIOR SUPPORT. 2) THE SLAB IN THE MIDDLE SECTION OF BOTH ADJACENT SPANS MUST BE POURED TO WITHIN AT LEAST 15 FEET OF THE SUPPORTS EITHER PRIOR TO OR CONCURRENTLY WITH THE SLAB OVER AN INTERIOR SUPPORT.

ALL SLAB CONSTRUCTION JOINTS SHALL BE IN ACCORDANCE WITH THE SLAB CONSTRUCTION JOINT DETAIL SHOWN ABOVE.



(TYP. BETWEEN. BEAMS

@ PH.I ONLY)

-SEE DETAIL "X"

2 SPA.@ 10'-6" = 21'-0"

DEAD LOAD CORRECTION CURVE: THIS CURVE IS FOR DEAD LOAD SLAB AND ALL DEAD LOADS THAT ARE APPLIED AFTER SLAB IS IN PLACE AND SHOULD BE CORRECTED TO COMPENSATE FOR THE EFFECTS DUE TO VERTICAL CURVE. IF PRESTRESSED DECK PANELS ARE USED AND THE BEAMS ARE PROFILED AFTER PANELS ARE IN PLACE, REDUCE THE DEAD LOAD CORRECTION VALUES SHOWN BY 25%.

NOTE: THE CONTRACTOR SHALL OFFSET ANY REINFORCEMENT NECESSARY TO MAINTAIN 2" CLEARANCE TO PHASE CONSTRUCTION

NOTE: SEE SHEET U-29-113 FOR "PHASE REMOVAL & CONSTRUCTION SEQUENCE."


CON	IST. NO	. 64	005-3219	9-94
PF	ROJECT	NO.	YEAR	SHEET NO.
BR	-STP-5	5(8)	2010	
			REVISIONS	5
NO.	DATE	ВҮ	BRIEF	DESCRIPTION
-				
二				
\dashv			<u> </u>	
\blacksquare				
			······································	
\dashv				
		<u> </u>		

NOTE: NO PORTION OF THE PARAPET SHALL BE POURED UNTIL THE ENTIRE DECK SLAB IS IN PLACE.

NOTE: WHEN POURING SLAB, PROVISIONS SHALL BE MADE FOR SETTING REINFORCING STEEL FOR PARAPET. THE PARAPET SHALL NOT BE POURED UNTIL THE SLAB IS POURED AND CURED. ALSO SEE DRAWING NO. STD-1-1SS.

NOTE: THE CONTRACTOR IS SOLELY RESPONSIBLE FOR SUPPORTING THE BEAMS TO PREVENT DAMAGE DUE TO TWISTING OR OVERTURNING DURING ALL PHASES OF CONSTRUCTION. IT IS STRONGLY RECOMMENDED THAT THE TEMPORARY ERECTION DIAPHRAGMS BE INSTALLED PRIOR TO PLACING ANY LOADS ON THE GIRDERS, HOWEVER, TEMPORARY ERECTION DIAPHRAGMS MUST BE IN PLACE IN THE SPAN AT THE TIME THE SLAB IS POURED IN SAID SPAN.

NOTE: THE SUPPORT DIAPHRAGM AT THE BENT SHALL BE FORMED AND THE BOTTOM 15 INCHES POURED AS SOON AS POSSIBLE AFTER THE BEAMS HAVE BEEN SET. THE REMAINDER OF THE DIAPHRAGM SHALL BE POURED CONCURRENTLY WITH THE DECK SLAB. THE BEAMS SHALL ATTAIN AN AGE OF AT LEAST 90 DAYS PRIOR TO POURING THE REMAINDER OF THE SUPPORT DIAPHRAGMS AND DECK SLAB. ALL DIAPHRAGM CONCRETE SHALL BE INCLUDED IN THE QUANTITY FOR ITEM NO. 604-03.09.



ESTIMATED QUANTITIES

CLASS 'D'	STEEL BAR	EPOXY COATE
CONCRETE	REINFORCEMENT	REINFORCING
(BRIDGE DECK)	(BRIDGES)	STEEL
C.Y.	LBS.	LBS.
227	1,071	85,500

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE

STATE ROUTE 55 OVER EAST FORK MULBERRY CREEK STATION 140+67.50 LOG MILE 4.26 MOORE COUNTY 2010

CORRECT Edward P. Wasserman
ENGINEER OF STRUCTURES

U-29-109

DESIGNED BY MIN XU
DRAWN BY T- WISEMAN DATE 08-10 ____ DATE <u>08-10</u> SUPERVISED BY MBC/HMB ____ DATE 08-10 CHECKED BY MIN XU DATE __10-10

DEAD LOAD CORRECTION CURVE

