

GRADING QUANTITIES SHEET

COMPUTED BY: AUSTIN BIGGS
 CHECKED BY: MATT NEWMAN
 ROUTE OR STREET : S.R. 6

SHEET NO. 1 of 2
 PROJ. #:94004-3234-04
 COUNTY: WILLIAMSON

ESTIMATED GRADING QUANTITIES					
LOCATION	ROAD & DRAINAGE EXC. (UNCL.)	BORROW EXC.	EXCESS EXC.	EMB.	TOPSOIL
	COMMON - C.Y.	UNCL. - C.Y.	WASTE C.Y.		
S.R. 6	150			1048	159
EROSION CONTROL	107				
EXISTING PAVEMENT	350				
EXC. TOPSOIL	159				
TOTALS	766			1048	159

GRADING QUANTITIES SHEET

COMPUTED BY: AUSTIN BIGGS

CHECKED BY: MATT NEWMAN

ROUTE OR STREET : S.R. 6

SHEET NO. 2 of 2

PROJ. #: 94004-3234-04

COUNTY: WILLIAMSON

STATION	Exc. Uncl	Exc. ROCK	Emb. Uncl	Emb. ROCK	Exc. Uncl	Exc. ROCK	Emb. Uncl	Emb. ROCK
	S.F	S.F.	S.F.	S.F.	C.Y.	C.Y.	C.Y.	C.Y.
101+00.00	0		0		0	0	0	0
101+50.00	0		62		0	0	58	0
102+00.00	0		58		0	0	112	0
102+50.00	3		52		3	0	102	0
103+00.00	6		52		9	0	96	0
103+50.00	2		142		8	0	180	0
104+00.00	0		0		2	0	132	0
104+50.00	0		0		0	0	0	0
105+00.00	0		0		0	0	0	0
105+50.00	48		0		44	0	0	0
106+00.00	2		0		46	0	0	0
106+50.00	10		56		11	0	52	0
107+00.00	7		61		16	0	108	0
107+50.00	2		82		9	0	132	0
108+00.00	0		0		2	0	76	0
108+50.00	0		0		0	0	0	0
					150	0	1048	0
	Exc. Uncl	Exc. ROCK	Emb. Uncl	Emb. ROCK				
	C.Y.	C.Y.	C.Y.	C.Y.				