

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 1 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

ESTIMATED GRADING QUANTITIES									
DESCRIPTION	UNADJUSTED VOLUMES (CY)		ADJUSTED VOLUMES (CY)	BALANCE SUMMARY					
	EXC.	EMB.	EXC.	SHRINK = 20 % SWELL = 20 %					
MAINLINE	5623	2124	4499	EXC.	VS.	EMB.			
SIDE ROADS									
PVT. DRIVES, BUSINESS AND FIELD ENTRANCES	18	411	15						
INDEPENDENT DITCHES									
TEMPORARY CONSTRUCTION EXITS	36		29						
OFFSET BASIN	1867		1494						
TOPSOIL (EMB.)									
TOPSOIL (EXC.)									
TOPSOIL TOTALS (SEE TOPSOIL TABLE)							AVAILABLE	=	4739
ROCK (C.Y.) - OFFSET BASIN							TOTALS (C.Y.)		
EXC.	EMB.	EXC. (UNCL.)	EMB. (UNCL.)	EXC (COMMON)	EXC. (AVAIL.)	EXC. (ADJ.)			
1032		8576	2535	7544	7544	7274			
				WASTE MATERIAL	=	5687			

Mainline - SR-6

Material Name	End Areas	Unadjusted	Adjusted	Mult	Mass	Accum	Accum
Station		Volumes	Volumes	Factor	Ordinate	Unadj Vol	Adj Vol
	(sq. ft.)	(cu. yd.)	(cu. yd.)			(cu. yd.)	(cu. yd.)

624+00.00 EARTH

Excavation	27.4	0	0	1.00		0	0
Fill	0.0	0	0	1.00	0	0	0

624+08.00 EARTH

Excavation	38.4	10	10	1.00		10	10
Fill	22.6	3	3	1.00	7	3	3

624+25.00 EARTH

Excavation	39.9	25	25	1.00		35	35
Fill	29.9	17	17	1.00	15	20	20

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 2 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

624+27.11 EARTH

Excavation	39.7	3	3	1.00		38	38
Fill	31.0	2	2	1.00	16	22	22

624+50.00 EARTH

Excavation	39.0	33	33	1.00		71	71
Fill	46.1	33	33	1.00	16	55	55

625+00.00 EARTH

Excavation	62.2	94	94	1.00		165	165
Fill	52.6	91	91	1.00	19	146	146

625+50.00 EARTH

Excavation	68.5	121	121	1.00		286	286
Fill	77.7	121	121	1.00	19	267	267

626+00.00 EARTH

Excavation	37.6	98	98	1.00		384	384
Fill	131.6	194	194	1.00	-77	461	461

626+33.35 EARTH

Excavation	41.7	49	49	1.00		433	433
Fill	168.3	185	185	1.00	-213	646	646

626+50.00 EARTH

Excavation	45.9	27	27	1.00		460	460
Fill	164.2	103	103	1.00	-289	749	749

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 3 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

627+00.00 EARTH

Excavation	49.5	88	88	1.00		548	548
Fill	130.7	273	273	1.00	-474	1022	1022

627+50.00 EARTH

Excavation	53.1	95	95	1.00		643	643
Fill	76.5	192	192	1.00	-571	1214	1214

627+83.35 EARTH

Excavation	136.7	117	117	1.00		760	760
Fill	113.5	117	117	1.00	-571	1331	1331

628+00.00 EARTH

Excavation	145.6	87	87	1.00		847	847
Fill	94.8	64	64	1.00	-548	1395	1395

628+49.25 EARTH

Excavation	108.4	232	232	1.00		1079	1079
Fill	51.0	133	133	1.00	-449	1528	1528

628+50.00 EARTH

Excavation	108.6	3	3	1.00		1082	1082
Fill	51.1	1	1	1.00	-447	1529	1529

SKIP STATION RANGE = 628+50.01 to 630+30.74

630+25.75 EARTH

Excavation	137.3	0	0	1.00		1082	1082
Fill	128.7	0	0	1.00	-447	1529	1529

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 4 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

630+50.00 EARTH

Excavation	169.4	109	109	1.00		1191	1191
Fill	148.7	99	99	1.00	-437	1628	1628

631+00.00 EARTH

Excavation	196.6	339	339	1.00		1530	1530
Fill	163.9	289	289	1.00	-387	1917	1917

631+50.00 EARTH

Excavation	99.1	274	274	1.00		1804	1804
Fill	17.0	167	167	1.00	-280	2084	2084

632+00.00 EARTH

Excavation	135.5	217	217	1.00		2021	2021
Fill	0.0	16	16	1.00	-79	2100	2100

632+50.00 EARTH

Excavation	191.2	303	303	1.00		2324	2324
Fill	1.3	1	1	1.00	223	2101	2101

633+00.00 EARTH

Excavation	197.4	360	360	1.00		2684	2684
Fill	10.6	11	11	1.00	572	2112	2112

633+50.00 EARTH

Excavation	223.5	390	390	1.00		3074	3074
Fill	0.7	10	10	1.00	952	2122	2122

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 5 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

634+00.00 EARTH

Excavation	193.4	386	386	1.00		3460	3460
Fill	0.0	1	1	1.00	1337	2123	2123

634+10.00 EARTH

Excavation	181.4	69	69	1.00		3529	3529
Fill	0.0	0	0	1.00	1406	2123	2123

634+50.00 EARTH

Excavation	73.6	189	189	1.00		3718	3718
Fill	0.8	1	1	1.00	1594	2124	2124

634+65.00 EARTH

Excavation	33.1	30	30	1.00		3748	3748
Fill	0.0	0	0	1.00	1624	2124	2124

635+00.00 EARTH

Excavation	0.0	21	21	1.00		3769	3769
Fill	0.0	0	0	1.00	1645	2124	2124

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 6 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

G R A N D	S U M M A R Y	T O T A L S	
Material Name	Unadjusted	Adjusted	Mult
	Volumes	Volumes	Factor
	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	3769	3769	1.00
Fill	2124	2124	1.00

S P L I T	S U M M A R Y		T O T A L S		
Material Name	XS Quant	XS Quant	Add/Sub Quant	Add/Sub Quant	Mult
	Unadjusted	Adjusted	Unadjusted	Adjusted	Factor
	Volume	Volume	Volume	Volume	Factor
	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	3769	3769	0	0	1.00
Fill	2124	2124	0	0	1.00

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 7 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

B A L A N C E P O I N T S U M M A R Y

Material Name	Cumulative		Incremental		Mult Factor
	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	

 Station = 625+59.90

EARTH

Excavation	305	305	305	305	1.00
Fill	305	305	305	305	1.00

Station = 632+13.08

EARTH

Excavation	2100	2100	1795	1795	1.00
Fill	2100	2100	1795	1795	1.00

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 8 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

SR-6 Bridge Excavation

Material Name	End Areas	Unadjusted	Adjusted	Mult	Mass	Accum	Accum	
Station		Volumes	Volumes		Factor	Ordinate	Unadj Vol	Adj Vol
	(sq. ft.)	(cu. yd.)	(cu. yd.)				(cu. yd.)	(cu. yd.)

 628+49.25 EARTH

Excavation	570	0	0	1.00			0	0
Fill	28	0	0	1.00	0		0	0

628+50.00 EARTH

Excavation	569	16	16	1.00			16	16
Fill	91	2	2	1.00	14		2	2

628+55.00 EARTH

Excavation	562	105	105	1.00			121	121
Fill	100	18	18	1.00	101		20	20

628+60.00 EARTH

Excavation	557	104	104	1.00			225	225
Fill	78	16	16	1.00	189		36	36

628+65.00 EARTH

Excavation	511	99	99	1.00			324	324
Fill	82	15	15	1.00	273		51	51

628+70.00 EARTH

Excavation	370	82	82	1.00			406	406
Fill	52	12	12	1.00	343		63	63

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 9 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

628+75.00 EARTH

Excavation	388	70	70	1.00		476	476
Fill	30	8	8	1.00	405	71	71

628+80.00 EARTH

Excavation	376	71	71	1.00		547	547
Fill	13	4	4	1.00	472	75	75

628+85.00 EARTH

Excavation	167	50	50	1.00		597	597
Fill	26	4	4	1.00	518	79	79

628+90.00 EARTH

Excavation	43	19	19	1.00		616	616
Fill	8	3	3	1.00	534	82	82

628+95.00 EARTH

Excavation	0	4	4	1.00		620	620
Fill	0	1	1	1.00	537	83	83

629+70.00 EARTH

Excavation	10	14	14	1.00		634	634
Fill	7	10	10	1.00	541	93	93

629+75.00 EARTH

Excavation	66	7	7	1.00		641	641
Fill	9	1	1	1.00	547	94	94

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 10 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

629+80.00 EARTH

Excavation	181	23	23	1.00		664	664
Fill	6	1	1	1.00	569	95	95

629+85.00 EARTH

Excavation	496	63	63	1.00		727	727
Fill	33	4	4	1.00	628	99	99

629+90.00 EARTH

Excavation	794	119	119	1.00		846	846
Fill	30	6	6	1.00	741	105	105

629+95.00 EARTH

Excavation	798	147	147	1.00		993	993
Fill	42	7	7	1.00	881	112	112

630+00.00 EARTH

Excavation	751	143	143	1.00		1136	1136
Fill	37	7	7	1.00	1017	119	119

630+05.00 EARTH

Excavation	1033	165	165	1.00		1301	1301
Fill	52	8	8	1.00	1174	127	127

630+10.00 EARTH

Excavation	833	173	173	1.00		1474	1474
Fill	34	8	8	1.00	1339	135	135

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 11 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

630+15.00 EARTH

Excavation	595	132	132	1.00		1606	1606
Fill	34	6	6	1.00	1465	141	141

630+20.00 EARTH

Excavation	625	113	113	1.00		1719	1719
Fill	12	4	4	1.00	1574	145	145

630+25.00 EARTH

Excavation	639	117	117	1.00		1836	1836
Fill	23	3	3	1.00	1688	148	148

630+25.75 EARTH

Excavation	641	18	18	1.00		1854	1854
Fill	18	1	1	1.00	1705	149	149

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 12 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

G R A N D	S U M M A R Y	T O T A L S	
Material Name	Unadjusted	Adjusted	Mult
	Volumes	Volumes	Factor
	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	1854	1854	1.00
Fill	149	149	1.00

S P L I T	S U M M A R Y		T O T A L S		
Material Name	XS Quant	XS Quant	Add/Sub Quant	Add/Sub Quant	Mult
	Unadjusted	Adjusted	Unadjusted	Adjusted	Factor
	Volume	Volume	Volume	Volume	Factor
	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	1854	1854	0	0	1.00
Fill	149	149	0	0	1.00

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 13 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

SR-6 Offset Basin

Material Name	End Areas	Unadjusted	Adjusted	Mult	Mass	Accum	Accum	
Station		Volumes	Volumes		Factor	Ordinate	Unadj Vol	Adj Vol
	(sq. ft.)	(cu. yd.)	(cu. yd.)				(cu. yd.)	(cu. yd.)

1+14.00 EARTH

Excavation	27.2	0	0	1.00			0	0
Fill	0.0	0	0	1.00	0		0	0

1+20.00 EARTH

Excavation	138.7	18	18	1.00			18	18
Fill	0.0	0	0	1.00	18		0	0

1+26.00 EARTH

Excavation	388.4	59	59	1.00			77	77
Fill	0.0	0	0	1.00	77		0	0

ROCK

Excavation	55.4	6	6	1.00			6	6
Fill	0.0	0	0	1.00	77		0	0

Mass ordinate for ROCK = 6

1+30.00 EARTH

Excavation	405.8	59	59	1.00			136	136
Fill	0.0	0	0	1.00	136		0	0

ROCK

Excavation	109.4	12	12	1.00			18	18
Fill	0.0	0	0	1.00	136		0	0

Mass ordinate for ROCK = 18

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 14 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

1+34.00 EARTH

Excavation	441.6	63	63	1.00		199	199
Fill	0.0	0	0	1.00	199	0	0

ROCK

Excavation	174.8	21	21	1.00		39	39
Fill	0.0	0	0	1.00	199	0	0

Mass ordinate for ROCK = 39

1+40.00 EARTH

Excavation	486.5	103	103	1.00		302	302
Fill	0.0	0	0	1.00	302	0	0

ROCK

Excavation	200.5	42	42	1.00		81	81
Fill	0.0	0	0	1.00	302	0	0

Mass ordinate for ROCK = 81

1+50.00 EARTH

Excavation	447.2	173	173	1.00		475	475
Fill	0.0	0	0	1.00	475	0	0

ROCK

Excavation	248.7	83	83	1.00		164	164
Fill	0.0	0	0	1.00	475	0	0

Mass ordinate for ROCK = 164

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 15 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

1+60.00 EARTH

Excavation	414.1	160	160	1.00		635	635
Fill	0.0	0	0	1.00	635	0	0

ROCK

Excavation	295.4	101	101	1.00		265	265
Fill	0.0	0	0	1.00	635	0	0

Mass ordinate for ROCK = 265

1+70.00 EARTH

Excavation	393.1	149	149	1.00		784	784
Fill	0.0	0	0	1.00	784	0	0

ROCK

Excavation	343.7	118	118	1.00		383	383
Fill	0.0	0	0	1.00	784	0	0

Mass ordinate for ROCK = 383

1+80.00 EARTH

Excavation	381.3	143	143	1.00		927	927
Fill	0.0	0	0	1.00	927	0	0

ROCK

Excavation	392.8	136	136	1.00		519	519
Fill	0.0	0	0	1.00	927	0	0

Mass ordinate for ROCK = 519

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 16 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

1+90.00 EARTH

Excavation	440.7	152	152	1.00		1079	1079
Fill	0.0	0	0	1.00	1079	0	0

ROCK

Excavation	385.0	144	144	1.00		663	663
Fill	0.0	0	0	1.00	1079	0	0

Mass ordinate for ROCK = 663

2+00.00 EARTH

Excavation	498.5	174	174	1.00		1253	1253
Fill	0.0	0	0	1.00	1253	0	0

ROCK

Excavation	379.0	141	141	1.00		804	804
Fill	0.0	0	0	1.00	1253	0	0

Mass ordinate for ROCK = 804

2+10.00 EARTH

Excavation	537.9	192	192	1.00		1445	1445
Fill	0.0	0	0	1.00	1445	0	0

ROCK

Excavation	320.4	130	130	1.00		934	934
Fill	0.0	0	0	1.00	1445	0	0

Mass ordinate for ROCK = 934

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 17 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

2+12.00 EARTH

Excavation	537.3	40	40	1.00		1485	1485
Fill	0.0	0	0	1.00	1485	0	0

ROCK

Excavation	279.0	22	22	1.00		956	956
Fill	0.0	0	0	1.00	1485	0	0

Mass ordinate for ROCK = 956

2+20.00 EARTH

Excavation	505.3	154	154	1.00		1639	1639
Fill	0.0	0	0	1.00	1639	0	0

ROCK

Excavation	102.9	57	57	1.00		1013	1013
Fill	0.0	0	0	1.00	1639	0	0

Mass ordinate for ROCK = 1013

2+30.00 EARTH

Excavation	154.8	122	122	1.00		1761	1761
Fill	0.0	0	0	1.00	1761	0	0

ROCK

Excavation	0.0	19	19	1.00		1032	1032
Fill	0.0	0	0	1.00	1761	0	0

Mass ordinate for ROCK = 1032

2+32.00 EARTH

Excavation	80.4	9	9	1.00		1770	1770
Fill	0.0	0	0	1.00	1770	0	0

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 18 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

G R A N D S U M M A R Y T O T A L S

Material Name	Unadjusted	Adjusted	Mult
	Volumes	Volumes	Factor
	(cu. yd.)	(cu. yd.)	

EARTH

Excavation	1770	1770	1.00
Fill	0	0	1.00

ROCK

Excavation	1032	1032	1.00
Fill	0	0	1.00

S P L I T S U M M A R Y T O T A L S

Material Name	XS Quant	XS Quant	Add/Sub Quant	Add/Sub Quant	Mult
	Unadjusted	Adjusted	Unadjusted	Adjusted	Factor
	Volume	Volume	Volume	Volume	Factor
	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	

EARTH

Excavation	1770	1770	0	0	1.00
Fill	0	0	0	0	1.00

ROCK

Excavation	1032	1032	0	0	1.00
Fill	0	0	0	0	1.00

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 19 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

SR-6 Offset Basin Ditch

Station	Material Name	End Areas (sq. ft.)	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Mult Factor	Mass Ordinate	Accum Unadj Vol (cu. yd.)	Accum Adj Vol (cu. yd.)
---------	---------------	------------------------	------------------------------------	----------------------------------	----------------	------------------	---------------------------------	-------------------------------

 1+10.00 EARTH

Excavation	4.8	0	0	1.00		0	0
Fill	0.0	0	0	1.00	0	0	0

1+15.00 EARTH

Excavation	24.2	3	3	1.00		3	3
Fill	0.0	0	0	1.00	3	0	0

1+20.00 EARTH

Excavation	57.0	8	8	1.00		11	11
Fill	0.0	0	0	1.00	11	0	0

1+25.00 EARTH

Excavation	90.7	14	14	1.00		25	25
Fill	0.0	0	0	1.00	25	0	0

1+30.00 EARTH

Excavation	85.9	16	16	1.00		41	41
Fill	0.0	0	0	1.00	41	0	0

1+35.00 EARTH

Excavation	81.7	16	16	1.00		57	57
Fill	0.0	0	0	1.00	57	0	0

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 20 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

1+40.00 EARTH

Excavation	77.1	15	15	1.00		72	72
Fill	0.0	0	0	1.00	72	0	0

1+45.00 EARTH

Excavation	72.1	14	14	1.00		86	86
Fill	0.0	0	0	1.00	86	0	0

1+50.00 EARTH

Excavation	64.2	13	13	1.00		99	99
Fill	0.0	0	0	1.00	99	0	0

GRADING REPORT

COMPUTED BY: Jordan Del Sardo
 CHECKED BY: Jesse Head
 FEDERAL PROJECT NO: R-BR-NH-6(128)
 ROUTE NO. OR STREET: SR-6

SHEET 21 OF 21
 STATE NO: 83077-3220-94
 PIN: 124721.00
 COUNTY: Sumner

G R A N D	S U M M A R Y	T O T A L S	
Material Name	Unadjusted	Adjusted	Mult
	Volumes	Volumes	Factor
	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	99	99	1.00
Fill	0	0	1.00

S P L I T	S U M M A R Y		T O T A L S		
Material Name	XS Quant	XS Quant	Add/Sub Quant	Add/Sub Quant	Mult
	Unadjusted	Adjusted	Unadjusted	Adjusted	Factor
	Volume	Volume	Volume	Volume	Factor
	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	

 EARTH

Excavation	99	99	0	0	1.00
Fill	0	0	0	0	1.00