



SHEET NAME	SHEET NO.
SIGNATURE SHEET	ROADWAY-SIGN2
ROADWAY INDEX, STANDARD ROADWAY DRAWINGS AND	
STANDARD TRAFFIC DESIGN DRAWINGS	1A
ESTIMATED ROADWAY QUANTITIES	2

YEAR	PROJECT NO.	SHEET NO.
2026	NH-I-65-2(116)	ROADWAY-SIGN 2

REV. 06-17-26: ADDED SHEET.

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SIGNATURE
SHEET

ROADWAY INDEX

SHEET NAME	SHEET NO.
SIGNATURE SHEETS.....	ROADWAY-SIGN1
SIGNATURE SHEETS.....	ROADWAY-SIGN2
TITLE SHEET	1
ROADWAY INDEX, STANDARD ROADWAY DRAWINGS, AND	
STANDARD TRAFFIC DESIGN DRAWINGS	1A
ESTIMATED ROADWAY QUANTITIES	2
TYPICAL SECTIONS AND PAVEMENT SCHEDULE	2B
GENERAL NOTES.....	2C
SPECIAL NOTES.....	2D, 2D1, 2D2
ENVIRONMENTAL NOTES.....	2E, 2E1
TABULATED QUANTITIES	2F
TRAFFIC DETECTION LOOPS DETAIL.....	2G
PAVEMENT MARKING IMPROVEMENTS.....	2G1 – 2G4
UTILITY NOTES, AND UTILITY OWNERS.....	3
R.R. R.O.W. DETAILS	4
PAVEMENT EDGE DROP-OFF NOTES FOR TRAFFIC CONTROL	T1
NOTE: THE ALPHABETICAL LETTERS "I", "O" & "Q" ARE NOT USED IN THE NUMBERING OF SHEETS.	
NO UTILITY SHEETS ARE INCLUDED IN THIS SET OF PLANS.	
NO PROJECT COMMITMENTS ARE INCLUDED IN THIS SET OF PLANS.	

STANDARD ROADWAY DRAWINGS

DWG.	REV.	DESCRIPTION
10-100.00 STANDARD ROADWAY TITLE SHEET, ABBREVIATIONS, AND LEGENDS		
RD-A-1	02-20-20	STANDARD ABBREVIATIONS A THROUGH L
RD-A-2		STANDARD ABBREVIATIONS M THROUGH Z
RD-L-1	01-30-26	STANDARD LEGEND
RD-L-1A		STANDARD LEGEND

STANDARD TRAFFIC DESIGN DRAWINGS

DWG.	REV.	DESCRIPTION
10-201.00 SIGNALS		
T-SG-2	12-18-25	LOOP LEAD-INS, CONDUIT AND PULL BOXES
T-SG-3	12-18-25	INDUCTIVE LOOPS DETECTION DETAILS
T-SG-3A	12-18-25	INDUCTIVE LOOP DETECTION DETAILS AND NOTES
10-204.00 DESIGN - TRAFFIC CONTROL		
T-M-3	01-24-25	MARKING STANDARDS FOR TRAFFIC ISLANDS, PAVED SHOULDERS AND MEDIANS FOR CONVENTIONAL ROADS
T-M-4	01-24-25	STANDARD INTERSECTION PAVEMENT MARKINGS
T-M-5	01-24-25	MARKING DETAIL FOR FREEWAYS
T-M-6	01-24-25	MARKING DETAIL FOR EXPRESSWAY AND FREEWAY INTERCHANGES
T-M-7	01-24-25	GORE MARKING DETAILS FOR EXPRESSWAY & FREEWAY INTERCHANGES
T-M-9	01-24-25	PAVEMENT MARKING AND SIGNING DETAILS FOR RAMP INTERSECTIONS
T-M-9A	01-24-25	PAVEMENT MARKING AND SIGNING DETAILS FOR RAMP INTERSECTIONS
T-M-15	01-24-25	ASPHALT SHOULDER RUMBLE STRIP INSTALLATION DETAILS FOR INTERSTATE AND ACCESS CONTROLLED ROUTES
T-WZ-10	03-26-25	ADVANCE ROAD WORK SIGNING ON HIGHWAYS AND FREEWAYS
T-WZ-11	03-26-25	ONE LANE CLOSURE DETAIL ON DIVIDED HIGHWAYS
T-WZ-13	03-26-25	TWO-OUTSIDE LANE CLOSURE FOR EXPRESSWAY AND FREEWAYS
T-WZ-60	03-26-25	FREEWAY RESURFACING SIGNING LAYOUT
T-WZ-63	03-26-25	WORK ZONE IN THE VICINITY OF AN ENTRANCE RAMP
T-WZ-64	03-26-25	WORK ZONE IN THE VICINITY OF AN EXIT
T-WZ-FAB1	03-26-25	FLASHING YELLOW ARROW BOARD

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2026	NH-L65-2(116)	1A

REV. 06-17-26: ADDED ROADWAY-SIGN2 TO INDEX.

SEALED BY



6/17/2026

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ROADWAY INDEX,
STANDARD ROADWAY
DRAWINGS AND
STANDARD TRAFFIC
DESIGN DRAWINGS

ESTIMATED ROADWAY QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY 94I065-F8-005
(1)(2)	208-01.05 BROOMING & DEGRASSING SHOULDERS	L.M.	7.8
(1)	303-01 MINERAL AGGREGATE, TYPE A BASE, GRADING D	TON	1027
	403-01 BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	139
	411-03.10 ACS MIX (PG76-22) GRADING D	TON	20843
(3)	411-01.51 VOID REDUCING ASPHALT MEMBRANE (VRAM) HALF-WIDTH	L.F.	247316
	411-12.01 SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	L.M.	14.6
	415-01.01 COLD PLANING BITUMINOUS PAVEMENT	TON	20647
(4)	611-09.01 ADJUSTMENT OF EXISTING CATCHBASIN	EACH	183
(5)	712-01 TRAFFIC CONTROL	LS	1
	712-04.01 FLEXIBLE DRUMS (CHANNELIZING)	EACH	576
	712-05.03 WARNING LIGHTS (TYPE C)	EACH	64
(6)	712-06 SIGNS (CONSTRUCTION)	S.F.	2098
(7)	712-06.16 SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	EACH	5
	712-07.03 TEMPORARY BARRICADES (TYPE III)	L.F.	24
	712-08.03 ARROW BOARD (TYPE C)	EACH	6
	712-08.08 SPEED FEEDBACK SIGN ASSEMBLY	EACH	2
	712-08.09 DIGITAL SPEED LIMIT SIGN ASSEMBLY	EACH	10
	712-08.12 QUEUE PROTECTION TRUCK	DAY	120
	713-16.01 CHANGEABLE MESSAGE SIGN UNIT	EACH	4
	716-01.23 SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	EACH	2171
(8)	716-01.30 REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	EACH	2171
(9)(10)	716-02.04 PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	S.Y.	36
(9)(10)(11)	716-02.05 PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	52
(9)(10)	716-02.06 PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH	12
(9)(12)	716-02.07 PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	L.F.	403
(9)(10)	716-02.08 PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	L.F.	736
(9)(10)	716-02.12 PLASTIC PAVEMENT MARKING (8IN LINE)	L.M.	0.4
(9)(10)	716-04.01 PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	EACH	6
(9)(10)	716-04.05 PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	EACH	4
(9)(12)	716-04.09 PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	EACH	32
(9)(10)	716-04.12 PLASTIC PAVEMENT MARKING (YIELD LINE)	S.F.	45
(13)	716-05.02 PAINTED PAVEMENT MARKING (8" BARRIER LINE)	L.F.	1970
(13)	716-05.20 PAINTED PAVEMENT MARKING (6" LINE)	L.M.	26.3
(14)	716-08.04 REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	S.Y.	36
(14)	716-08.05 REMOVAL OF PAVEMENT MARKING (STOP LINE)	L.F.	52
(14)	716-08.06 REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	EACH	12
(14)	716-08.07 REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	EACH	6
(14)	716-08.09 REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	L.F.	736
(14)	716-08.19 REMOVAL OF PAVEMENT MARKING (YIELD LINE)	S.F.	45
(15)	716-08.20 REMOVAL OF PAVEMENT MARKING (LINE)	L.M.	2.2
(14)	716-08.23 REMOVAL OF PAVEMENT MARKING (STRAIGHT ARROW)	EACH	4
(16)	716-09.83 CONTRAST PAVEMENT MARKING 6"	L.F.	600
(17)	716-09.89 CONTRAST PAVEMENT MARKING 12"	L.F.	150
(18)	716-09.97 CONTRAST PAVEMENT SHADOW MARKING 6"	L.F.	188
(19)	716-12.02 ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	L.M.	22
(12)	716-12.03 ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	L.F.	1970
(12)(20)	716-12.05 ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	L.F.	4431
(12)	716-12.09 ENHANCED FLAT LINE THERMO (12IN LINE)	L.F.	20486
	717-01 MOBILIZATION	LS	1
(21)	730-03.20 INSTALL PULL BOX (TYPE A)	EACH	2
(21)	730-12.02 CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	L.F.	40
(21)	730-14.02 SAW SLOT	L.F.	750
(21)	730-14.03 LOOP WIRE	L.F.	3000

THERE IS NO GUARDRAIL WORK ON THIS PROJECT

FOOTNOTES	
(1)	TO BE USED AS DIRECTED BY THE ENGINEER.
(2)	INCLUDES THE COST OF REMOVING DEBRIS AND SWEEPING SHOULDERS PRIOR TO WORK. SEE SHEET 2C, PAVEMENT MARKINGS, FINAL PAVEMENT MARKING NOTE 6 AND SHEET 2D, PAVEMENT, RESURFACING, NOTE 2.
(3)	THIS WILL BE USED ONLY AT THE LONGITUDINAL JOINT BETWEEN TRAVEL LANES AND WILL BE PLACED IN 9" WIDE STRIPS ON BOTH SIDES OF THE LONGTUDINAL JOINT AS EACH LANE IS PAVED.
(4)	ITEM INCLUDES 11 CATCH BASINS AND 172 AREA DRAINS. ITEM WILL BE ADJUSTED AS DIRECTED BY THE ENGINEER.
(5)	THE CONTRACTOR SHALL COMPLY WITH SECTION 712 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION REGARDING TEMPORARY TRAFFIC CONTROL AND THE CURRENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
(6)	THE CONTRACTOR IS RESPONSIBLE FOR THE STAKING OF CONSTRUCTION SIGNS. IN THE EVENT THAT A CONSTRUCTION AND/OR REGULATORY SIGN IS TEMPORARILY DESIGNATED NOT IN USE DURING THE CONSTRUCTION PHASE OF A PROJECT, THE CONTRACTOR SHALL CHOOSE A SIGN COVERING APPROVED BY THE ENGINEER. TEMPORARY SIGN COVERINGS SHALL NOT BE PAID FOR DIRECTLY BUT SHALL BE INCLUDED IN THE PRICE BID FOR ITEM NO. 712-06 SIGNS (CONSTRUCTION).
(7)	ITEM TO BE USED ONLY WHEN A REDUCED SPEED LIMIT IS ESTABLISHED WITHIN THE PROJECT CONSTRUCTION WORK ZONE LIMITS. ITEM INCLUDES SIGN FACE, SUPPORTS, AND TWO TYPE "B" FLASHERS PER THE STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TURNING ON THE TYPE "B" FLASHERS WHEN WORKERS ARE IN THE CONSTRUCTION WORK ZONE AND TURNING THEM OFF WHEN WORKERS ARE NO LONGER IN THE CONSTRUCTION WORK ZONE.
(8)	CONTRACTOR SHALL REMOVE EXISTING SPM BY A METHOD THAT DOES NOT DAMAGE THE EXISTING ASPHALT. IF DAMAGE OCCURS DURING REMOVAL, THE CONTRACTOR SHALL MAKE REPAIRS AT THEIR OWN EXPENSE BEFORE PAVING.
(9)	THE CONTRACTOR MAY ELECT TO SUBSTITUTE PREFORMED PLASTIC FOR THERMOPLASTIC. PREFORMED PLASTIC SHALL BE PAID FOR AT THE SAME UNIT PRICE AS BID FOR THERMOPLASTIC.
(10)	ITEM TO BE USED AS PERMANENT MARKING ON RAMPS ONLY.
(11)	ALL STOP BARS ON SIDE STREETS WILL BE RETRACED AS DIRECTED BY THE ENGINEER.
(12)	ITEM TO BE USED AS PERMANENT MARKING ONLY.
(13)	ITEM TO BE USED AS TEMPORARY PAVEMENT MARKING ONLY.
(14)	ITEM TO BE USED ON RAMPS ONLY.
(15)	INCLUDES 2 L.M. FOR REMOVAL OF PAVEMENT MARKINGS ON RAMPS.
(16)	FOR PERMANENT EDGE LINE MARKING ON CONCRETE SURFACES.
(17)	FOR PERMANENT MARKING ON CONCRETE SURFACES.
(18)	FOR PERMANENT LANE LINE MARKING ON CONCRETE SURFACES. ITEM COST INCLUDES 10 LF WHITE MARKING AND 10 LF BLACK MARKING.
(19)	INCLUDES 1.6 L.M. FOR PERMANENT MARKING ON RAMPS.
(20)	SEE SHEETS 2G1 - 2G4, PAVEMENT MARKING IMPROVEMENTS, FOR LOCATIONS.
(21)	ITEM TO BE USED FOR REPLACEMENT OF LOOP DETECTION AT L.M. 17.56.

TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF	2026	NH-I-65-2(116)	2

REV. 06-17-26: REVISED QUANTITY FOR PAY ITEM 411-01.51.

SEALED BY



6/17/2026

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

ESTIMATED
ROADWAY
QUANTITIES