TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2015	STP-NH/HSIP-4(10)	4A

SPECIAL NOTES

SURFACE IS TO BE CROWNED AS DIRECTED BY THE ENGINEER.

ALL SIGNS WHICH INTERFERE WITH CONSTRUCTION WILL BE RELOCATED OUTSIDE LIMITS OF CONSTRUCTION BY THE CONTRACTOR. UPON COMPLETION OF CONSTRUCTION, THE CONTRACTOR WILL RESTORE THE SIGNS TO ORIGINAL LOCATION. COST TO BE INCLUDED IN ITEM NO. 712-06.

IF THE CONTRACTOR ELECTS TO UTILIZE SIGN POST ANCHORS (STUBS) FOR SIGN ERECTION. THESE SHALL BE REMOVED WHEN THE SIGNS ARE REMOVED TO AVOID FUTURE DAMAGE TO MOWERS OR OTHER MACHINERY.

UNDER THE DIRECTION OF THE ENGINEER, THE CONTRACTOR MAY BE REQUIRED TO APPLY PAINTED MARKINGS IN THE PAVEMENT AREAS NOT SPECIFICALLY DETAILED IN THE PLANS. PAYMENT WILL BE MADE AT THE UNIT PRICE BID FOR ITEM NO. 716-05.01.

UNDER THE DIRECTION OF THE ENGINEER, THE CONTRACTOR MAY BE REQUIRED TO APPLY PLASTIC MARKINGS IN THE PAVEMENT AREAS NOT SPECIFICALLY DETAILED IN THE PLANS. PAYMENT WILL BE MADE AT THE UNIT PRICE BID FOR ITEM NO. 716-13.01.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ANY SIGNS AND MAILBOXES DURING THE OPERATION, ANY SIGNS OR MAILBOXES DAMAGED AS A RESULT OF THE OPERATIONS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

THE CONTRACTOR SHALL PROPERLY ADJUST ALL MANHOLES, ALL UTILITY VALVE COVERS AND LIKE STRUCTURES TO THE FINISHED GRADE OF THE PAVEMENT. IF EXTENSION RINGS ARE USED. THEY WILL BE SPOT WELDED A MINIMUM OF FIVE TIMES. COST OF ADJUSTMENT IS TO BE INCLUDED IN ITEM 411-03.10, ADJUSTMENT IS TO BE MADE PRIOR TO THE LAYING OF ITEM 411-03.10.

TAPER AROUND ALL CATCH BASINS.

MATERIAL TRANSFER DEVICE SHALL BE USED FOR "D" MIX.

DRIVEWAYS AND FIELD ENTRANCES WILL BE PAVED THE SHOULDER WIDTH PLUS UP TO THREE FEET LIP OFF.

THE CONTRACTOR SHALL KEEP TWO TRAFFIC LANES, ONE IN EACH DIRECTION, OPEN TO TRAFFIC DURING NON-WORK HOURS / OR NON-WORK DAYS.

THE CONSTRUCTION OFFICE SHOULD CONTACT THE CITY ENGINEER FOR ADVICE ON LOCATING THE ADVANCE DETECTION LOOPS

THE CONTRACTOR SHALL NOT DISTURB EXISTING LOOP DETECTORS WHILE BREAKING OUT AND REMOVING EXISTING PAVEMENTS.

THE BITUMINOUS MATERIAL DESIGNATED TO RESTORE THE COLD PLANING AREA WILL BE PLACED WITHIN 48 HOURS OF THE COMMENCEMENT OF COLD PLANING OPERATIONS. COLD PLANING OPERATIONS WILL BE LIMITED TO AN AREA EQUAL TO THAT WHICH CAN BE COVERED WITH BITUMINOUS MATERIAL WITHIN THE TIME LIMITS SPECIFIED. EVEN IF COLD PLANING OPERATIONS MUST BE SUSPENDED UNTIL PAVING CATCHES UP.

THE CONTRACTOR WILL BE REQUIRED TO PAVE IMMEDIATELY BEHIND COLD PLANING OPERATIONS TO ENSURE THAT THE MILLED SURFACE WILL BE COVERED WITH BITUMINOUS/CEMENT THE SAME WORK DAY, AND ABIDE BY DROP-OFF POLICY.

THE MILLING AND PAVING OF THE ROADWAY SHALL BE PERFORMED BETWEEN THE HOURS OF 6:00 P.M. AND 6:00 A.M. DURING WEEKDAYS. THE CONTRACTOR SHALL MAINTAIN ALL LANES OF TRAFFIC IN EACH DIRECTION BETWEEN 6:00 A.M. AND 6:00 P.M. MONDAY THROUGH FRIDAY.

BETWEEN L.M. 7.48 AND L.M. 9.87:
THE CONTRACTOR SHALL PROPERLY ADJUST ALL MANHOLES AND CATCH BASINS TO THE FINISHED GRADE OF THE PAVEMENT. EXTENSION RINGS SHALL BE REMOVED FROM EXISTING CATCH BASINS TO LOWER GRATE TO PAVEMENT ELEVATION. ADJUSTMENTS ARE TO BE MADE PRIOR TO LAYING OF ITEM 411-03. PAYMENT FOR THESE ADJUSTMENT WILL BE MADE AT THE UNIT PRICE BID FOR ITEMS 611-09.01 RESPECTIVELY.

ANY WORK REQUIRING LANE CLOSURES IN EXCESS OF 30 MINUTES (EXCEPT EMERGENCY GUARDRAIL REPAIR) SHALL BE ACCOMPLISHED DURING THE HOURS OF 8:00 P.M. AND 6:00 A.M. THIS INCLUDES THE SETUP AND REMOVAL OF ALL TRAFFIC CONTROL MEASURES.

THIS IS A NIGHT JOB ALL LANES OPEN TO TRAFFIC FROM 7:00 P.M. TO 6:00 A.M. MONDAY THRU FRIDAY.

THIS IS A NIGHT JOB ALL LANES OPEN TO TRAFFIC FROM 6:00 A.M. TO 7:00 P.M. SUNDAY THRU THURSDAY.

THE CONTRACTOR SHALL COMPLY WITH SECTION 712 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION REGARDING TEMPORARY TRAFFIC CONTROL AND THE CURRENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

PAVEMENT EDGE DROP-OFF TRAFFIC CONTROL

A. DIFFERENCE IN ELEVATION BETWEEN ADJACENT TRAFFIC LANES OR TRAFFIC LANE AND SHOULDER WHERE THE TRAFFIC LANE IS BEING USED BY TRAFFIC. CAUSED BY BASE, PAVING OR RESURFACING:

1. DIFFERENCE IN ELEVATION BETWEEN ADJACENT ROADWAY ELEMENTS GREATER THAN 0.75 INCH AND NOT EXCEEDING 2 INCHES.

   a. WARNING SIGNS, UNEVEN PAVEMENT (W8-11) AND/OR SHOULDER DROP-OFF (W8-9A), SHALL BE PLACED IN ADVANCE OF AND THROUGHOUT THE EXPOSED AREA. MAXIMUM SPACING BETWEEN SIGNS SHALL BE 2,000 FEET WITH A MINIMUM OF 2 SIGNS PER EXPOSED AREA. WHERE UNEVEN PAVEMENT IS ENCOUNTERED, SIGNS SHALL BE PLACED ON EACH SIDE OF THE ROADWAY.

   b. DIFFERENCES IN ELEVATION BETWEEN ADJACENT TRAFFIC LANES BEING UTILIZED BY TRAFFIC CAUSED BY ADDED PAVEMENT SHALL BE ELIMINATED WITHIN THREE WORKDAYS.

   c. DIFFERENCES IN ELEVATION BETWEEN ADJACENT TRAFFIC LANES BEING UTILIZED BY TRAFFIC CAUSED BY COLD PLANING SHALL BE ELIMINATED WITHIN THREE WORKDAYS.

   d. WHEN THE DIFFERENCE IN ELEVATION IS BETWEEN THE TRAFFIC LANE BEING UTILIZED BY TRAFFIC AND SHOULDER, THE DIFFERENCE IN ELEVATION SHALL BE ELIMINATED WITHIN SEVEN WORKDAYS AFTER THE CONDITION IS CREATED.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SPECIAL NOTES

3-MAR-2015 14:06
\\j04wf01.tdot.state.tn.us\04SHARED\Design\DESIGN\DESIGNKG\RESURFACING PROJECTS\Shelby\SR-4\LM7-48LM9-87\79004LM7-48 GN&SN.dgn