TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	HSIP-I-24-1(105)	6A

GUIDANCE

1. Install enhanced flatline thermoplastic 6-inch single solid white edgeline, 6-inch single solid yellow edgeline, and 6-inch single broken white skip lines along eastbound Interstate 24 to match existing, from L.M. 15.28 to L.M. 15.49.
2. Install 24-inch diagonal chevron channelization plastic pavement marking spaced at twenty (20) feet surrounded by enhanced flatline thermoplastic 8-inch single solid white edgelines, along the westbound Interstate 24 exit ramp gore to Shelby Avenue to match existing.
3. Replace thirty-seven (37) Red-White Bi-Directional Snowplowable Reflective Markers spaced at 20 feet along the diagonal chevron channelization pavement markings along the westbound Interstate 24 exit ramp gore to Shelby Avenue to match existing.
4. Replace forty-five (45) Red-White Bi-Directional Snowplowable Reflective Markers spaced at 80 feet along the mainline of eastbound Interstate 24 from L.M. 15.28 to L.M. 15.49.
5. Install enhanced flatline thermoplastic 12-inch single solid white line along the westbound Interstate 24 exit only lane for 700 feet, beginning approximately 700 feet in advance of the Shelby Avenue exit ramp.
6. Replace thirty-four (34) Red-White Bi-Directional Snowplowable Reflective Markers spaced at 40 feet along the eastbound Interstate 24 exit only lane, beginning approximately 700 feet in advance of the Shelby Avenue exit ramp.
7. Replace thirty (30) Red-White Bi-Directional Snowplowable Reflective Markers spaced at 80 feet along the mainline of westbound Interstate 24 from L.M. 15.28 to L.M. 15.49.
8. Remove and replace the two (2) existing Exit Pavement Arrows along the westbound Interstate 24 exit ramp to Shelby Avenue.
9. Install enhanced flatline thermoplastic 6-inch single solid white edgeline, 6-inch single solid yellow edgeline, and 6-inch single broken white skip lines along westbound Interstate 24 to match existing, from L.M. 15.28 to L.M. 15.49.
10. Install enhanced flatline thermoplastic 12-inch wide single dotted white line with three (3) foot lines and nine (9) foot spacing along the westbound deceleration lane for approximately 115 feet beginning at the westbound Interstate 24 exit ramp to Shelby Avenue.
11. Install two (2) Red-White Bi-Directional Snowplowable Reflective Markers spaced at 60 feet along the exit-only lane from westbound Interstate 24 to Shelby Avenue.
12. Install a new "Right Lane Must Exit 2nd - 4th Ave. 1 Mile" guide sign along the existing diagrammatic guide signs above the rightmost lane along eastbound interstate 24.

CONSTRUCTABILITY FIELD REVIEW

SEALED BY

ROAD SAFETY AUDIT REVIEW

INTERSTATE 24
L.M. 14.67 TO L.M. 16.06
DAVIDSON COUNTY

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

GUIDANCE

INTERSTATE 24

0-JAN-2014 14:22
\\JJ03WF01.tdot.state.tn.us\03Shared\SURVEY\DESIGN\PIN 118363.00 Davidson I-24 RSAR\Cadd files from Planning\dgn\006A I-24 Guide 06A.dgn