TYPE	YEAR	PROJECT NO.	SHEET NO.
RESURF.	2014	HSIP-24-1(105)	2E

TRAFFIC CONTROL QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	M.U.T.C.D. NO.
712-01	TRAFFIC CONTROL	LS	0.5	
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	100	
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	EACH	3	TN-44
712-08.03	ARROW BOARD (TYPE C)	EACH	6	
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	EACH	6	
717-01	MOBILIZATION	LS	0.5	

SIGNS CONSTRUCTION 712-06

	QUANTITY	M.U.T.C.D. NO.	DESCRIPTION	SIZE	712-06 S.F.
	4	G20-1	ROAD WORK NEXT 1.5 MILES	48 x 24	32
1	2	M4-9R	EXIT SIGN W/ ARROW	30 x 24	10
1	5	R1-2	YIELD SIGN	36 x 36 x 36	135
	4	G20-2	END ROAD WORK	48 x 24	32
	4	W20-1	ROAD WORK 1 MILE	48 x 48	64
	4	W20-5R	RIGHT LANE CLOSED ½ MILE	48 x 48	64
	4	W20-5L	LEFT LANE CLOSED ½ MILE	48 x 48	64
	7	W20-1	ROAD WORK AHEAD	48 x 48	112
	7	W21-1	GROOVED PAVEMENT - PORTABLE	48 x 48	112
	4	W4-2R	RIGHT LANE ENDS SYMBOL	48 x 48	64
	4	W4-2L	LEFT LANE ENDS SYMBOL	48 x 48	64
	2	W20-7a	FLAGGER SYMBOL - PORTABLE	48 x 48	32
	2	W16-2	SUPPLEMENTAL PLATE - PORTABLE	30 x 24	10
	6	W8-9a	SHOULDER DROP-OFF - PORTABLE	48 x 48	96
	6	W8-11	UNEVEN LANES - PORTABLE	48 x 48	96
			TOTAL S.F.		**987**

OTHER SIGNS, AS DIRECTED BY THE ENGINEER MAY BE REQUIRED DURING VARIOUS PHASES OF CONSTRUCTION AND WILL BE MEASURED AND PAID FOR AT THE UNIT BID PRICE. SEE CURRENT M.U.T.C.D. FOR STANDARDS AND TYPICAL APPLICATIONS.

1 TO BE USED FOR EXIT AND ENTRANCE TO I-24.

CONSTRUCTABILITY FIELD REVIEW

SEALED BY

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL QUANTITIES AND NOTES

10-JAN-2014 14:22
\\JU03WF01.tdot.state.tn.us\03Shared\SURVEY\DESIGN\PIN 118363.00 Davidson I-24 RSAR\Cadd files from Planning\dgn\002E TRAFFIC CONTROL QUANTITIES AND NOTES.dgn